

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
SN 054-0057, 054-0058	
STAGE 1	
NB SKIP DASH	
STA 553+35.00 TO STA 563+35.00	104.17
NB OUTSIDE EDGE LINE	
STA 571+54.00 TO STA 581+64.00	420.83
SB OUTSIDE EDGE LINE	
STA 572+04.50 TO STA 582+14.00	420.63
SB SKIP DASH	
STA 587+14.00 TO STA 597+14.00	104.17
STAGE 2	
NB MEDIAN EDGE LINE	
STA 572+80.00 TO STA 574+70.23	79.26
STA 578+98.07 TO STA 580+38.00	58.30
SB MEDIAN EDGE LINE	
STA 573+30.50 TO STA 574+70.23	58.22
STA 578+98.07 TO STA 580+88.00	79.14
FINAL PHASE	
NB OUTSIDE EDGE LINE	
STA 553+35.00 TO STA 571+54.00	757.92
NB SKIP DASH	
STA 563+35.00 TO STA 574+70.23	120.83
STA 578+98.07 TO STA 581+64.36	29.17
NB MEDIAN EDGE LINE	
STA 553+35.00 TO STA 570+80.50	727.29
STA 580+38.00 TO STA 581+64.36	52.65
SB OUTSIDE EDGE LINE	
STA 582+14.00 TO STA 597+14.00	625.00
SB SKIP DASH	
STA 572+04.50 TO STA 574+70.23	29.17
STA 578+98.07 TO STA 587+14.00	87.50
SB MEDIAN EDGE LINE	
STA 572+04.50 TO STA 573+30.50	52.50
STA 580+88.00 TO STA 597+14.00	677.50
SN 054-0060, 054-0061	
STAGE 1	
NB SKIP DASH	
STA 677+08.20 TO STA 687+08.20	104.17
NB OUTSIDE EDGE LINE	
STA 692+08.20 TO STA 706+32.00	593.25
SB OUTSIDE EDGE LINE	
STA 693+29.00 TO STA 708+82.40	647.25
SB SKIP DASH	
STA 713+00.00 TO STA 723+00.00	104.17
STAGE 2	
NB SKIP DASH	
STA 687+08.20 TO STA 687+57.00	8.33
NB MEDIAN EDGE LINE	
STA 692+56.00 TO STA 705+83.85	553.27
SB MEDIAN EDGE LINE	
STA 694+27.25 TO STA 707+54.75	553.13
SB SKIP DASH	
STA 712+50.00 TO STA 713+00.00	8.33

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
FINAL PHASE	
NB OUTSIDE EDGE LINE	
STA 677+08.20 TO STA 692+08.20	625.00
NB SKIP DASH	
STA 687+57.00 TO STA 695+51.35	83.33
STA 703+43.48 TO STA 706+32.00	33.33
NB MEDIAN EDGE LINE	
STA 677+08.20 TO STA 692+56.00	644.92
STA 703+83.85 TO STA 706+32.00	103.40
SB OUTSIDE EDGE LINE	
STA 703+82.40 TO STA 723+00.00	799.00
SB SKIP DASH	
STA 694+27.25 TO STA 696+52.85	25.00
STA 704+58.10 TO STA 712+50.00	83.33
SB MEDIAN EDGE LINE	
STA 707+54.75 TO STA 723+00.00	643.85
SN 054-0063, 054-0064	
STAGE 1	
NB SKIP DASH	
STA 261+48.40 TO STA 271+48.40	104.17
NB OUTSIDE EDGE LINE	
STA 276+48.40 TO STA 288+20.40	488.33
SB OUTSIDE EDGE LINE	
STA 276+58.26 TO STA 288+30.26	488.33
SB SKIP DASH	
STA 293+30.26 TO STA 303+30.26	104.17
STAGE 2	
NB SKIP DASH	
STA 271+48.40 TO STA 272+74.75	16.67
NB MEDIAN EDGE LINE	
STA 277+74.40 TO STA 286+94.38	383.33
SB MEDIAN EDGE LINE	
STA 277+84.26 TO STA 287+04.26	383.33
SB SKIP DASH	
STA 292+04.00 TO STA 293+30.26	16.67
FINAL PHASE	
NB OUTSIDE EDGE LINE	
STA 261+48.39 TO STA 276+48.40	625.00
NB SKIP DASH	
STA 272+74.75 TO STA 279+59.76	75.00
STA 285+64.16 TO STA 288+20.38	29.17
NB MEDIAN EDGE LINE	
STA 261+48.39 TO STA 277+74.40	677.50
STA 286+94.38 TO STA 288+20.38	52.50
SB OUTSIDE EDGE LINE	
STA 288+30.26 TO STA 303+30.27	625.00
SB SKIP DASH	
STA 276+58.26 TO STA 279+04.50	29.17
STA 285+18.90 TO STA 292+04.00	75.00
SB MEDIAN EDGE LINE	
STA 276+58.26 TO STA 277+84.26	52.50
STA 287+04.26 TO STA 303+30.27	677.50

CONTINUES NEXT COLUMN

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
SN 054-0065, 054-0066, 054-0067, 054-0068	
STAGE 1	
NB SKIP DASH	
STA 429+75.00 TO STA 439+75.00	104.17
NB OUTSIDE EDGE LINE	
STA 449+75.00 TO STA 479+46.45	1,238.10
NB MEDIAN EDGE LINE	
STA 449+89.30 TO STA 451+98.64	87.22
STA 478+96.50 TO STA 482+08.12	129.84
SB MEDIAN EDGE LINE	
STA 443+36.78 TO STA 446+00.00	109.68
STA 484+52.78 TO STA 487+61.92	128.81
SB SKIP DASH	
STA 497+62.00 TO STA 507+62.00	104.17
STAGE 2	
NB SKIP DASH	
STA 423+27.15 TO STA 429+75.00	70.83
NB MEDIAN EDGE LINE	
STA 443+27.15 TO STA 446+36.32	128.82
STA 482+08.12 TO STA 482+88.90	
SB MEDIAN EDGE LINE	
STA 448+91.90 TO STA 452+00.00	128.37
STA 472+00.00 TO STA 476+47.88	186.62
SB OUTSIDE EDGE LINE	
STA 447+25.53 TO STA 455+07.65	325.88
STA 459+09.46 TO STA 467+96.99	369.80
STA 472+44.17 TO STA 475+30.79	119.43
SB SKIP DASH	
STA 487+00.00 TO STA 497+00.00	104.17
FINAL PHASE	
NB OUTSIDE EDGE LINE	
STA 423+27.15 TO STA 449+75.00	1,103.27
STA 479+46.45 TO STA 485+00.00	230.65
NB SKIP DASH	
STA 439+75.00 TO STA 455+00.31	162.50
STA 458+99.38 TO STA 468+33.64	100.00
STA 472+73.07 TO STA 485+00.00	129.17
NB MEDIAN EDGE LINE	
STA 423+27.15 TO STA 443+27.15	833.33
STA 446+36.32 TO STA 449+89.30	147.08
STA 451+98.64 TO STA 455+00.31	125.70
STA 458+99.38 TO STA 468+33.64	389.28
STA 472+73.07 TO STA 478+96.50	259.76
SB OUTSIDE EDGE LINE	
STA 443+36.78 TO STA 447+25.53	161.98
STA 475+30.78 TO STA 485+00.00	403.84
SB SKIP DASH	
STA 443+36.78 TO STA 455+07.65	125.00
STA 459+09.46 TO STA 467+96.99	95.83
STA 472+44.17 TO STA 487+00.00	154.17
SB MEDIAN EDGE LINE	
STA 446+00.00 TO STA 448+91.90	121.63
STA 452+00.00 TO STA 455+07.00	127.92
STA 459+09.46 TO STA 467+96.99	369.80
STA 476+47.90 TO STA 485+00.00	355.04

CONTINUES NEXT COLUMN

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
SN 054-0069	
STAGE 1	
WB SOLID LANE LINE	
STA 1044+00.00 TO STA 1045+73.00	72.08
WB MEDIAN EDGE LINE	
STA 1045+61.88 TO STA 1046+40.00	32.55
STA 1054+43.00 TO STA 1056+26.84	76.60
EB MEDIAN EDGE LINE	
STA 1046+07.00 TO STA 1047+89.66	76.11
STA 1054+02.00 TO STA 1056+26.00	93.33
EB SOLID LANE LINE	
STA 1054+26.00 TO STA 1055+98.00	71.67
STAGE 2	
WB MEDIAN EDGE LINE	
STA 1043+87.00 TO STA 1046+02.00	89.58
STA 1052+10.00 TO STA 1056+10.00	166.67
EB MEDIAN EDGE LINE	
STA 1043+76.00 TO STA 1045+57.00	75.42
STA 1053+56.00 TO STA 1056+10.00	105.83
TOTAL	
	24,592.35

CONTINUES NEXT COLUMN



JOB = 2236.10
 FILE NAME = D672E11-sht-Schedules.dgn
 PLOT SCALE = 1/8333 "/>

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 1/4/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 15 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011-1	LOGAN	429	58
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72E11	