

PAVING SCHEDULE (Cont' d)			LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE WEDGE SHOULDER, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL (BUTT-JOINT)	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	LEVELING BINDER (MACHINE METHOD), N70	LEVELING BINDER (MACHINE METHOD), N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	INCIDENTAL HOT-MIX ASPHALT SURFACING	HOT-MIX ASPHALT SHOULDERS, 8'
STATION	TO	STATION	FEET	FEET	FEET	SQ YD	UNIT	TON	GALLON	TON	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON	TON
296+20.10	TO	296+55.10	35.0	24.0	6.0	93.3	0.7	2.0	9.3	0.2	0.0	0.0	93.3	3.9	0.0	8.7	0.0		0.0
296+55.10	TO	309+15.41	1,260.3	24.0	6.0	3,360.8	24.8	69.5	336.1	6.7	0.0	0.0	3360.8	141.2	0.0	311.7	0.0	3.2	0.0
309+15.41	TO	309+50.41	35.0	24.0	6.0	93.3	0.7	2.0	9.3	0.2	0.0	0.0	93.3	3.9	0.0	8.7	0.0		0.0
309+50.41	TO	310+24.36	74.0	24.0	6.0	197.2	1.5	4.2	19.7	0.4	0.0	197.2	0.0	8.3	0.0	18.3	0.0		0.0
310+24.36	TO	310+59.36	35.0	24.0	6.0	93.3	0.7	2.0	9.3	0.2	0.0	0.0	93.3	3.9	0.0	8.7	0.0		0.0
310+59.36	TO	328+44.05	1,784.7	24.0	6.0	4,759.2	35.5	101.6	475.9	9.5	0.0	0.0	4759.2	199.9	0.0	441.4	0.0		0.0
328+44.05	TO	328+79.05	35.0	24.0	6.0	93.3	0.4	0.0	9.3	0.2	0.0	0.0	93.3	3.9	0.0	8.7	0.0	4.6	0.0
328+79.05	TO	329+40.95	61.9	24.0	6.0	165.1	0.6	3.5	16.5	0.3	0.0	165.1	0.0	6.9	0.0	15.3	0.0		0.0
329+40.95	TO	329+75.95	35.0	24.0	6.0	93.3	0.4	0.0	9.3	0.2	0.0	0.0	93.3	3.9	0.0	8.7	0.0		0.0
329+75.95	TO	437+50.00	10,774.1	24.0	6.0	28,730.8	208.4	585.3	2,873.1	57.5	0.0	0.0	28730.8	1206.7	0.0	2,664.4	0.0	36.5	0.0
437+50.00	TO	457+76.09	2,026.1	24.0	6.0	5,402.9	40.5	115.4	540.3	10.8	0.0	0.0	5402.9	226.9	0.0	501.1	0.0		0.0
457+76.09	TO	470+16.90	1,240.8	30.0	0.0	4,136.0	0.0	0.0	496.3	9.9	0.0	0.0	4963.2	208.5	0.0	445.8	0.0	3.5	0.0
470+16.90 B	=	470+71.1 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0
470+71.10	TO	473+55.29	284.2	24.0	0.0	757.8	0.0	0.0	94.7	1.9	0.0	0.0	947.3	39.8	0.0	86.2	0.0		0.0
473+55.29	TO	509+10.40	3,555.1	24.0	6.0	9,480.3	70.0	196.1	948.0	19.0	0.0	0.0	9480.3	398.2	0.0	879.2	0.0	7.6	0.0
509+10.4 BK	=	509+10.9 AH	0.0	0.0	6.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0
509+10.90	TO	534+16.32	2,505.4	24.0	6.0	6,681.1	48.2	142.7	668.1	13.4	0.0	0.0	6681.1	280.6	0.0	619.6	0.0		0.0
534+16.32	TO	534+51.32	35.0	24.0	6.0	93.3	0.0	2.0	9.3	0.2	101.1	0.0	0.0	3.9	0.0	8.7	0.0		0.0
534+51.32	TO	535+95.64	144.3	NA	6.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0
535+95.64	TO	536+30.64	35.0	24.0	6.0	93.3	0.0	2.0	9.3	0.2	101.1	0.0	0.0	3.9	0.0	8.7	0.0		0.0
536+30.64	TO	561+49.50	2,518.9	24.0	6.0	6,717.0	46.0	129.4	671.7	13.4	0.0	0.0	6717.0	282.1	0.0	622.9	0.0	14.3	0.0
561+49.50	TO	572+25.97	1,076.5	30.0	0.0	3,588.2	0.0	0.0	430.6	8.6	0.0	0.0	4305.8	180.8	0.0	386.8	0.0	4.6	0.0
572+25.97 B	=	572+85.70 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0
572+85.70	TO	574+85.70	200.0	24.0	0.0	533.3	0.0	0.0	66.7	1.3	0.0	0.0	666.6	28.0	0.0	60.7	0.0		0.0
574+85.70	TO	605+05.78	3,020.1	24.0	6.0	8,053.5	58.9	163.2	805.4	16.1	0.0	0.0	8053.5	338.2	0.0	746.9	0.0	10.1	0.0
605+05.78 B	=	605+07.60 AH	0.0	0.0	6.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0
605+07.60	TO	631+88.00	2,680.4	24.0	6.0	7,147.7	53.2	152.6	714.8	14.3	0.0	0.0	7147.7	300.2	0.0	662.9	0.0		0.0
631+88.00	TO	632+23.00	35.0	24.0	6.0	93.3	0.4	0.0	9.3	0.2	101.1	0.0	0.0	3.9	0.0	8.7	0.0	4.4	0.0
SHEET TOTALS			33,487			90,458	591	1,674	9,233	185	303	362	91,683	3,878	0	8,532	0	89	0
PROJECT TOTALS			50,769			154,766	978	2,764	15,883	318	941	19,972	137,940	5,859	812	12,804	1,762	137	480

FILE NAME =	USER NAME = \$USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#		DRAWN -	REVISED -						116	(124,125,126)RS-3	RICHLAND	60	15
	PLOT SCALE = \$SCALE*	CHECKED -	REVISED -		SCALE: NA				SHEET NO. 2 OF 7 SHEETS		STA.	TO STA.	
	PLOT DATE = \$DATE*	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								