

M001

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		CLAY COUNTY 0004	EFFINGHAM COUNTY 0004	EFFINGHAM COUNTY 0014
X0327487	TRIAXIAL GEOGRID REINFORCEMENT, TYPE I	SO YD	4395	1810	2585	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30.5		30.5	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	17	7	10	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3360	1320	2040	
20400800	FURNISHED EXCAVATION	CU YD	18.3	2.9	15.4	
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	4004	1649	2355	
31102100	SUBBASE GRANULAR MATERIAL, TYPE C 4"	SO YD	2930	1207	1723	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19217	800	18417	
40600300	AGGREGATE (PRIME COAT)	TON	384	16	368	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1	
40600990	TEMPORARY RAMP	SO YD	475	44.5	430.5	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	16960	1210	15750	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	9856	404	9452	

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		CLAY COUNTY 0004	EFFINGHAM COUNTY 0004	EFFINGHAM COUNTY 0014
40701886	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/4"	SO YD	1810	1810		
40701931	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 1/2"	SO YD	2586		2586	
44000100	PAVEMENT REMOVAL	SO YD	4395	1810	2585	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	8458		8458	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	82965		82965	
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SO YD	4501		4501	
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SO YD	19391	3087	16304	
44004250	PAVED SHOULDER REMOVAL	SO YD	13787	2430	11357	
44200561	CLASS A PATCHES, TYPE I, 11 INCH	SO YD	24		24	
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SO YD	378.7		378.7	
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SO YD	36		36	
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SO YD	66.7		66.7	
44200608	CLASS A PATCHES, TYPE I, 13 INCH	SO YD	4		4	

• (25-6-11RS-8 & (13-11RS-2  
•• EFFINGHAM, CLAY

FILE NAME: c:\pr-work\p101011\teasleyk\00101558\4774450-shr-sq.dgn	USER NAME: teasleyk	DESIGNED: -	REVISED: -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE. 57	SECTION	COUNTY **	TOTAL SHEETS 84	SHEET NO. 4
PLOT SCALE: 1/8" = 1'-0"	PLotted DATE: 10/18/2012	DRAWN: -	REVISED: -		SCALE: NA	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 74450			
CHECKED: -	DATE: -	REVISED: -	REVISED: -		ILLINOIS FED. AID PROJECT							
DATE: -	REVISED: -											