

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		CLAY COUNTY	EFFINGHAM COUNTY	
			0004	0004	0014	
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SO YD	40	40		
44200616	CLASS A PATCHES, TYPE I, 14 INCH	SO YD	24	24		
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SO YD	216	184	32	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	206		206	
44201299	DOWEL BARS 1 1/2"	EACH	812		812	
44213000	PATCHING REINFORCEMENT	SO YD	789	208	581	
44213200	SAW CUTS	FOOT	6788	1364	5424	
44213206	TIE BARS 5/8"	EACH	97	10	87	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	983	515	468	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2137	85	2052	
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	13810	2430	11380	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	6194	187	6007	
50102400	CONCRETE REMOVAL	CU YD	27.8		27.8	
50157300	PROTECTIVE SHIELD	SO YD	131		131	

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		CLAY COUNTY	EFFINGHAM COUNTY	
			0004	0004	0014	
50300100	FLOOR DRAINS	EACH	40		40	
50300225	CONCRETE STRUCTURES	CU YD	3		3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	27.8		27.8	
50300260	BRIDGE DECK GROOVING	SO YD	932		932	
50300300	PROTECTIVE COAT	SO YD	89		89	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3010		3010	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4170	530	3640	
50800515	BAR SPLICERS	EACH	56		56	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	179		179	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28		28	
52100520	ANCHOR BOLTS, 1"	EACH	56		56	
60100082	SHOULDER REMOVAL AND REPLACEMENT 11 1/2"	FOOT	57445	24	57421	
60107700	PIPE UNDERDRAINS 6"	FOOT	78919	3402	75517	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	3012	266	2746	

• (25-6-URS-8 & (13-URS-2
 ** EFFINGHAM, CLAY

FILE NAME :	USER NAME : teasleyk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			P.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pvidot\teasleyk\0181598\077	4450-shr-000.dgn	DRAWN -	REVISED -		57	.	**	84	5			
	PLOT SCALE : 100.0000 1/16"	CHECKED -	REVISED -		SCALE: NA SHEET NO. 2 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 74450				
	PLOT DATE : 10/18/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							