

**UNDERDRAIN SCHEDULE**

STATIONS ARE ALONG CENTERLINE UNLESS NOTED OTHERWISE DRAIN SLOPE IS 0.2% MINUS PAVEMENT SLOPE OR PGL				PIPE UNDERDRAINS, 6"				PIPE UNDERDRAINS, 6" (SPECIAL)								HMA SHOULDER REMOVAL AND REPLACEMENT (FOR UNDERDRAIN TRENCH)				HMA SHOULDER REMOVAL AND REPLACEMENT, (FOR UNDERDRAIN (SPL) TRENCH)			
FROM STATION	TO STATION	PAVEMENT SLOPE (%)	DRAIN SLOPE (%)	NORTHBOUND		SOUTHBOUND		NORTHBOUND		SOUTHBOUND		CLASS SI CONCRETE OUTLET PROTECTOR (CU. YD.)	NORTHBOUND		SOUTHBOUND		NORTHBOUND		SOUTHBOUND				
				OUTSIDE (FT)	INSIDE (FT)	OUTSIDE (FT)	INSIDE (FT)	OUTSIDE (FT)	%	INSIDE (FT)	%		OUTSIDE (FT)	%	INSIDE (FT)	%	OUTSIDE (FT)	INSIDE (FT)	OUTSIDE (FT)	INSIDE (FT)	OUTSIDE (FT)	INSIDE (FT)	
Begin Project	3309+82.00	+0.23	PGL			0.0	0.0					3											
	3309+82.00	3312+57.09	+0.23	PGL			275.1	275.1					3										
	3312+57.09	3317+57.09	+0.06	0.14			500.0	500.0					3										
	3317+57.09	3319+28.74	+0.06	0.14			171.6	171.6					0										
	3319+28.74	4199+97.27	Station Equation				0.0	0.0					0										
	4199+97.27	4201+08.16	+0.06	0.14			110.9	110.9					0										
	4201+08.16	4203+25.67	-0.28	PGL			217.5	217.5					3										
	4203+25.67	4208+25.67	+0.06	0.14			500.0	500.0					3										
	4208+25.67	4213+25.67	+0.06	0.14			500.0	500.0					3										
	4213+25.67	4218+25.67	+0.06	0.14			500.0	500.0					3										
	4218+25.67	4223+25.67	+0.06	0.14			500.0	500.0					3										
	4223+25.67	4228+25.67	+0.06	0.14			500.0	500.0					3										
	4228+25.67	4233+25.67	+0.06	0.14			500.0	500.0					3										
	4233+25.67	4238+25.67	+0.06	0.14			500.0	500.0					3										
	4238+25.67	4243+25.67	+0.06	0.14			500.0	500.0					3										
	4243+25.67	4248+25.67	+0.06	0.14			500.0	500.0					3										
	4248+25.67	4253+25.67	+0.06	0.14			500.0	500.0					3										
	4253+25.67	4258+25.67	+2.5	PGL			500.0	500.0					3										
	4258+25.67	4263+25.67	+2.5	PGL			500.0	500.0					3										
	4263+25.67	4268+25.67	+2.5	PGL			500.0	500.0					0										
	4268+25.67	4271+30.08	U. D. OMISSION				0.0	0.0					0										
	4271+30.08	4276+30.08	-2.5	PGL			500.0	500.0					3										
	4276+30.08	4281+30.08	-2.5	PGL			500.0	500.0					3										
	4281+30.08	4287+50.00	-2.5	PGL			619.9	619.9					3										
	4287+50.00	4291+30.08	+0.65	PGL			0.0	380.1				1.5											
	4291+30.08	4296+30.08	+0.65	PGL			0.0	500.0				1.5											
	4296+30.08	4299+50.00	+0.65	PGL			0.0	319.9				3											
	4299+50.00	4302+00.00	+0.65	PGL			250.0	250.0					0										
	4302+00.00	4306+02.57	-0.18	-0.02			402.6	402.6					3										
	4306+02.57	4308+65.32	U. D. OMISSION				0.0	0.0					0										
	4308+65.32	4313+65.32	-0.18	-0.02			500.0	500.0					3										
	4313+65.32	4318+65.32	-0.18	-0.02			500.0	500.0					3										
	4318+65.32	4323+65.32	-0.18	-0.02			0.0	500.0					1.5										
	4323+65.32	4326+60.54	-0.18	-0.02			0.0	295.2					0										
	4326+60.54	4328+65.32	-0.18	-0.02			204.8	204.8					3										
	4328+65.32	4333+65.32	-0.18	-0.02			500.0	500.0					3										
	4333+65.32	4338+65.32	-0.18	-0.02			500.0	500.0					3										
	4338+65.32	4343+65.32	-0.18	-0.02			500.0	500.0					3										
	4343+65.32	4348+50.00	-0.18	-0.02			484.7	484.7					3										
	4348+50.00	4354+00.00	+0.22	PGL			550.0	550.0					3										
	4354+00.00	4359+00.00	+0.22	PGL			500.0	500.0					3										
	4359+00.00	4364+00.00	+0.22	PGL			500.0	500.0					3										
	4364+00.00	4369+00.00	+0.22	PGL			500.0	500.0					3										
	4369+00.00	4374+00.00	+0.22	PGL			500.0	500.0					3										
	4374+00.00	4379+00.00	+0.22	PGL			500.0	500.0					0										
SHEET TOTALS				0.00	0.00	16,287.09	18,282.31	0.00	0.00	675.50	746.00	103.50	0.00	0.00	6,892.03	8,887.25	0.00	0.00	248.00	102.00			

• (25-6-1)RS-8 & (13-1)RS-2  
•• EFFINGHAM, CLAY

FILE NAME =	USER NAME = teasleyk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\p\p\dot\teasleyk\d0181558\d774450-sht-sch.dgn		DRAWN -	REVISED -			57	•	••	84	31
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -			CONTRACT NO. 74450				
PLOT DATE = 10/18/2012		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				

SCALE: NA SHEET NO. 8 OF 13 SHEETS STA. TO STA.