

EARTHWORK SCHEDULE

Location	Earth Excavation		Earthwork Balance	
	Earth Excavation	Adj. for Shrinkage	Embankment	Waste (+)/Shortage (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
4204+51.39 TO 4207+41.80 (SB O/S SHLD, SN 013-0027)			2.9	-2.9
4265+30.10 TO 4268+56.74 (SB O/S SHLD SN 025-0068)			0.0	0.0
4271+00.08 TO 4278+02.23 (SB O/S SHLD SN 025-0068)			0.0	0.0
4271+00.08 TO 4278+02.23 (SB MED SHLD SN 025-0068)			3.4	-3.4
4308+08.65 TO 4311+44.49 (SB MED SHLD SN 025-0070)			3.4	-3.4
4308+32.14 TO 4311+15.97 (SB O/S SHLD SN 025-0070)			2.8	-2.8
4430+22.51 TO 4433+12.16 (SB O/S SHLD SN 025-0043)			2.9	-2.9
4481+96.51 TO 4484+86.16 (SB O/S SHLD SN 025-0073)			2.9	-2.9
PROJECT TOTAL	9.0	6.8	18.3	-18

TRIAxIAL GEOGRID REINFORCEMENT, TYPE 1 SCHEDULE

LOCATION	LENGTH (FT.)	@ WIDTH (FT.)	QTY (SQ YD)	
4201+08.13 TO 4207+86.83	678.7	24.0	1,809.9	CLAY CO.
4428+44.30 TO 4431+97.40	353.1	24.0	941.6	EFF. CO.
4478+57.87 TO 4484+74.37	616.5	24.0	1,644.0	EFF. CO.
PROJECT TOTAL = 4,395.5				

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL SCHEDULE

LOCATION	LENGTH (FT.)	@ WIDTH (FT.)	AVG. DEPTH (FT.)	QTY (CU YD)	
4201+08.13 TO 4207+86.83	678.7	24.0	2.188	1,319.7	CLAY CO.
4428+44.30 TO 4431+97.40	353.1	24.0	1.9	601.6	EFFINGHAM CO.
4478+57.87 TO 4484+74.37	616.5	24.0	2.625	1,438.5	EFFINGHAM CO.
TOTAL = 3,360 CU YD					

PAVEMENT MARKING REMOVAL SCHEDULE

LOCATION	LENGTH	O/S	MEDIAN	DASHED	TOTAL SQ. FT.
		EDGE LINE FOOT	EDGE LINE FOOT	EDGE LINE FOOT	
FAI 57					
4201+08.10 TO 4209+58.60	850.5	850.5	850.5	36.7	585.3
4267+00.80 TO 4270+64.10	363.3	363.3	363.3	72.3	278.3
4289+40.20 TO 4292+47.40	307.2	0.0	0.0	76.8	38.4
4304+69.10 TO 4310+00.20	531.1	531.1	531.1	75.1	391.6
4326+05.60 TO 4329+10.00	304.4	0.0	0.0	76.1	38.1
4428+44.30 TO 4433+62.40	518.1	518.1	518.1	35.0	362.9
4477+17.90 TO 4486+39.40	921.5	921.5	921.5	70.0	649.3
PROJECT TOTAL =					2,343.8
CLAY CO.					585.3
EFFINGHAM CO.					1,758.5

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION	LENGTH	
SN 013-0027	FT.	
4201+08.13 TO 4208+11.83	704	
4208+11.83 TO 4209+80.30	168	12:1 TAPER
SN 025-0068		
4268+40.75 TO 4271+15.08	274	
4271+15.08 TO 4272+95.08	180	12:1 TAPER
SN 025-0070		
4306+18.15 TO 4308+49.74	232	
4308+49.74 TO 4310+29.74	180	12:1 TAPER
SN 025-0043		
4428+44.30 TO 4432+22.39	378	
4432+22.39 TO 4433+90.39	168	12:1 TAPER
SN 025-0073		
4478+57.87 TO 4484+99.37	642	
4484+99.37 TO 4486+67.37	168	12:1 TAPER
TOTAL = 3,094		

RELOCATE TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION	LENGTH	
SN 013-0027	FT.	
4201+08.13 TO 4208+11.83	704	
4208+11.83 TO 4209+80.30	168	12:1 TAPER
SN 025-0068		
4268+40.75 TO 4271+15.08	274	
4271+15.08 TO 4272+95.08	180	12:1 TAPER
SN 025-0070		
4306+18.15 TO 4308+49.74	232	
4308+49.74 TO 4310+29.74	180	12:1 TAPER
SN 025-0043		
4428+44.30 TO 4432+22.39	378	
4432+22.39 TO 4433+90.39	168	12:1 TAPER
SN 025-0073		
4478+57.87 TO 4484+99.37	642	
4484+99.37 TO 4486+67.37	168	12:1 TAPER
TOTAL = 3,094		

• (25-6-1)RS-8 & (13-1)RS-2
 ** EFFINGHAM, CLAY