

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SO YD	109	109		
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SO YD	131	131		
44213000	PATCHING REINFORCEMENT	SO YD	3374	3374		
44213200	SAW CUTS	FOOT	18014	18014		
44213204	TIE BARS 3/4"	EACH	3670	3670		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1153	1153		
50104650	SLOPE WALL REMOVAL	SO YD	129	129		
51100100	SLOPE WALL 4 INCH	SO YD	129	129		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	73	73		
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	15363	15363		
60100076	SHOULDER REMOVAL AND REPLACEMENT 11"	FOOT	13161	13161		
60107700	PIPE UNDERDRAINS 6"	FOOT	27830	27830		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	1232	1232		
60261000	INLETS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	
60500205	FILLING CATCH BASINS	EACH	1	1		
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	708	708		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	26177	26177		
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SO FT	31660	31660		
60621200	CONCRETE MEDIAN, TYPE SB-9.24	SO FT	3624	3624		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25		

FILE NAME : c:\pwork\p10271050\07	USER NAME : steffernk	DESIGNED -	REVISED -
4537-ahf-soq.dgn		DRAWN -	REVISED -
PLOT SCALE : 100.0000 1/4 in.		CHECKED -	REVISED -
PLOT DATE : 3/22/2013		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE. 712, F.A.U. RTE. 7464

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	58-64-IRS, 126RS-2	Macon	69	5
CONTRACT NO. 74537			[ILLINOIS] FED. AID PROJECT	