

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	10713	10713		
* 70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1482	1482		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	60858	60858		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13895	13895		
* 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	510	510		
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	445	445		
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	536	536		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3571	3571		
72400720	RELOCATE SIGN PANEL - TYPE 2	SO FT	42		42	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1482	1482		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	60858	60858		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6090	6090		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	510	510		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	445	445		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	536	536		
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	7805	7805		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	593	593		
* 78200300	PRISMATIC CURB REFLECTOR	EACH	1150	1150		
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2		2	
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2	
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	7		7	
88600100	DETECTOR LOOP, TYPE I	FOOT	4453		4453	
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	6		6	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
X4060995	TEMPORARY RAMP, SPECIAL	SO YD	160	160		

13 *SPECIALTY ITEM

12

FILE NAME :	USER NAME : efferank	DESIGNED -	REVISED -
cr:\pwr\work\pwr\dot\st\effrank\0271050\074537\sh\soq.dgn	4537-sh-soq.dgn	DRAWN -	REVISED -
Default	PLOT SCALE : 100.0000 / in.	CHECKED -	REVISED -
	PLOT DATE : 3/22/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 3 OF 4 SHEETS STA. TO STA.

* F.A.P. RTE. 712, F.A.U. RTE. 7464				
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	58-64-IRS, 126RS-2	Macon	69	6
			CONTRACT NO. 74537	
ILLINOIS FED. AID PROJECT				