

PAVING SCHEDULE (CONT)

SOUTHBOUND LANES

								HOT MIX ASPHALT SURFACE REMOVAL, 1 1/2" (SHOULDER)	HOT MIX ASPHALT SURFACE REMOVAL, 2 1/2" (PAVEMENT)	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N90 (PAVEMENT)	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N30 (SHOULDER)	AGGREGATE WEDGE SHOULDER, TYPE B
		PAVEMENT				SHOULDER									
		LENGTH	WIDTH	AREA	WIDTH	AREA									
STATION	TO	STATION	FEET	FEET	SO YD	FEET	SO YD	SO YD	SO YD	GALLON	TON	TON	TON	TON	TON
200+93	TO	202+87	193.7	36-24	645.7	10.0	215.2	215.2	645.7	86.1	1.7	36.2	54.2	18.1	4.9
202+86.71 BK	=	126+96.71 AH						0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
126+97	TO	127+44	47.3	24.0	164.3	10.0	52.5	52.5	164.3	21.7	0.4	9.2	13.8	4.4	1.2
127+44	TO	128+05	61.0	46.0	311.8	10.0	67.8	67.8	311.8	38.0	0.8	17.5	26.2	5.7	1.5
128+05	TO	129+29	124.0	38.0	527.5	10.0	137.8	137.8	527.5	66.5	1.3	29.5	44.3	11.6	3.1
129+29	TO	130+31	102.0	38-26	362.7	10.0	113.3	0.0	0.0	47.6	1.0	20.3	30.5	12.7	4.5
130+31	TO	130+91	60.0	26.0	214.3	10.0	66.7	0.0	0.0	28.1	0.6	12.0	18.0	7.5	2.7
130+91	TO	131+51	60.0	46.0	306.7	10.0	66.7	0.0	0.0	37.3	0.7	17.2	25.8	7.5	2.7
131+51	TO	133+86	235.0	38.0	997.5	10.0	261.1	0.0	0.0	125.9	2.5	55.9	83.8	29.2	10.4
133+86	TO	135+64	178.0	38-26	632.9	10.0	197.8	0.0	0.0	83.1	1.7	35.4	53.2	22.2	7.9
135+64	TO	142+26	662.0	26.0	1,953.4	10.0	735.6	0.0	0.0	268.9	5.4	109.4	164.1	82.4	29.3
142+26	TO	142+84	58.0	46.0	296.4	10.0	64.4	0.0	0.0	36.1	0.7	16.6	24.9	7.2	2.6
142+84	TO	145+20	236.0	38.0	1,002.2	10.0	262.2	0.0	0.0	126.4	2.5	56.1	84.2	29.4	10.5
145+20	TO	147+02	182.0	38-26	647.1	10.0	202.2	0.0	0.0	84.9	1.7	36.2	54.4	22.6	8.1
147+02	TO	151+15	413.0	26.0	1,193.1	10.0	458.9	0.0	0.0	165.2	3.3	66.8	100.2	51.4	18.3
151+15	TO	152+15	100.0	46.0	511.1	10.0	111.1	0.0	0.0	62.2	1.2	28.6	42.9	12.4	4.4
152+15	TO	154+56	241.0	38.0	1,017.6	10.0	267.8	0.0	0.0	128.5	2.6	57.0	85.5	30.0	10.7
154+56	TO	156+64	208.0	38-26	739.6	10.0	231.1	0.0	0.0	97.1	1.9	41.4	62.1	25.9	9.2
156+64	TO	170+76	1,412.0	26.0	4,079.1	10.0	1,568.9	0.0	0.0	564.8	11.3	228.4	342.6	175.7	62.5
170+76	TO	172+07	131.0	46.0	669.6	10.0	145.6	0.0	0.0	81.5	1.6	37.5	56.2	16.3	5.8
172+07	TO	173+96	189.0	38.0	798.0	10.0	210.0	0.0	0.0	100.8	2.0	44.7	67.0	23.5	8.4
173+96	TO	175+59	163.0	38-26	579.6	10.0	181.1	0.0	0.0	76.1	1.5	32.5	48.7	20.3	7.2
175+59	TO	176+20	61.0	26.0	215.2	10.0	67.8	0.0	0.0	28.3	0.6	12.1	18.1	7.6	2.7
176+20	TO	176+65	45.0	46.0	230.0	10.0	50.0	0.0	0.0	28.0	0.6	12.9	19.3	5.6	2.0
176+65	TO	178+82	217.0	38.0	919.2	10.0	241.1	0.0	0.0	116.0	2.3	51.5	77.2	27.0	9.6
178+82	TO	180+54	172.0	38-26	611.6	10.0	191.1	0.0	0.0	80.3	1.6	34.2	51.4	21.4	7.6
180+54	TO	181+23	69.0	26.0	237.3	10.0	76.7	0.0	0.0	31.4	0.6	13.3	19.9	8.6	3.1
181+23	TO	181+66	43.0	46.0	219.8	10.0	47.8	0.0	0.0	26.8	0.5	12.3	18.5	5.4	1.9
181+66	TO	183+77	211.0	38.0	893.9	10.0	234.4	0.0	0.0	112.8	2.3	50.1	75.1	26.3	9.3
183+77	TO	185+35	158.0	38-26	561.8	10.0	175.6	0.0	0.0	73.7	1.5	31.5	47.2	19.7	7.0
185+35	TO	186+09	74.0	26.0	257.8	10.0	82.2	0.0	0.0	34.0	0.7	14.4	21.7	9.2	3.3
186+09	TO	186+78	69.0	46.0	352.7	10.0	76.7	0.0	0.0	42.9	0.9	19.7	29.6	8.6	3.1
186+78	TO	187+78	100.0	38.0	426.1	10.0	111.1	0.0	0.0	53.7	1.1	23.9	35.8	12.4	4.4
187+78	TO	189+44	166.0	38-26	590.2	10.0	184.4	0.0	0.0	77.5	1.5	33.1	49.6	20.7	7.4

* F.A.P. RTE. 712, F.A.U. RTE. 7464

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\p\dot\stefennk\d0271850\074537-sh-t-sch.dgn		DRAWN -	REVISED -		SCALE: N/A				*	58-64-IRS, 126RS-2	Macon	69	16
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SHEET 2 OF 11 SHEETS				CONTRACT NO. 74537				
	PLOT DATE = 3/22/2013	DATE -	REVISED -		STA. TO STA.				ILLINOIS FED. AID PROJECT				