

# PAVING SCHEDULE (CONT)

## NORTHBOUND LANES

								HOT MIX ASPHALT SURFACE REMOVAL, 1 1/2" ( SHOULDER)	HOT MIX ASPHALT SURFACE REMOVAL, 2 1/2" ( PAVEMENT)	BITUMINOUS MATERIALS ( PRIME COAT)	AGGREGATE ( PRIME COAT)	LEVELING BINDER ( MACHINE METHOD)	POLYMERIZED HMA SURFACE COURSE, MIX "D", NSO ( PAVEMENT)	HOT MIX ASPHALT SURFACE COURSE, MIX "C", NSO ( SHOULDER)	AGGREGATE WEDGE SHOULDER, TYPE B
			PAVEMENT			SHOULDER									
STATION	TO	STATION	LENGTH FEET	WIDTH FEET	AREA SQ YD	WIDTH FEET	AREA SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	TON
28+76	TO	29+84	108.0	24.0	288.0	0.0	0.0	0.0	0.0	28.8	0.6	16.1	24.2	0.0	4.8
29+84	TO	30+58	74.0	26.0	213.8	11.0	90.4	0.0	0.0	30.4	0.6	12.0	18.0	10.1	3.3
30+58	TO	32+07	149.0	24.0	397.3	11.0	182.1	182.1	397.3	57.9	1.2	22.3	33.4	20.4	3.8
32+07	TO	33+95	188.0	24-36	501.3	11.0	229.8	229.8	501.3	73.1	1.5	28.1	42.1	19.3	4.8
33+95	TO	36+34	239.0	36.0	637.3	11.0	292.1	292.1	637.3	92.9	1.9	35.7	53.5	24.5	6.0
36+34	TO	37+95	161.0	24.0	429.3	0.0	0.0	0.0	429.3	42.9	0.9	24.0	36.1	0.0	4.1
37+95	TO	43+30	535.0	24.0	1,426.7	11.0	653.9	653.9	1,426.7	208.1	4.2	79.9	119.8	54.9	13.5
43+30	TO	43+92	62.0	24.0	165.3	0.0	0.0	0.0	165.3	16.5	0.3	9.3	13.9	0.0	1.6
43+92	TO	61+74	1,782.0	24.0	4,752.0	11.0	2,178.0	2,178.0	4,752.0	693.0	13.9	266.1	399.2	183.0	45.1
61+74	TO	62+74	100.0	24.0	266.7	11.0	122.2	122.2	266.7	38.9	0.8	14.9	22.4	10.3	2.5
62+74	TO	66+60	386.0	26.0	1,115.1	11.0	471.8	471.8	1,115.1	158.7	3.2	62.4	93.7	39.6	9.8
66+60	TO	68+54	194.0	24-36	517.3	11.0	237.1	237.1	517.3	75.4	1.5	29.0	43.5	19.9	4.9
68+54	TO	69+90	136.0	37.0	347.6	11.0	166.2	166.2	347.6	51.4	1.0	19.5	29.2	14.0	3.4
69+90	TO	71+60	170.0	37-24	226.7	10.0	188.9	188.9	226.7	41.6	0.8	12.7	19.0	15.9	4.3
71+60	TO	72+50	90.0	24-12	120.0	0.0	0.0	0.0	120.0	12.0	0.2	6.7	10.1	0.0	2.3
72+50	TO	79+50	700.0	12.0	933.3	10.0	777.8	777.8	933.3	171.1	3.4	52.3	78.4	65.3	17.7
NORTHBOUND TOTALS			17,071.8		48,629.8		17,536.9	8,476.6	23,912.7	6,616.7	132.3	2,723.3	4,084.9	1,731.9	576.3
SOUTHBOUND TOTALS			17,071.8		59,975.2		18,559.0	9,442.9	30,636.9	7,853.4	157.1	3,358.6	5,037.9	1,814.2	576.3
PROJECT TOTALS					108,605.0		36,095.8	17,919.4	54,549.6	14,470.1	289.4	6,081.9	9,122.8	3,546.1	1,152.7

NOTE: AREAS BETWEEN MEDIANS AT INTERSECTIONS INCLUDED IN SOUTHBOUND LANE CALCULATIONS

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\steffenmk\d0271850\074537-sht-sch.dgn		DRAWN -	REVISED -		SCALE: N/A				58-64-IRS, 126RS-2	Macon	69	20	
Default		CHECKED -	REVISED -		SHEET 6 OF 11 SHEETS				CONTRACT NO. 74537		ILLINOIS FED. AID PROJECT		
		DATE -	REVISED -		STA. TO STA.								

• F.A.P. RTE. 712, F.A.U. RTE. 7464