

PAVEMENT MARKING SCHEDULE				PERFORMED PLASTIC, TYPE B-INLAID-6" (WHITE)-SKIP DASHES	THERMOPLASTIC- 6" (WHITE)	THERMOPLASTIC- 4" (WHITE)	THERMOPLASTIC- 4" (YELLOW)	THERMOPLASTIC-LETTERS AND SYMBOLS (WHITE)	THERMOPLASTIC- 24" (WHITE)	THERMOPLASTIC- 12" (WHITE)	THERMOPLASTIC- 12" (YELLOW)	THERMOPLASTIC- 8" (WHITE)	RRPM: 1-WAY CRYSTAL	RRPM: 1-WAY AMBER	RRPM: 2-WAY AMBER	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY LINE 4"	TEMPORARY LINE 6"	TEMPORARY LINE 8"	TEMPORARY LINE 12"	TEMPORARY LINE 24"	TEMPORARY-LETTERS AND SYMBOLS (WHITE)	
STATION	TO	STATION	LENGTH FEET	FEET	FEET	FEET	FEET	SO FT	FEET	FEET	FEET	FEET	EACH	EACH	EACH	FEET	SO FT	FEET	FEET		FEET	FEET	SO FT	
165+40	TO	169+00	360	180	100		640	31.2					13			138	46	640	280				31.2	
169+00	TO	175+00	600	300	100	1000	1080	31.2					19			330	110	2080	400				31.2	
175+00	TO	181+00	600	300	260	1040	1100	78.0					23			383	128	2140	560				78.0	
181+00	TO	187+00	600	240	770	820	960	187.2	112				30			509	170	1780	1010			112	187.2	
187+00	TO	193+00	600	300	410	1100	860	109.2					26			435	145	1960	710				109.2	
193+00	TO	198+00	500	200	270	650	860	78.0	36				17			309	103	1510	470			36	78.0	
198+00	TO	127+00	500	225	240	700	900	62.4	36				18			306	102	1600	465			36	62.4	
127+00	TO	133+00	600	300	260	1170	1200	62.4					23			398	133	2370	560				62.4	
133+00	TO	139+00	600	300	180	1200	1200	31.2					19			378	126	2400	480				31.2	
139+00	TO	145+00	600	300	210	1100	1100	46.8					21			375	125	2200	510				46.8	
145+00	TO	150+00	500	250	230	1000	1000	46.8					19			339	113	2000	480				46.8	
150+00	TO	156+00	600	250	360	760	1040	62.4	92				23			379	126	1800	610			92	62.4	
156+00	TO	162+00	600	300		1200	1200						16			324	108	2400	300					
162+00	TO	168+00	600	300		1200	1200						16			324	108	2400	300					
168+00	TO	174+00	600	300	240	1200	950	62.4					22			396	132	2150	540				62.4	
174+00	TO	180+00	600	300		1200	1120						16			324	108	2320	300					
180+00	TO	186+00	600	300		1200	1140						16			324	108	2340	300					
186+00	TO	191+00	500	250	110	1000	970	31.2					17			303	101	1970	360				31.2	
191+00	TO	196+00	500	250	170	1000	860	46.8					18			321	107	1860	420				46.8	
196+00	TO	202+00	600	300	210	1200	1200	46.8					21			387	129	2400	510				46.8	
202+00	TO	208+00	600	300		1200	1200						16			324	108	2400	300					
208+00	TO	33+00	572	240	300	994	944	46.8	70				16			381	127	1938	540			70	46.8	
33+00	TO	39+00	600	300	360	900	920	93.6					24			396	132	1820	660				93.6	
39+00	TO	45+00	600	300	240	970	1080	62.4	60				21			368	123	2050	540			60	62.4	
45+00	TO	51+00	600	300	140	1200	1200	31.2					19			366	122	2400	440				31.2	
51+00	TO	57+00	600	300		1200	1200						16			324	108	2400	300					
57+00	TO	62+00	500	250		920	960						14			260	87	1880	250					
62+00	TO	67+00	500	250	300	860	860	62.4					21			343	114	1720	550				62.4	
67+00	TO	73+00	600	120	290	790	850	78.0			30		11	8	2	362	121	1640	410		30		78.0	
73+00	TO	79+50	650		20	1300	810	15.6			65			12	15	357	119	2110	20		65		15.6	
INTERSECTIONS					320		180	78.0	130	250	100	510	3	2		249	83	180	320	510	350	130	78.0	
TOTALS				7805	6090	30074	30784	1482	536	250	195	510	554	22	17		10713	3571	60858	13895	510	445	536	1482

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pw_work\p\dot\stef\enmk\d0271850\074537-sh-t-sch.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/22/2013	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: N/A	SHEET 7 OF 11 SHEETS	STA.	TO STA.

• F.A.P. RTE. 712, F.A.U. RTE. 7464				
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	58-64-IRS, 126RS-2	Macon	69	21
CONTRACT NO. 74537				
ILLINOIS FED. AID PROJECT				