

SURVEY MONUMENT SCHEDULE

STATION	TYPE OF POINT	DESCRIPTION	PERMANENT SURVEY MARKERS, TYPE 1	SURVEY MARKER VAULT	PROTECTING OR RESETTING SURVEY MARKERS
			EACH	EACH	EACH
157+00	PC	MARKER	1	1	1
164+46.40	PT	MARKER	1	1	1
165+97.80	PC	MARKER	1	1	1
200+21.45	PC	MARKER	•	•	•
204+49.62	PT	MARKER	•	•	•
204+49.71	PC	MARKER	•	•	•
208+77.88	PT	MARKER	•	•	•
48+97	P. O. T.	MARKER	•	•	•
50+00	P. O. T.	ALUMINUM DISK	•	•	•
52+00	P. O. T.	ALUMINUM DISK	•	•	•
		TOTALS	3	3	3

NOTE: TIE POINTS NOT PROVIDED FOR ALL SURVEY POINTS. THE RESIDENT ENGINEER NEEDS TO ESTABLISH ANY NECESSARY TIE POINTS BEFORE THE SURVEY POINT IS DISTURBED.

- FOR INFORMATION ONLY. EXISTING MARKERS SHOULD NOT BE DISTURBED.

SLOPEWALL REPAIR SCHEDULE

SLOPEWALL REPAIR SCHEDULE				SLOPEWALL SLURRY PUMPING	SLOPEWALL REMOVAL	SLOPEWALL -4"	
LOCATION	LENGTH	WIDTH	FEET	FEET	CU YD	SQ YD	SQ YD
SN 058-0084	LT	8.0	20.0	5.9	17.8	17.8	
SN 058-0084	RT	20.0	10.0	7.4	22.2	22.2	
SN 058-0085	RT	40.0	20.0	29.6	88.9	88.9	
			TOTALS	43.0	128.9	128.9	

• F.A.P. RTE. 712, F.A.U. RTE. 7464

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ci:\pw_work\p\dot\steffenmk\d0271850\074537-sh-t-sch.dgn		DRAWN -	REVISED -		SCALE: N/A	SHEET 8	OF 11	SHEETS	STA.	TO STA.	58-64-IRS, 126RS-2	Macon	69	22
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -					CONTRACT NO. 74537		ILLINOIS FED. AID PROJECT				
	PLOT DATE = 3/22/2013	DATE -	REVISED -											