

| UNDERDRAINS SCHEDULE NORTHBOUND | | | | PIPE UNDERDRAINS 6" | PIPE UNDERDRAINS 6" (SPECIAL) | CONCRETE HEADWALLS FOR PIPE DRAINS | SHOULDER REMOVAL AND REPLACEMENT 8" | SHOULDER REMOVAL AND REPLACEMENT 11" |
|------------------------------------|----|---------|-------------|---------------------|-------------------------------|------------------------------------|-------------------------------------|--------------------------------------|
| STATION | TO | STATION | LENGTH FEET | FEET | FEET | EACH | FEET | FEET |
| 170+25 | TO | 181+60 | 1135 | 1135 | 64 | 3 | | 1135 |
| 185+16 | TO | 187+15 | 199 | 199 | 16 | 1 | | 199 |
| 188+10 | TO | 192+32 | 422 | 422 | 16 | 1 | | 422 |
| 193+22 | TO | 194+25 | 103 | 103 | 32 | 1 | | 103 |
| 195+20 | TO | 195+65 | 45 | 45 | 16 | 1 | | 45 |
| 199+09 | TO | 202+87 | 378 | 378 | | | | 378 |
| 202+87 | = | 126+97 | Sta. Eq. | | | | | |
| 126+97 | TO | 127+04 | 7 | 7 | 16 | 1 | | 7 |
| 128+51 | TO | 129+29 | 78 | 78 | | | | 78 |
| 129+29 | TO | 130+60 | 131 | 131 | 16 | 1 | 131 | |
| 131+70 | TO | 142+00 | 1030 | 1030 | 48 | 3 | 1030 | |
| 143+10 | TO | 150+84 | 774 | 774 | 48 | 3 | 774 | |
| 153+23 | TO | 185+85 | 3262 | 3262 | 128 | 7 | 3262 | |
| 186+88 | TO | 190+17 | 329 | 329 | 16 | 1 | 329 | |
| 191+20 | TO | 194+51 | 331 | 331 | 16 | 1 | 331 | |
| 195+95 | TO | 197+00 | 105 | 105 | 16 | 1 | 105 | |
| 198+05 | TO | 208+78 | 1073 | 1073 | 48 | 3 | 1073 | |
| 208+78 | = | 28+06 | Sta. Eq. | | | | | |
| 28+06 | TO | 28+24 | 18 | 18 | | | 18 | |
| 30+36 | TO | 30+58 | 22 | 22 | 16 | 1 | 22 | |
| 30+58 | TO | 36+76 | 618 | 618 | 16 | 1 | | 618 |
| 38+89 | TO | 42+47 | 358 | 358 | 16 | 1 | | 358 |
| 45+39 | TO | 61+23 | 1584 | 1584 | 64 | 4 | | 1584 |
| 64+09 | TO | 71+50 | 572 | 572 | 32 | 2 | | 572 |
| 73+00 | TO | 79+50 | 650 | 650 | 32 | 2 | | 650 |
| SOUTHBOUND TOTAL | | | | 13224 | 672 | 39 | 7075 | 6149 |

| UNDERDRAINS SCHEDULE SOUTHBOUND | | | | PIPE UNDERDRAINS 6" | PIPE UNDERDRAINS 6" (SPECIAL) | CONCRETE HEADWALLS FOR PIPE DRAINS | SHOULDER REMOVAL AND REPLACEMENT 8" | SHOULDER REMOVAL AND REPLACEMENT 11" |
|------------------------------------|----|---------|-------------|---------------------|-------------------------------|------------------------------------|-------------------------------------|--------------------------------------|
| STATION | TO | STATION | LENGTH FEET | FEET | FEET | EACH | FEET | FEET |
| 171+14 | TO | 172+00 | 86 | 86 | 16 | 1 | | 86 |
| 173+19 | TO | 176+42 | 323 | 323 | 16 | 1 | | 323 |
| 178+00 | TO | 183+42 | 542 | 542 | 16 | 1 | | 542 |
| 185+50 | TO | 189+85 | 435 | 435 | 32 | 2 | | 435 |
| 190+77 | TO | 192+45 | 168 | 168 | 16 | 1 | | 168 |
| 193+50 | TO | 194+40 | 90 | 90 | 16 | 1 | | 90 |
| 195+82 | TO | 196+61 | 79 | 79 | 16 | 1 | | 79 |
| 200+31 | TO | 202+87 | 256 | 256 | | | | 256 |
| 202+87 | = | 126+97 | Sta. Eq. | | | | | |
| 126+97 | TO | 129+29 | 232 | 232 | | | | 232 |
| 129+29 | TO | 150+00 | 2071 | 2071 | 64 | 4 | 2071 | |
| 152+55 | TO | 208+78 | 5623 | 5623 | 192 | 11 | 5623 | |
| 208+78 | = | 28+06 | Sta. Eq. | | | | | |
| 28+06 | TO | 30+58 | 252 | 252 | 16 | 1 | 252 | |
| 30+58 | TO | 36+45 | 587 | 587 | 16 | 1 | | 587 |
| 37+70 | TO | 69+92 | 3222 | 3222 | 112 | 7 | | 3222 |
| 73+10 | TO | 79+50 | 640 | 640 | 32 | 2 | | 640 |
| NORTHBOUND TOTAL | | | | 14606 | 560 | 34 | 7946 | 6660 |
| OUTLET LOCATIONS | | | | | | | 342 | 352 |
| SOUTHBOUND TOTAL | | | | 13224 | 672 | 39 | 7075 | 6149 |
| PROJECT TOTALS | | | | 27830 | 1232 | 73 | 15363 | 13161 |

NOTE: APPLICATION RATE FOR SEEDING AT HEADWALLS: FERTILIZER 90 LBS/ACRE, MULCH 2 TONS/ACRE

• F.A.P. RTE. 712, F.A.U. RTE. 7464