

MEDIAN SCHEDULE					CONCRETE MEDIAN SURFACE REMOVAL	CONCRET MEDIAN SURFACE, 4"	PAVEMENT REMOVAL *	PCC PAVEMENT, 10"	PAVEMENT FABRIC	CONCRETE MEDIAN, TYPE SB-6, 24	CONCRETE MEDIAN, TYPE SB-9, 24	COMBINATION CURB AND GUTTER REMOVAL	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9, 24	SUBBASE GRANULAR MAERIAL, TYPE B 4"	PRISMATIC CURB REFLECTOR	
#	STATION	TO	STATION	LENGTH	LOCATION	SO FT	SO FT	SO YD	SO YD	SO YD	SO FT	SO FT	FOOT	FOOT	SO YD	EACH
1	165+23	TO	168+40	317		1594.2		4.7	5.6	5.6	3082.3		626		348.0	34
2	169+00	TO	172+31	331		1519.1		4.6	5.2	5.2	3978.3		668		447.2	36
3	173+00	TO	176+84	384		2151.4		3.0	4.7	4.7	3816.4		773		428.7	38
4	177+47	TO	183+67	620		5299.9		2.0	261.8	261.8	6206.6		1253		951.4	57
5	184+86	TO	187+23	237												
6	188+05	TO	192+61	456		3591.3		5.0	185.4	185.4	4454.0		900		680.3	46
7	193+25	TO	197+37	412		1808.0		2.6	1.7	1.7	4967.1		832		553.6	42
8	198+53	TO	127+44	481		3536.1		1.3	155.4	155.4	4868.7		986		696.3	42
9	128+05	TO	130+91	286	S. NOSE	102.9		4.0	3.1	3.1	287.0		62		34.9	
					MIDDLE								15	15		27
					N. NOSE	20.2							65.6	15		7.3
10	131+51	TO	142+26	1075	S. NOSE	103.4		4.0	3.1	3.1	287.6		62		35.0	
					MIDDLE	1718.0	1718									72
					N. NOSE	20.5							66.2	15		7.4
11	142+84	TO	151+15	831	S. NOSE	103.4		4.0	3.1	3.1	287.6		62		35.0	
					MIDDLE								8	8		72
					N. NOSE	110.0		1.9	1.6	1.6	287.6	62		33.6		
12	152+14	TO	170+76	1862	S. NOSE	109.8		1.9	1.6	1.6	287.6		62		33.5	
					MIDDLE	21250.0	21250						377	377		119
					N. NOSE	104.3		1.3	0.2	0.2	286.7	62		32.0		
13	172+07	TO	176+20	413	S. NOSE	103.4		1.3	0.2	0.2	286.1		62		32.0	
					MIDDLE	523.0	523						13	13		37
					N. NOSE	20.7							66.4	15		7.4
14	176+65	TO	181+23	458	S. NOSE	104.9		1.3	0.2	0.2	287.6		62		32.1	
					MIDDLE	326.0	326						56	56		39
					N. NOSE	20.6							66.4	15		7.4
15	181+66	TO	186+09	443	S. NOSE	103.9		4.0	3.0	3.0	287.6		62		35.0	
					MIDDLE	1602.0	1602						72	72		38
					N. NOSE	20.6							66.4	15		7.4
16	186+78	TO	190+42	364	S. NOSE	103.1		4.1	3.1	3.1	287.6		62		35.0	
					MIDDLE	248.0	248						21	21		33
					N. NOSE	20.6							66.4	15		7.4
17	191+11	TO	194+95	384	S. NOSE	103.3		4.1	3.1	3.1	287.6		62		35.0	
					MIDDLE	510.0	510						33	33		35
					N. NOSE	20.6							66.4	15		7.4
18	195+60	TO	28+76	1388	S. NOSE	113.6		4.0	3.0	3.0	287.5		62		35.0	
					MIDDLE									113		89
19	29+84	TO	36+34	650												62
20	37+95	TO	43+30	535												46
21	43+92	TO	61+74	1782												108
22	62+74	TO	68+54	580												54
					TOTALS	47086	26177	59	645	645	31660	3624	7479	708	4565	1150

* MEDIANS #1-#9 PAVEMENT REMOVAL IS 10"

MEDIANS #9-#18 PAVEMENT REMOVAL IS 8"

F.A.P. RTE. 712, F.A.U. RTE. 7464

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ci:\pw_work\p\idot\steffenmk\d0271850\074537-sht-sch.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/22/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 11 OF 11 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	58-64-IRS, 126RS-2	Macon	69	25
			CONTRACT NO. 74537	
ILLINOIS FED. AID PROJECT				