



**TYPICAL SECTION AT MAILBOX TURNOUT**

NOTE: SEE STANDARD 406201 FOR MAILBOX TURNOUT DETAILS

**NOTES**

THE COST OF THE ASPHALT MATERIALS, AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROADS AND APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

THE COST OF EXCAVATION IS INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

IF THERE IS NOT EXISTING HOT-MIX ASPHALT SHOULDER THEN THE ENTRANCE TAPER STARTS AT THE EDGE OF EXISTING PAVEMENT.

THE COST OF THE BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B	HMA SURFACE REMOVAL, VARIABLE DEPTH
			TON	TON	SO YD
LT	166+03	CE			
LT	167+01	CE			
LT	168+72	CE			
LT	169+78	CE			
LT	172+65	CE			
LT	177+23	CE			
RT	184+19	PRA			
LT	184+20	PRA			
RT	187+62	CE	4.8		57.1
LT	190+31	CE			
LT	192+80	CE			
RT	192+80	CE	4.8		57.1
RT	194+73	CE	4.4		52.3
LT	195+33	CE			
RT	197+93	PRA	146		1783.4
LT	197+93	PRA	87		1063.7
RT	127+82	CE	7.8		93.2
RT	131+15	PRA	5		60.2
RT	142+50	PRA	4.9		58.3
RT	151+68	PRA	13.1		156.8
LT	151+68	PRA	13.7		162.9
RT	154+47	FE		5.4	
RT	168+43	FE		4.9	
LT	170+00	FE		3.8	
RT	171+26	FE		4	
LT	171+43	PE		4.3	
RT	184+14	FE		4.7	

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B	HMA SURFACE REMOVAL, VARIABLE DEPTH
			TON	TON	SO YD
RT	186+37	CE	4.8		
RT	190+69	CE	4.7		
RT	195+21	CE	7.3		
RT	197+53	CE	4.5		
RT	29+24	PRA	8.9		
RT	37+38	PRA			
LT	37+38	PRA			
LT	71+82	PRA			
RT	71+82	PRA			
RT	74+30	PE	1.7		
RT	75+20	PE	1.6		
RT	76+03	PE	1.4		
RT	76+73	PE	1.4		
RT	77+82	PE	1.5		
RT	78+76	PE	1.9		
TOTALS =			331	27	3545

FE=FIELD ENTRANCE PRA - PUBLIC ROAD APPROACH  
 PE=PRIVATE ENTRANCE MBT - MAILBOX TURNOUT  
 CE=COMMERCIAL ENTRANCE

• F.A.P. RTE. 712, F.A.U. RTE. 7464

FILE NAME =	USER NAME = steffenmk	DESIGNED - 08-03-99	REVISED - 03-13-07
ca:\pwork\pwork\stevfemk\d0271850\074537-sh1-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 3/22/2013	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**RURAL ENTRANCE SCHEDULE AND MAILBOX TURNOUT DETAILS  
WITH SHOULDERS**

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	58-64-IRS, 126RS-2	Macon	69	26
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74537	