

80% FED.
20% STATE

80% FED.
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004	0021	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	1584	1584		
* 70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	187	187		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13339	13339		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	795	795		
* 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	303	303		
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	438	438		
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	59	59		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	132	132		
* 73000100	WOOD SIGN SUPPORT	FOOT	72		72	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	187	187		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13339	13339		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	795	795		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004	0021	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	303	303		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	438	438		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	59	59		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	151	151		
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1		1	
* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	1712		1712	
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	63		63	
* 81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	56		56	
* 81400100	HANDHOLE	EACH	1		1	
* 81500100	GULFBOX JUNCTION	EACH	5		5	
* 85800100	FLASHER CONTROLLER	EACH	1		1	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1985		1985	
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	75		75	

* SPECIALTY ITEM

FILE NAME: c:\pwork\pvidnt\stefrenk\00309111\071567.sht-soq.dgn	USER NAME: stefrenk	DESIGNED -	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 116	SECTION 126N	COUNTY EDWARDS	TOTAL SHEETS 71	SHEET NO. 6
PLOT SCALE: 1/8"=1'-0"	PLOT DATE: 3/18/2013	DRAWN -	REVISIONS -		SCALE: N/A	SHEET 3 OF 4 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
		CHECKED -	REVISIONS -									
		DATE -	REVISIONS -									

26