

DRAINAGE SCHEDULE

LOCATION	PIPE CULVERT REMOVAL FOOT	PRECAST CONCRETE BOX CULVERTS 2' X 2' (SPECIAL) FOOT	BOX CULVERT END SECTIONS, CULVERT NO. 1 EACH	BOX CULVERT END SECTIONS, CULVERT NO. 2 EACH	PIPE CULVERTS, CLASS A, TYPE 1 18" FOOT	PIPE CULVERTS, CLASS D, TYPE 1 18" FOOT	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" EACH	METAL END SECTIONS 18" EACH
LT 811+97	0.0	24.0	1.0	0.0	0.0	0.0	0.0	0.0
RT 811+97	0.0	12.0	1.0	0.0	0.0	0.0	0.0	0.0
LT 815+46	0.0	0.0	0.0	0.0	32.0	0.0	2.0	0.0
LT 823+76	30.0	0.0	0.0	0.0	0.0	32.0	0.0	2.0
LT 823+80	0.0	18.0	0.0	1.0	0.0	0.0	0.0	0.0
RT 823+80	0.0	18.0	0.0	1.0	0.0	0.0	0.0	0.0
RT 823+80	30.0	0.0	0.0	0.0	0.0	32.0	0.0	2.0
LT 1018+07	37.0	0.0	0.0	0.0	40.0	0.0	2.0	0.0
TOTALS	97.0	72.0	2.0	2.0	72.0	64.0	4.0	4.0

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT
RT 808+60	6.0	
RT 808+79	6.0	
LT 815+22		27.0
LT 816+54		36.0
LT 810+00 TO 814+90	294.1	290.9
LT 820+00 TO 822+50	206.3	
LT 822+50 TO 823+00	110.0	
TOTAL	622.0	354.0

SEEDING SCHEDULE

STATION TO STATION	SEEDING, CLASS 2 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	NITROGEN FERTILIZER NURTIENT POUND	PHOSPHORUS FERTILIZER NURTIENT POUND	POTASSIUM FERTILIZER NURTIENT POUND	MULCH, METHOD 2 ACRE	AGRICULTURAL GROUND LIMESTONE TON
IL 130							
808+00.0 TO 826+00.0	1.4	143.0	128.7	128.7	128.7	1.4	2.9
WEST SALEM ROAD							
1017+00.0 TO 2+00.0	0.2	19.0	17.1	17.1	17.1	0.2	0.4
TOTAL =	1.7	162.0	146.0	146.0	146.0	1.7	3.0

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EARTH FILL CU YD	EARTHWORK BALANCE, WASTE (+) OR SHORTAGE (-) CU YD
IL 130				
808+50.00 TO 826+00.00	4816.6	3612.5	1032.4	2580.1
WEST SALEM ROAD				
1017+00.00 TO 2+00.00	611.0	458.3	41.2	417.1
TOTALS =	5428.0	4071.0	1074.0	2997.0