

WIDENING SCHEDULE

STATION TO STATION	LOCATION	PORTLAND CEMENT CONCRETE BASE COURSE, 10"	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10"	PAVEMENT FABRIC	PAVED SHOULDER REMOVAL
	CORNER	SO YD	SO YD	SO YD	SO YD
S. N. 013-0002 (EB)					
	NE		141	141	141
	NW		186	186	186
	SE	197		197	197
	SW	268		268	268
S. N. 013-0003 (WB)					
	NE	268.4		268.4	268.4
	NW	197.0		197.0	197.0
	SE		189.1	189.1	189.1
	SW		142.2	142.2	142.2
TOTALS		931	658	1589	1589

PAVING SCHEDULE

STATION TO STATION	HOT MIX ASPHALT SURFACE COURSE, MIX D, N90	HOT MIX ASPHALT SURFACE REMOVAL 1 1/2"	TEMPORARY RAMP
	TON	SO YD	SO YD
S. N. 013-0002 (EB)			
	EAST	3.75	43
	WEST	3.75	43
S. N. 013-0003 (WB)			
	EAST	3.75	43
	WEST	3.75	43
TOTALS	15	172	107

TRAFFIC CONTROL DEVICES SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	FOOT	FOOT	EACH	EACH
S. N. 013-0002 (EB)	370.0	370.0	1.0	1.0
S. N. 013-0003 (WB)	370.0	370.0	1.0	1.0
TOTALS	740.0	740.0	2.0	2.0

PAVEMENT MARKING SCHEDULE

STATION TO STATION	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING 4"	TEMPORARY PAVEMENT MARKING 6"	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	FOOT	SO FT	FOOT	FOOT	SO FT
S. N. 013-0002 (EB)						
798+55 TO 805+05	1300	163	478	1300	163	117
S. N. 013-0003 (WB)						
798+55 TO 805+05	1300	163	478	1300	163	117
TOTALS	2600	325	956	2600	325	234