

LOCATION 11
I-70 & US 51/N KENNEDY BLVD
FAYETTE COUNTY

USE DETAIL "B" (EB EXIT RAMP)
USE DETAIL "A" (WB EXIT RAMP)

SIGNS

BILL OF MATERIALS

SIGN TYPES BY LOCATION	UNITS	EB EXIT RAMP	WB EXIT RAMP
FREEWAY ENTRANCE (D13-3) 48" x 30"	EACH	0	0
DIRECTIONAL ARROW (M6-2a) 21" x 15"	EACH	0	0
STOP SIGN (R1-1) 48" x 48"	EACH	0	3
NO RIGHT TURN (R3-1) 36" x 36"	EACH	1	1
NO LEFT TURN (R3-2) 36" x 36"	EACH	2	2
KEEP RIGHT (R4-7) 40" x 60"	EACH	0	0
DO NOT ENTER (R5-1) 36" x 36"	EACH	0	1
DO NOT ENTER (R5-1) 48" x 48"	EACH	2	2
WRONG WAY (R5-1a) 42" x 30"	EACH	4	4
ONE WAY (R6-1 - LEFT) 54" x 18"	EACH	2	3
ONE WAY (R6-1 - RIGHT) 54" x 18"	EACH	2	3
RETROREFLECTIVE SIGN SUPPORT PANEL (RED) 2" x 60"	EACH	6	7
CHEVRON (W1-8 - YELLOW) 30" x 36"	EACH	7	8

PAY ITEM DESCRIPTION	UNITS	EB EXIT RAMP	WB EXIT RAMP
SIGN PANEL - TYPE 1	SQ FT	133.0	157.1
SIGN PANEL - TYPE 2	SQ FT	32.0	80.0
REMOVE SIGN PANEL - TYPE 1	SQ FT	43.0	51.0
REMOVE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
RELOCATE SIGN PANEL - TYPE 1	SQ FT	6.0	0.0
RELOCATE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
WOOD SIGN SUPPORT	FOOT	213.0	259.0
REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	4.0	6.0
THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	55.5	55.5
THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	150.0	150.0
THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100.0	50.0
THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40.0	40.0
MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	0.0	0.0
PAVEMENT MARKING REMOVAL	SQ FT	120.0	90.0
WOOD SIGN SUPPORT, SPECIAL	FOOT	15.0	33.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BILL OF MATERIALS LOCATION 11			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ct:\pw\work\p\dot\steffenmk\d0339033\074614-Int_Signs.dgn		DRAWN -	REVISED -								44	15		
Default	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -					SCALE:	SHEET	OF SHEETS	STA.	TO STA.	CONTRACT NO. 74614	
	PLOT DATE = 3/28/2013	DATE -	REVISED -										ILLINOIS FED. AID PROJECT	