

LOCATION 18

I-70 & SPRING CREEK RD - EFFINGHAM COUNTY

USE DETAIL "A"

SIGNS

SIGN TYPES BY LOCATION	UNITS	EB EXIT RAMP	WB EXIT RAMP
FREEWAY ENTRANCE (D13-3) 48" x 30"	EACH	0	0
DIRECTIONAL ARROW (M6-2a) 21" x 15"	EACH	0	0
STOP SIGN (R1-1) 48" x 48"	EACH	3	3
NO RIGHT TURN (R3-1) 36" x 36"	EACH	1	1
NO LEFT TURN (R3-2) 36" x 36"	EACH	2	2
KEEP RIGHT (R4-7) 40" x 60"	EACH	0	0
DO NOT ENTER (R5-1) 36" x 36"	EACH	1	1
DO NOT ENTER (R5-1) 48" x 48"	EACH	2	2
WRONG WAY (R5-1a) 42" x 30"	EACH	4	4
ONE WAY (R6-1 - LEFT) 54" x 18"	EACH	3	3
ONE WAY (R6-1 - RIGHT) 54" x 18"	EACH	3	3
RETROREFLECTIVE SIGN SUPPORT PANEL (RED) 2" x 60"	EACH	7	7
CHEVRON (W1-8 - YELLOW) 30" x 36"	EACH	3	3

BILL OF MATERIALS

PAY ITEM DESCRIPTION	UNITS	EB EXIT RAMP	WB EXIT RAMP
SIGN PANEL - TYPE 1	SQ FT	119.6	119.6
SIGN PANEL - TYPE 2	SQ FT	80.0	80.0
REMOVE SIGN PANEL - TYPE 1	SQ FT	63.0	63.0
REMOVE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
RELOCATE SIGN PANEL - TYPE 1	SQ FT	0.0	0.0
RELOCATE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
WOOD SIGN SUPPORT	FOOT	223.0	223.0
REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	7.0	7.0
THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	0.0	0.0
THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	55.5	55.5
MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	150.0	150.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	50.0	50.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	40.0	40.0
PAVEMENT MARKING REMOVAL	SQ FT	15.0	15.0
WOOD SIGN SUPPORT, SPECIAL	FOOT	0.0	0.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BILL OF MATERIALS LOCATION 18			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\steffenmk\d0339033\0774614-Int_Signs.dgn		DRAWN -	REVISED -								44	22
Default	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -		SCALE:	SHEET	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 74614	
	PLOT DATE = 3/28/2013	DATE -	REVISED -									