

**LOCATION 28**  
**I-72 & IL 48 - MACON COUNTY**

**USE DETAIL "E" (EB EXIT RAMP)**  
**USE DETAIL "D" (WB EXIT RAMP)**

**SIGNS**

**BILL OF MATERIALS**

SIGN TYPES BY LOCATION	UNITS	EB EXIT RAMP	WB EXIT RAMP
FREEWAY ENTRANCE (D13-3) 48" x 30"	EACH	1	1
DIRECTIONAL ARROW (M6-2a) 21" x 15"	EACH	1	1
STOP SIGN (R1-1) 48" x 48"	EACH	0	2
NO RIGHT TURN (R3-1) 36" x 36"	EACH	0	0
NO LEFT TURN (R3-2) 36" x 36"	EACH	0	0
KEEP RIGHT (R4-7) 40" x 60"	EACH	1	1
DO NOT ENTER (R5-1) 36" x 36"	EACH	0	1
DO NOT ENTER (R5-1) 48" x 48"	EACH	2	2
WRONG WAY (R5-1a) 42" x 30"	EACH	4	4
ONE WAY (R6-1 - LEFT) 54" x 18"	EACH	1	2
ONE WAY (R6-1 - RIGHT) 54" x 18"	EACH	1	2
RETROREFLECTIVE SIGN SUPPORT PANEL (RED) 2" x 60"	EACH	6	7
CHEVRON (W1-8 - YELLOW) 30" x 36"	EACH	9	8

PAY ITEM DESCRIPTION	UNITS	EB EXIT RAMP	WB EXIT RAMP
SIGN PANEL - TYPE 1	SQ FT	116.4	125.5
SIGN PANEL - TYPE 2	SQ FT	58.7	90.7
REMOVE SIGN PANEL - TYPE 1	SQ FT	36.2	54.2
REMOVE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
RELOCATE SIGN PANEL - TYPE 1	SQ FT	6.2	6.2
RELOCATE SIGN PANEL - TYPE 2	SQ FT	0.0	0.0
WOOD SIGN SUPPORT	FOOT	263.0	286.0
REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	4.0	6.0
THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	67.0	67.0
THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12.0	12.0
THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	150.0	150.0
THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	150.0	50.0
THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40.0	40.0
MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	0.0	0.0
MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	0.0	0.0
PAVEMENT MARKING REMOVAL	SQ FT	330.0	230.0
WOOD SIGN SUPPORT, SPECIAL	FOOT	0.0	0.0

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>BILL OF MATERIALS LOCATION 28</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
ct:\pw\work\p\dot\steffenmk\d0339033\074614-Int_Signs.dgn		DRAWN -	REVISED -								44	32			
Default	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -					SCALE:	SHEET	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 74614	
	PLOT DATE = 3/28/2013	DATE -	REVISED -												