

# LOCATION 29

## I-72 & CO HWY 25 - MACON COUNTY

# USE DETAIL "A"

### SIGNS

| SIGN TYPES BY LOCATION                            | UNITS | EB EXIT RAMP | WB EXIT RAMP |
|---|-------|--------------|--------------|
| FREEWAY ENTRANCE (D13-3) 48" x 30"                | EACH  | 0            | 0            |
| DIRECTIONAL ARROW (M6-2a) 21" x 15"               | EACH  | 0            | 0            |
| STOP SIGN (R1-1) 48" x 48"                        | EACH  | 3            | 3            |
| NO RIGHT TURN (R3-1) 36" x 36"                    | EACH  | 1            | 1            |
| NO LEFT TURN (R3-2) 36" x 36"                     | EACH  | 2            | 2            |
| KEEP RIGHT (R4-7) 40" x 60"                       | EACH  | 0            | 0            |
| DO NOT ENTER (R5-1) 36" x 36"                     | EACH  | 1            | 1            |
| DO NOT ENTER (R5-1) 48" x 48"                     | EACH  | 2            | 2            |
| WRONG WAY (R5-1a) 42" x 30"                       | EACH  | 4            | 4            |
| ONE WAY (R6-1 - LEFT) 54" x 18"                   | EACH  | 3            | 3            |
| ONE WAY (R6-1 - RIGHT) 54" x 18"                  | EACH  | 3            | 3            |
| RETROREFLECTIVE SIGN SUPPORT PANEL (RED) 2" x 60" | EACH  | 7            | 7            |
| CHEVRON (W1-8 - YELLOW) 30" x 36"                 | EACH  | 4            | 4            |

### BILL OF MATERIALS

| PAY ITEM DESCRIPTION                                     | UNITS | EB EXIT RAMP | WB EXIT RAMP |
|--|-------|--------------|--------------|
| SIGN PANEL - TYPE 1                                      | SQ FT | 127.1        | 127.1        |
| SIGN PANEL - TYPE 2                                      | SQ FT | 80.0         | 80.0         |
| REMOVE SIGN PANEL - TYPE 1                               | SQ FT | 57.0         | 63.0         |
| REMOVE SIGN PANEL - TYPE 2                               | SQ FT | 0.0          | 0.0          |
| RELOCATE SIGN PANEL - TYPE 1                             | SQ FT | 0.0          | 0.0          |
| RELOCATE SIGN PANEL - TYPE 2                             | SQ FT | 0.0          | 0.0          |
| WOOD SIGN SUPPORT  | FOOT  | 224.0        | 224.0        |
| REMOVE GROUND MOUNTED SIGN SUPPORT                       | EACH  | 7.0          | 7.0          |
| THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS     | SQ FT | 0.0          | 0.0          |
| THERMOPLASTIC PAVEMENT MARKING - LINE 4"                 | FOOT  | 0.0          | 0.0          |
| THERMOPLASTIC PAVEMENT MARKING - LINE 8"                 | FOOT  | 0.0          | 0.0          |
| THERMOPLASTIC PAVEMENT MARKING - LINE 12"                | FOOT  | 0.0          | 0.0          |
| THERMOPLASTIC PAVEMENT MARKING - LINE 24"                | FOOT  | 0.0          | 0.0          |
| MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 55.5         | 55.5         |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 4"             | FOOT  | 0.0          | 0.0          |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 8"             | FOOT  | 150.0        | 150.0        |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 12"            | FOOT  | 50.0         | 50.0         |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 24"            | FOOT  | 40.0         | 40.0         |
| PAVEMENT MARKING REMOVAL                                 | SQ FT | 15.0         | 15.0         |
| WOOD SIGN SUPPORT, SPECIAL                               | FOOT  | 15.0         | 15.0         |

|             |   |            |           |   |  |           |         |        |                           |           |                    |      |
|-------------|---|------------|-----------|---|--|-----------|---------|--------|---------------------------|-----------|--------------------|------|
| FILE NAME = | USER NAME = steffenmk                                     | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>BILL OF MATERIALS<br/>LOCATION 29</b> | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS              | SHEET NO. |                    |      |
| Default     | et:\pw\work\p\dot\steffenmk\d0339033\074614-Int Signs.dgn | DRAWN -    | REVISED - |   |  |           |         |        |                           |           |                    |      |
|             | PLOT SCALE = 40.0000' / in.                               | CHECKED -  | REVISED - |   |  | SCALE:    | SHEET   | OF     | SHEETS                    | STA.      | TO                 | STA. |
|             | PLOT DATE = 3/28/2013                                     | DATE -     | REVISED - |   |  |           |         |        | ILLINOIS FED. AID PROJECT |           | CONTRACT NO. 74614 |      |