

SUMMARY OF QUANTITIES

M2A0,01 M2A0,01 M2A0,02 07CDL01 M2A0,01 07ADL01

CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE						
				80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 20% STATE	80% STATE 20% CITY	80% FEDERAL 20% STATE	100% STATE	
				ROADWAY 0003 URBAN	TRAFFIC SIGNALS 0021 ILLINOIS AVE	TRAFFIC SIGNALS 0021 ALL OTHERS	BICYCLE/PEDS 0028	MINOR STRUCTURES 0040 S. N. 067-2427 PEDESTRIAN CULVERT	TRAFFIC SIGNS 0021 URBAN	
4400600	SIDEWALK REMOVAL	SQ FT	1164	1164						
44003100	MEDIAN REMOVAL	SQ FT	2459	2459						
44004250	PAVED SHOULDER REMOVAL	SQ YD	32164	32164						
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	8	8						
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	17	17						
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	78	78						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	38423	38423						
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	2683	802			1881			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1997	1997						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	28786	28786						
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	1981	1981						
48203039	HOT-MIX ASPHALT SHOULDERS, 10 1/2"	SQ YD	195	195						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	451	451						
50102400	CONCRETE REMOVAL	CU YD	81.6	81.6						

• SPECIALTY ITEM

LAST SAVED: 1/25/2013 5:31:20 PM
 PEN TABLE: 1/25/2013 5:31:20 PM
 PLOT DRIVER: 1/25/2013 5:31:20 PM

FILE NAME =	USER NAME = berachmann	DESIGNED -	REVISED -
I:\1801100\Phase II - 76817\Cad\1\Plans\993.0876017-act-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**HORNER &
SHIRIN, INC.**
ENGINEERS

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF 25 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	68-WRS-1	MONROE	760	8
CONTRACT NO. 76817				
ILLINOIS FED. AID PROJECT				