CURB & GUTTER / MEDIAN

LOCATION	STATION	CONCRETE CURB, TYPE B	COMBINATION CURB & GUTTER, TYPE B-6.06	COMBINATION CURB & GUTTER, TYPE B-6.12	COMBINATION CURB & GUTTER, TYPE B-6.12 (SPECIAL)	COMBINATION CURB & GUTTER, TYPE B-6.24	COMBINATION CURB & GUTTER, TYPE B-9.12 (SPECIAL)	COMBINATION CURB & GUTTER, TYPE B-9.24	COMBINATION CURB & GUTTER, TYPE M-2.12	COMBINATION CURB & GUTTER, TYPE M-2.12 (SPECIAL)	CONCRETE MEDIAN SURFACE, 4"	CONCRETE MEDIAN, TYPE SB (SPECIAL)	PROTECTIVE COAT	PAINT CURB	PRISMATIC CURB REFLECTOR
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ YD	FOOT	EACH
IL ROUTE 3	2018+30.00 40.00 LT TO 2020+66.43 40.00 LT					236.5							79		
	2018+96.00 40.00 RT TO 2054+72.69 38.00 RT							3586.5					1275		
	2030+16.80 31.00 LT TO 2041+29.33 31.00 LT					1100.5							367		
	2054+72.69 38.00 RT TO 2054+80.33 55.11 RT					19.5							7		
	2055+19.45 55.00 RT TO 2058+11.21 50.26 RT					311.5							104		
	2058+19.99 39.42 LT TO 2058+61.91 53.03 LT					44.5							15		
	2059+27.54 72.30 RT TO 2060+06.63 40.00 RT					86.0							29		
	2059+84.18 66.02 LT TO 2065+27.97 56.95 LT					660.5							220		
	2060+06.63 40.00 RT TO 2070+60.46 35.00 RT							1054.5					375		
	2068+77.18 34.98 LT TO 2072+96.78 35.00 LT					461.5							154		
	2070+60.46 35.00 RT TO 2071+19.46 35.00 RT					75.0							25		
	2071+19.46 35.00 RT TO 2076+22.09 39.20 RT							502.5					179		
	2076+22.09 39.20 RT TO 2076+80.87 40.00 RT					75.0							25		
	2076+80.87 40.00 RT TO 2082+66.54 51.43 RT							586.5					209		
	2083+04.86 39.42 LT TO 2083+33.34 46.88 LT					29.5							10		
	2083+53.17 55.33 RT TO 2084+10.77 40.00 RT					61.0							20		
	2084+10.77 40.00 RT TO 2089+64.07 40.00 RT							553.5					197		
	2084+36.06 60.87 LT TO 2084+61.99 39.42 LT					35.0							12		
	2099+76.90 51.42 RT TO 2100+06.75 67.15 RT					33.5							11		
	2101+12.02 60.79 RT TO 2101+43.73 42.63 RT					36.0							12		
	2101+43.73 42.63 RT TO 2118+77.70 51.00 RT							1713.0					609		
	2130+39.45 32.00 RT TO 2134+97.67 32.00 RT							458.0					163		
	2134+97.67 32.00 RT TO 2135+63.00 32.00 RT					94.5							32		
	2135+63.00 32.00 RT TO 2138+92.12 32.00 RT							329.0					117		
	2138+92.12 32.00 RT TO 2139+58.12 32.00 RT					95.0							32		
	2139+58.12 32.00 RT TO 2151+24.86 53.41 RT							1181.0					420		
	2152+11.36 55.33 RT TO 2154+48.13 32.65 RT							242.0					86		
	2154+48.13 32.65 RT TO 2154+99.19 33.36 RT					51.0							17		
	2154+99.19 33.36 RT TO 2157+73.47 72.78 RT							281.0					100		
	2155+84.29 6.04 LT TO 2158+14.60 9.74 LT											1549	172	116	19
	2157+84.91 46.44 LT TO 2158+35.33 61.48 LT					53.0							18		
	2159+36.33 73.22 RT TO 2169+37.67 56.10 RT					1078.0							359		
	2159+39.02 12.00 RT TO 2167+10.19 11.18 LT											6163	685	116	70
	2159+51.52 71.65 LT TO 2163+05.15 56.00 LT					424.5					14		144		
	2162+83.28 111.58 LT TO 2170+68.98 33.01 LT					955.0							318		
S LIBRARY STREET	19+20.29 18.83 RT TO 19+55.90 17.78 RT					116.0					444		88	98	14
	20+44.00 17.00 LT TO 20+62.83 16.00 LT					58.5					166		38	55	13
SOUTHVIEW DRIVE	50+39.40 33.59 LT TO 50+74.87 15.88 LT					41.5							14		
	50+40.23 33.17 RT TO 50+74.94 15.91 RT					44.5							15		
IL ROUTE 156	4+44.37 29.39 LT TO 5+01.40 25.22 LT					62.0							21		
	4+70.38 1.63 RT TO 5+17.03 12.26 RT				96.5						276		52	96	
	5+01.40 25.22 LT TO 5+18.43 33.81 LT								44.5				8		
	5+06.61 28.15 LT TO 5+08.21 54.72 LT	30.0											3		
	5+14.98 1.63 LT TO 5+17.03 12.26 RT			15.5									3		13
	5+17.32 32.02 LT TO 8+90.33 56.65 LT					585.0							195		
	5+38.37 3.84 RT TO 6+25.37 2.53 RT								273.5				49	270	
	5+54.88 3.59 RT TO 6+08.87 2.78 RT						169.5						41	166	
	6+25.24 56.18 RT TO 9+51.66 50.95 RT					419.0							140		
	6+46.73 2.40 LT TO 6+47.71 18.11 RT			21.0									5		
	6+46.73 2.40 LT TO 9+26.23 1.67 LT				563.0						1823		328	129	28
	10+17.21 37.99 LT TO 10+53.43 22.00 LT					58.5					256		48	75	13
	10+21.65 41.66 LT TO 10+52.31 23.80 LT			35.5									8		
	10+39.77 59.61 LT TO 12+70.50 20.17 LT					238.0							79		
	10+66.67 54.62 RT TO 12+68.66 19.73 RT					209.5							70		
LAKEVIEW DRIVE	90+71.99 39.28 LT TO 90+94.66 23.24 LT					28.5							10		
	90+83.81 3.79 LT TO 90+85.65 9.73 RT			14.0									3		
	90+83.81 3.79 LT TO 91+72.88 2.93 RT				143.5						461		83	181	16
	90+94.66 23.24 LT TO 92+14.37 19.08 LT	120.0								123.5			35		
	91+34.56 1.95 RT TO 91+72.88 2.93 RT	39.0							44.0				12		
	92+14.37 19.07 LT TO 92+51.12 71.87 LT					70.0							23		
	92+91.04 71.66 LT TO 93+38.00 19.58 LT					79.5							27		
ILLINOIS AVENUE	17+19.19 34.50 LT TO 17+36.27 18.79 LT					25.5							9		
	18+00.00 18.69 LT TO 19+09.85 54.63 LT					119.0							40		
	19+00.00 18.48 RT TO 19+63.66 33.98 RT					68.0							23		
	19+18.96 24.00 LT TO 19+47.71 25.00 LT					82.0					183		47	57	15
	20+49.47 24.97 LT TO 23+89.90 16.60 LT					341.5							114		
	20+52.84 26.20 RT TO 20+72.66 24.00 RT					57.5					94		29	40	13
	20+80.46 56.02 RT TO 23+89.55 19.13 RT					319.0							106		
COLUMBIA AVENUE	30+37.14 32.95 RT TO 30+61.66 32.00 RT					56.0					237		45	69	16
	30+38.45 11.13 LT TO 30+64.96 10.00 LT					55.0					197		40	66	11
	30+40.52 55.92 RT TO 30+60.94 33.54 RT		30.5										5		
	30+42.88 30.85 LT TO 30+64.05 11.68 LT		28.5										5		
	30+62.83 42.10 LT TO 31+13.45 19.50 LT					57.0							19		
	30+65.99 59.79 RT TO 31+96.84 19.75 RT					140.5							47		
	SUBTOTAL	189.0	59.0	86.0	803.0	9348.0	169.5	10487.5	362.0	123.5	4151	7712	8524	1534	241

LAST SAVED = 1/25/2013
PEN TABLE = VBi-Half.tbl
PLOT DRIVER = pdfNOLAYERS=.pltcfg

FILE NAME = I:\100110_Phase II - 76817\Cad\T_Plans\005_D876817-sht-schedule.dgn	USER NAME = beriechmann	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/25/2013 3:28:49 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HORNER & SHIFRIN, INC. ENGINEERS

SCALE: NONE

SCHEDULES OF QUANTITIES
CURB & GUTTER / MEDIAN

SHEET NO. 9 OF 32 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	68-WRS-1	MONROE	760	57

CONTRACT NO. 76817

ILLINOIS FED. AID PROJECT