

PIPE UNDERDRAINS

| STATION | SIDE | PIPE UNDERDRAINS 4" | | CONCRETE HEADWALLS FOR PIPE DRAINS | PIPE UNDERDRAIN REMOVAL | STATION | SIDE | PIPE UNDERDRAINS 4" | | CONCRETE HEADWALLS FOR PIPE DRAINS | PIPE UNDERDRAIN REMOVAL | STATION | SIDE | PIPE UNDERDRAINS 4" | | CONCRETE HEADWALLS FOR PIPE DRAINS | PIPE UNDERDRAIN REMOVAL | |
|--------------------------|------|---------------------|--------------|------------------------------------|-------------------------|--------------------------|------|---------------------|--------------|------------------------------------|-------------------------|--------------------------|------|---------------------|--------------|------------------------------------|-------------------------|--|
| | | 4" | 4" (SPECIAL) | | | | | 4" | 4" (SPECIAL) | | | | | 4" | 4" (SPECIAL) | | | |
| | | FOOT | FOOT | | | | | FOOT | FOOT | | | | | FOOT | FOOT | | | |
| IL ROUTE 3 | | | | | | IL ROUTE 3 | | | | | | IL ROUTE 3 | | | | | | |
| 1995+76.51 TO 2000+50.00 | LT | 473 | 22 | 1 | | 2047+50.00 TO 2051+50.00 | RT | 400 | 6 | | | 2123+50.00 TO 2128+00.00 | RT | 450 | 19 | 1 | | |
| 1995+76.51 TO 2000+50.00 | RT | 473 | 18 | 1 | | 2048+06.63 | LT | | | | 21 | 2123+50.00 TO 2128+50.00 | LT | 500 | 18 | 1 | | |
| 1995+76.51 TO 2047+67.25 | RT | | | | 5191 | 2051+50.00 TO 2055+50.00 | LT | 400 | 19 | 1 | | 2125+41.39 | LT | | | | 19 | |
| 1995+76.51 TO 2058+01.24 | LT | | | | 6225 | 2051+50.00 TO 2055+50.00 | RT | 400 | 6 | | | 2125+45.44 | LT | | | | 24 | |
| 1996+82.74 | RT | | | | | 2052+94.00 | LT | | | | 27 | 2128+00.00 TO 2129+00.00 | RT | 100 | 18 | 1 | | |
| 1996+86.60 | LT | | | | 20 | 2055+50.00 TO 2058+00.00 | LT | 250 | 19 | 1 | | 2128+50.00 TO 2131+00.00 | LT | 250 | 38 | 2 | | |
| 2000+50.00 TO 2005+50.00 | LT | 500 | 19 | 1 | | 2055+50.00 TO 2056+00.00 | RT | 50 | | | | 2129+00.00 TO 2130+85.00 | RT | 185 | | | | |
| 2000+50.00 TO 2005+50.00 | RT | 500 | 17 | 1 | | 2056+00.00 TO 2056+50.00 | RT | 50 | | | | 2130+84.21 | LT | | | | 23 | |
| 2001+97.19 | RT | | | | 20 | 2056+50.00 TO 2057+00.00 | RT | 50 | | | | 2130+85.00 TO 2131+00.00 | RT | 15 | | | | |
| 2002+00.15 | LT | | | | 20 | 2057+00.00 TO 2057+50.00 | RT | 50 | | | | 2130+91.55 | LT | | | | 23 | |
| 2005+50.00 TO 2010+50.00 | LT | 500 | 19 | 1 | | 2060+20.00 TO 2065+00.00 | LT | 480 | 6 | | | 2130+93.17 | LT | | | | 19 | |
| 2005+50.00 TO 2010+50.00 | RT | 500 | 17 | 1 | | 2060+50.00 TO 2065+00.00 | RT | 450 | 8 | | | 2130+99.35 | LT | | | | 19 | |
| 2006+48.60 | RT | | | | 20 | 2065+00.00 TO 2068+00.00 | LT | 300 | 19 | 1 | | 2131+00.00 TO 2131+50.00 | RT | 50 | | | | |
| 2006+49.77 | LT | | | | 20 | 2065+00.00 TO 2069+00.00 | RT | 400 | 8 | | | 2131+50.00 TO 2132+00.00 | RT | 50 | | | | |
| 2010+49.37 | LT | | | | 19 | 2067+74.45 TO 2157+97.99 | RT | | | | 9024 | 2132+00.00 TO 2133+00.00 | RT | 100 | | | | |
| 2010+50.00 | RT | | | | 19 | 2067+76.07 TO 2157+92.17 | LT | | | | 9016 | 2131+00.00 TO 2133+00.00 | LT | 200 | 19 | 1 | | |
| 2010+50.00 TO 2014+00.00 | LT | 350 | 18 | 1 | | 2068+00.00 TO 2072+00.00 | LT | 400 | 8 | | | 2133+00.00 TO 2135+50.00 | LT | 250 | 19 | 1 | | |
| 2010+50.00 TO 2014+50.00 | RT | 400 | 21 | 1 | | 2069+00.00 TO 2074+00.00 | RT | 500 | 8 | | | 2133+00.00 TO 2135+66.00 | RT | 266 | | | | |
| 2014+41.48 | LT | | | | 20 | 2072+00.00 TO 2076+00.00 | LT | 400 | 21 | 1 | | 2135+50.00 TO 2140+50.00 | LT | 500 | | | | |
| 2014+52.36 | RT | | | | 18 | 2072+97.38 | LT | | | | 21 | 2135+53.43 | LT | | | | 17 | |
| 2015+90.00 TO 2018+40.00 | LT | 250 | 23 | 1 | | 2074+00.00 TO 2076+00.00 | RT | 200 | 8 | | | 2135+66.00 TO 2138+00.00 | RT | 234 | | | | |
| 2016+25.00 TO 2019+00.00 | RT | 275 | 31 | 1 | | 2076+00.00 TO 2079+00.00 | LT | 300 | 40 | 2 | | 2138+00.00 TO 2140+50.00 | RT | 250 | | | | |
| 2019+49.73 | RT | | | | 21 | 2076+00.00 TO 2079+00.00 | RT | 300 | 16 | | | 2140+50.00 TO 2145+50.00 | LT | 500 | 19 | 1 | | |
| 2019+50.00 TO 2023+00.00 | LT | 350 | 38 | 2 | | 2079+00.00 TO 2082+30.00 | RT | 330 | | | | 2140+50.00 TO 2145+50.00 | RT | 500 | | | | |
| 2019+50.17 | LT | | | | 24 | 2079+00.00 TO 2082+70.00 | LT | 370 | | | | 2145+36.15 | LT | | | | 21 | |
| 2019+65.00 TO 2023+00.00 | RT | 335 | 16 | | | 2084+49.74 | LT | | | | 17 | 2145+50.00 TO 2148+00.00 | LT | 250 | 19 | 1 | | |
| 2021+94.74 | LT | | | | 21 | 2085+00.00 TO 2089+00.00 | LT | 400 | 8 | | | 2145+50.00 TO 2148+00.00 | RT | 250 | | | | |
| 2022+00.57 | RT | | | | 19 | 2084+66.25 | LT | | | | 20 | 2148+00.00 TO 2151+00.00 | LT | 300 | 18 | 1 | | |
| 2022+01.27 | LT | | | | 21 | 2084+50.00 TO 2088+50.00 | RT | 400 | 14 | 1 | | 2148+00.00 TO 2151+00.00 | RT | 300 | | | | |
| 2022+08.89 | RT | | | | 20 | 2089+00.00 TO 2093+50.00 | LT | 450 | 8 | | | 2152+25.00 TO 2154+00.00 | LT | 175 | 18 | 1 | | |
| 2023+00.00 TO 2023+65.00 | LT | 65 | | | | 2088+50.00 TO 2093+50.00 | RT | 500 | 18 | 1 | | 2153+00.00 TO 2153+50.00 | RT | 50 | | | | |
| 2023+00.00 TO 2025+00.00 | RT | 200 | | | | 2093+50.00 TO 2097+50.00 | LT | 400 | 20 | 1 | | 2153+50.00 TO 2154+00.00 | RT | 50 | | | | |
| 2024+70.00 TO 2029+50.00 | LT | 480 | 21 | 1 | | 2093+50.00 TO 2098+50.00 | RT | 500 | 19 | 1 | | 2154+00.00 TO 2154+36.00 | RT | 36 | | | | |
| 2025+00.00 TO 2030+00.00 | RT | 500 | 8 | | | 2094+49.12 | LT | | | | 18 | 2154+35.63 | LT | | | | 22 | |
| 2025+49.50 | LT | | | | 19 | 2097+50.00 TO 2099+75.00 | LT | 225 | 18 | 1 | | 2155+25.00 TO 2157+50.00 | LT | 225 | 18 | 1 | | |
| 2025+54.27 | RT | | | | 19 | 2099+75.00 TO 2103+00.00 | LT | 325 | 19 | 1 | | 2154+36.00 TO 2155+73.00 | RT | 137 | | | | |
| 2029+49.09 | LT | | | | 21 | 2098+50.00 TO 2099+50.00 | RT | 100 | 19 | 1 | | 2155+73.00 TO 2156+50.00 | RT | 77 | | | | |
| 2029+49.10 | RT | | | | 20 | 2102+00.00 TO 2105+50.00 | RT | 350 | 16 | | | 2156+50.00 TO 2157+24.00 | RT | 74 | | | | |
| 2029+50.00 TO 2033+00.00 | LT | 350 | 21 | 1 | | 2103+00.00 TO 2105+00.00 | LT | 200 | 36 | 2 | | 2160+00.00 TO 2160+50.00 | LT | 50 | | | | |
| 2030+00.00 TO 2035+00.00 | RT | 500 | 6 | | | 2104+56.81 | LT | | | | 25 | 2160+00.00 TO 2165+00.00 | RT | 500 | | | | |
| 2033+00.00 TO 2037+00.00 | LT | 400 | 4 | | | 2105+00.00 TO 2106+50.00 | LT | 150 | 18 | 1 | | 2160+50.00 TO 2161+00.00 | LT | 50 | | | | |
| 2033+49.41 | RT | | | | 20 | 2105+03.44 | LT | | | | 25 | 2161+00.00 TO 2162+00.00 | LT | 100 | | | | |
| 2033+44.44 | LT | | | | 19 | 2105+50.00 TO 2108+50.00 | RT | 300 | 8 | | | 2162+00.00 TO 2162+50.00 | LT | 50 | | | | |
| 2035+00.00 TO 2038+50.00 | RT | 350 | 33 | 1 | | 2106+50.00 TO 2108+50.00 | LT | 200 | | | | 2162+50.00 TO 2163+00.00 | LT | 50 | | | | |
| 2037+00.00 TO 2038+50.00 | LT | 150 | | | | 2108+50.00 TO 2110+00.00 | LT | 150 | 18 | 1 | | 2163+50.00 TO 2164+00.00 | LT | 50 | | | | |
| 2038+50.00 TO 2041+25.00 | RT | 275 | 4 | | | 2108+50.00 TO 2111+50.00 | RT | 300 | 8 | | | 2164+00.00 TO 2164+58.00 | LT | 58 | | | | |
| 2038+50.00 TO 2041+25.00 | LT | 275 | | | | 2109+50.76 | LT | | | | 19 | 2164+58.00 TO 2166+00.00 | LT | 142 | | | | |
| 2041+25.00 TO 2044+85.00 | LT | 360 | 4 | | | 2109+50.97 | LT | | | | 17 | 2165+00.00 TO 2166+50.00 | RT | 150 | | | | |
| 2041+25.00 TO 2044+85.00 | RT | 360 | 6 | | | 2110+00.00 TO 2112+50.00 | LT | 250 | 18 | 1 | | 2166+00.00 TO 2166+50.00 | LT | 50 | | | | |
| 2041+50.31 | RT | | | | 19 | 2111+50.00 TO 2115+50.00 | RT | 400 | 8 | | | 2166+50.00 TO 2167+00.00 | RT | 50 | | | | |
| 2041+51.77 | LT | | | | 21 | 2112+50.00 TO 2115+50.00 | LT | 300 | 19 | 1 | | 2167+00.00 TO 2167+15.00 | RT | 15 | | | | |
| 2044+85.00 TO 2047+50.00 | LT | 265 | 48 | 2 | | 2114+50.69 | LT | | | | 20 | 2167+15.00 TO 2168+28.00 | RT | 113 | | | | |
| 2044+85.00 TO 2047+50.00 | RT | 265 | 12 | | | 2114+51.68 | LT | | | | 20 | 2168+00.00 TO 2168+50.00 | LT | 50 | | | | |
| 2044+97.48 | RT | | | | 20 | 2115+50.00 TO 2118+50.00 | LT | 300 | 19 | 1 | | 2168+28.00 TO 2169+25.00 | RT | 97 | | | | |
| 2045+03.91 | LT | | | | 24 | 2115+50.00 TO 2118+50.00 | RT | 300 | | | | 2168+50.00 TO 2169+00.00 | LT | 50 | | | | |
| 2045+05.89 | RT | | | | 19 | 2120+00.00 TO 2123+50.00 | LT | 350 | 28 | 1 | | 2169+00.00 TO 2170+00.00 | LT | 100 | | | | |
| 2047+50.00 TO 2051+50.00 | LT | 400 | 18 | 1 | | 2120+00.00 TO 2123+50.00 | RT | 350 | 18 | 1 | | | | | | | | |
| TOTAL | | | | | | | | | | | | | | 31430 | 1216 | 52 | 30439 | |

LAST SAVED = 1/25/2013
 PEN TABLE = Vg...
 PLOT DRIVER = pdf...layers...dwtcf9

| | | | |
|--|-------------------------|------------|-----------|
| FILE NAME = | USER NAME = beriechmann | DESIGNED - | REVISED - |
| I:\1001100\Phase II - 76817\Cad\T\Plans\005_0876817-sht-schedule.dgn | | DRAWN - | REVISED - |
| | | CHECKED - | REVISED - |
| | | DATE - | REVISED - |

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**



SCHEDULES OF QUANTITIES
 PIPE UNDERDRAINS

SCALE: NONE SHEET NO. 24 OF 32 SHEETS STA. TO STA.

| | | | | |
|---------------------------|----------|--------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 312 | 68-WRS-1 | MONROE | 760 | 72 |
| CONTRACT NO. 76817 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |