LEGEND

- HMA SURFACE REMOVAL, VARIABLE DEPTH
- PAVEMENT REMOVAL
- PAVED SHOULDER REMOVAL

- REMOVE PIPE UNDERDRAINS PER TYPICAL SECTIONS
- •• GREAT RIVER ROAD AND AMERICA'S BYWAYS SIGNS ARE TO BE RELOCATED. ALL OTHER SIGNS ARE TO BE REMOVED. SEE SCHEDULE.
- ••• PIPE CULVERT REMOVAL - 69 FT
  END SECTION TBR (2)

PARK STREET
FAP 829 (IL ROUTE 156)

FAP 312 (IL ROUTE 3)

S MOORE STREET

LAKEVIEW DRIVE

DRIVEWAY PAVEMENT REMOVAL - 191 SQ YD
PAVEMENT REMOVAL - 537 SQ YD
PAVEMENT REMOVAL - 630 SQ YD
DRIVEWAY PAVEMENT REMOVAL - 25 SQ YD
DRIVEWAY PAVEMENT REMOVAL - 12 SQ YD
CURB AND GUTTER REMOVAL STA. 5+37.49 TO 6+47.65
SIGN TBR (2)
DRIVEWAY PAVEMENT REMOVAL - 115 SQ YD
CURB AND GUTTER REMOVAL STA. 7+22.03 TO 7+94.01
MANHOLE TO BE FILLED REMOVE STORM SEWER - 28 FT
DRIVEWAY PAVEMENT REMOVAL - 59 SQ YD
SIGN TBR
INLET TBR (2)
SIGN TBR
SIDEWALK TBR
SIGN TBR (2)
HANDHOLE TBR
DRIVEWAY PAVEMENT REMOVAL - 13 SQ YD
MANHOLE (TBR)
SIGN TBR
DRIVEWAY PAVEMENT REMOVAL - 62 SQ YD
REMOVE EXISTING RIPRAP - 14 SQ YD
REMOVE INLET AND STORM SEWER - 15 FT
CURB AND GUTTER REMOVAL STA. 90+33.61 TO 91+36.63
PAVEMENT REMOVAL - 113 SQ YD
PAVEMENT REMOVAL - 92 SQ YD
••• SEE NOTE
SIDEWALK TBR
CURB AND GUTTER REMOVAL STA. 6+20.00 TO 7+36.55
REMOVE INLET AND STORM SEWER - 18 FT
CURB AND GUTTER REMOVAL STA. 90+64.20 TO 92+53.11
CURB AND GUTTER REMOVAL STA. 7+94.91 TO 10+12.08
SIGN TBR (3)
DRIVEWAY PAVEMENT REMOVAL - 284 SQ YD
REMOVE INLET (2) AND STORM SEWER - 75 FT
SIDEWALK TBR
DRIVEWAY PAVEMENT REMOVAL - 306 SQ YD
PIPE CULVERT REMOVAL - 38 FT
CURB AND GUTTER REMOVAL STA. 8+48.55 TO 9+14.88
TRAFFIC SIGNAL EQUPMENT TBR (3)
MANHOLE (TBR)
ROW MARKER (TBR)
INLET TBR (3)
PAVEMENT REMOVAL - 317 SQ YD
HANDHOLE TBR
TRAFFIC SIGNAL EQUPMENT TBR
HANDHOLE TBR
MANHOLE (TBR)
CURB AND GUTTER REMOVAL STA. 10+34.77 TO 12+70.50
DRIVEWAY PAVEMENT REMOVAL - 46 SQ YD
INLET TBR (2)
DRIVEWAY PAVEMENT REMOVAL - 56 SQ YD
CURB AND GUTTER REMOVAL STA. 10+71.24 TO 12+70.50
ROW MARKER (TBR)
PARKING
HOUSE #405
HOUSE #407
CHILDRENS FIRST LEARNING
SHED
HOUSE

N

50 25 0 50 100
SCALE IN FEET

FILE NAME = F:\Projects\IDOT PROJECTS\09-101-11.4\Drawings\CADD Sheets\Contract 2\166_D876817-sht-RemovalPlan	USER NAME = Richard Heinke	DESIGNED - JAH	REVISED -
		DRAWN - RNH	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED - TMM	REVISED -
	PLOT DATE = 1/24/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

McDonough-Whitlow, P.C.
PROFESSIONAL DESIGN No. 184-002754

SCALE: 1" = 50'

REMOVAL PLAN
IL ROUTE 156 & LAKEVIEW DR.

SHEET NO. 16 OF 19 SHEETS | STA. 3+30.00 TO STA. 12+70.50

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	68-WRS-1	MONROE	760	156
		CONTRACT NO. 76817		
	ILLINOIS FED. AID PROJECT			