


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY	URBAN
60100945	PIPE DRAINS 12"	FOOT	30	30	
60107600	PIPE UNDERDRAINS 4"	FOOT	7765	7765	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	280	280	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	8	8	
60255900	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1	
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	16	16	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1567	1567	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	30	30	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	40	40	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	50 FT	250	250	
60900515	CONCRETE THRUST BLOCKS	EACH	1	1	
61000225	TYPE F INLET BOX, STANDARD 610001	EACH	1	1	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	4484	4484	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	

14

* SPECIALTY ITEM

 Farnsworth GROUP, INC. 2709 McGraw Drive Bloomington, IL 61704 309/693-8435 309/693-1571 fax	USER NAME > USER1 PLOT SCALE > ASSEMBLY PLOT DATE > 03/20/13	DESIGNED - JJO DRAWN - JJO CHECKED - PJM DATE - 03/20/13	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE. 788 SECTION 520-1-2 COUNTY ST. CLAIR TOTAL SHEETS 142 SHEET NO. 6 CONTRACT NO. 76850	ILLINOIS FED. AID PROJECT
	SCALE: SHEET NO. OF SHEETS STA. TO STA.							