

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011 FEDERAL 80% STATE 20%		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	276	276		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	55	55		
44000100	PAVEMENT REMOVAL	SQ YD	310	310		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	540	540		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	340	340		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	45	45		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
50105220	PIPE CULVERT REMOVAL	FOOT	75	75		
50200100	STRUCTURE EXCAVATION	CU YD	262	262		
50300225	CONCRETE STRUCTURES	CU YD	48	48		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	137.1	137.1		
50300260	BRIDGE DECK GROOVING	SQ YD	338	338		
50300280	CONCRETE ENCASEMENT	CU YD	6.6	6.6		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011 FEDERAL 80% STATE 20%		
50300300	PROTECTIVE COAT	SQ YD	423	423		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		
50500505	STUD SHEAR CONNECTORS	EACH	1692	1692		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	36,950	36,950		
50800515	BAR SPLICERS	EACH	401	401		
51201800	FURNISHING STEEL PILES HP14X73	FOOT	457	457		
51202305	DRIVING PILES	FOOT	457	457		
51203800	TEST PILE STEEL HP14X73	EACH	1	1		
51500100	NAME PLATES	EACH	1	1		
52100520	ANCHOR BOLTS, 1"	EACH	24	24		
54213450	END SECTIONS 15"	EACH	2	2		
54213471	END SECTIONS 36"	EACH	2	2		
54201060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	35	35		

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 793	SECTION 40BR-1	COUNTY MADISON	TOTAL SHEETS 72	SHEET NO. 4
#FILE#		DRAWN -	REVISED -					CONTRACT NO. 76A36		
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
	PLOT DATE = #DATE#	DATE -	REVISED -							