



EROSION CONTROL SCHEDULE

LOCATION	RIGHT OR LEFT	TEMPORARY DITCH CHECK		INLET AND PIPE PROTECTION
		STAGE I EACH	FINAL EACH	
STA 52+35	43' RT			1
STA 52+60	42' LT			1
STA 53+00	44' RT		1	
STA 53+45	50' LT		1	
STA 53+50	42' RT	1		
STA 54+00	51' LT	1		
STA 54+50	50' RT		1	
STA 54+95	57' LT		1	
STA 55+00	42' RT	1		
STA 55+50	61' LT	1		
STA 56+00	54' RT		1	
STA 56+15	63' LT		1	
STA 58+50	33' RT		1	
STA 58+90	30' RT		1	
STA 59+30	28' RT		1	
STA 59+50	27' LT		1	
STA 59+70	27' RT		1	
STA 60+00	23' LT		1	
STA 60+10	26' RT		1	
STA 60+50	25' RT		1	
STA 60+50	23' LT		1	
SUB-TOTAL		4	15	
TOTAL			19	2

EROSION CONTROL SCHEDULE

LOCATION	RIGHT OR LEFT	PERIMETER EROSION BARRIER FOOT	EROSION CONTROL BLANKET SQ YD
STA 53+50 TO STA 55+00	LT		733
STA 55+95 TO STA 58+00	RT	105	
STA 55+95 TO STA 59+50	LT	260	
STA 59+00 TO STA 60+50	RT		316
STA 475+82 TO STA 61+00	LT		341
TOTAL		365	1390

LEGEND

- TEMPORARY DITCH CHECK- ROLLED EXCELSIOR, SILT WEDGES/PANELS
- EROSION CONTROL BLANKET
- PERIMETER EROSION BARRIER- SILT FILTER FENCE OR OTHER AS APPROVED BY THE ENGINEER
- INLET AND PIPE PROTECTION- STRAW BALES, FILTER FABRIC, AGGREGATES

