

STRIP REFLECTIVE CRACK CONTROL TREATMENT SCHEDULE			
LOCATION			STRIP REFLECTIVE CRACK CONTROL TREATMENT FOOT
575+56	TO	589+91.7	2871.4
590+69.8	TO	737+84	29428.4
738+04	TO	925+49	37490.0
TOTAL =			69790

REMOVAL SCHEDULE						
LOCATION			HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL 3/4"	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"
STATION	TO	STATION	SQ YD	SQ YD	SQ YD	SQ YD
575+56	TO	575+71	74			
575+71	TO	577+86		573.3		
577+86	TO	589+59		2867.3		
589+59	TO	589+91.7				64.4
MILLING OMISSION - SN 082-0281						
590+69.8	TO	591+02.5				64.4
591+02.5	TO	737+69		35851.4		
737+69	TO	737+84	47			
MILLING OMISSION - SN 082-0283						
738+04	TO	738+19	47			
738+19	TO	828+70		22124.7		
828+70	TO	865+75		9880.0		
865+75	TO	892+80			7213.3	
892+80	TO	908+67.27		4232.7		
908+67.27	TO	917+00		3053.3		
917+00	TO	919+00		844.4		
919+00	TO	925+34		2183.8		
925+34	TO	925+49	50			
SUBTOTAL =			218	81611.1	7213.3	128.8
TOTAL =			218	81612	7214	129

PAVING SCHEDULE									
LOCATION			BITUMINOUS MATERIALS (PRIME COAT) TON	AGGREGATE (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE COURSE TON	HOT-MIX ASPHALT SHOULDERS		AGG WEDGE SHOULDER, TYPE B	
STATION	TO	STATION				LEFT TON	RIGHT TON	LEFT TON	RIGHT TON
MAINLINE IL 13									
575+56	TO	577+86	0.35	1.69	77.28	21.47	21.47	6.39	6.39
577+86	TO	589+59	1.14	5.47	361.28	32.84	32.84	32.58	32.58
589+59	TO	589+79	0.02	0.09	11.91	0.56	0.56	0.56	0.56
589+79	TO	590+82.5	0.12	0.55	35.42	4.83	4.83		
590+82.5	TO	591+02.5	0.02	0.09	11.57	0.56	0.56	0.56	0.56
591+02.5	TO	659+13	6.63	31.78	2097.63	190.69	190.69	189.16	189.16
659+13	TO	661+36.5	0.23	1.12	68.84	6.26	10.43	6.21	6.21
661+36.5	TO	665+64	0.42	2.00	131.67	11.97	11.97	11.87	11.87
665+64	TO	669+35	0.39	1.86	114.27	17.31	10.39	10.30	10.30
669+35	TO	737+84	6.67	31.96	2109.49	191.77	191.77	190.23	190.23
OMISSION - SN 082-0283									
738+04	TO	828+70	8.83	42.31	2792.33	253.85	253.85	251.81	251.81
828+70	TO	865+75	3.61	18.53	1244.88	103.74	103.74	102.91	102.91
865+75	TO	892+80	2.26	10.82	908.88				
892+80	TO	908+67.27	1.55	7.94	533.32	44.44	44.44	44.09	44.09
908+67.27	TO	917+00	0.81	4.16	384.72	23.32	23.32	23.13	23.13
917+00	TO	919+00	0.19	1.00	106.40	5.60	5.60	5.56	5.56
919+00	TO	925+49	0.63	3.25	281.67	18.17	18.17	18.03	18.03
SUBTOTAL =			33.85	164.61	11271.57	927.39	924.63	893.37	893.37
TOTAL =			33.9	165	11271.6	1852		1787	

TEMPORARY RAMP SCHEDULE					
LOCATION			WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP SQ YD
STATION	TO	STATION			
575+56	TO	575+61	44	5	24.44
589+86.7	TO	589+91.7	28	5	15.56
590+69.8	TO	590+74.8	28	5	15.56
737+79	TO	737+84	28	5	15.56
738+04	TO	738+09	28	5	15.56
925+44	TO	925+49	30	5	16.67
* 886+60	LT		6	7.5	5.00
* 886+60	RT		6	7.5	5.00
SUBTOTAL =					113.33
TOTAL =					114

*CROSSWALK LOCATION