

TEMPORARY PAVEMENT MARKING SCHEDULE															
LOCATION STA TO STA	DESCRIPTION	TEMPORARY PAVEMENT MARKING - LINE 4"						TEMPORARY PAVEMENT MARKING LINE 12"			TEMPORARY PVMT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SHORT TERM PVMT MARKING	WORK ZONE PAVEMENT REMOVAL	
		CENTERLINE SKIP-DASH	CENTERLINE SOLID YELLOW		EDGE LINE SOLID WHITE		SOLID WHITE	YELLOW (DIAG)	WHITE	WHITE (DIAG)	WHITE (STOP BAR)	WHITE	FOOT	SQ FT	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT								FOOT
FAP 103 (IL 13)															
575+56 TO 580+46		110			490	490								206	431.9
580+46 TO 590+25	NO PASSING ZONE RT	227		979	979	979								268	1144.0
590+25 TO 592+70	NO PASSING ZONE LT & RT		245	245	245	195								67	332.3
592+70 TO 603+75	NO PASSING ZONE LT	276	1105		1105	1105								301	1297.5
603+75 TO 614+30		264			1055	1055								288	887.2
614+30 TO 621+64	NO PASSING ZONE RT	184		734	734	734								200	862.1
621+64 TO 625+38		94			340	374								102	303.3
625+38 TO 632+43	NO PASSING ZONE LT	177	705		496	496								192	688.8
632+43 TO 658+79		560			2490	2490								719	2086.3
658+79 TO 668+82	NO PASSING ZONE RT	251		1003	1003	1003								274	1177.8
668+82 TO 669+89		27			107	107								29	90.1
669+89 TO 680+60	NO PASSING ZONE LT	268	1071		1071	1071								292	1257.7
680+60 TO 693+50		323			1290	1290								352	1084.9
693+50 TO 701+77	NO PASSING ZONE RT	207		827	802	802								226	954.5
701+77 TO 703+93		54			216	216								59	181.6
703+93 TO 712+19	NO PASSING ZONE LT	207	826		826	826								225	970.1
712+19 TO 714+31		53			212	212								58	178.3
714+31 TO 736+03	NO PASSING ZONE RT	543		2172	2172	2172								592	2550.5
736+03 TO 741+41		135			538	538								147	452.6
741+41 TO 750+18	NO PASSING ZONE RT	215		877	877	877								239	1028.4
750+18 TO 752+48		58			230	230								63	193.6
752+48 TO 760+96	NO PASSING ZONE LT	212	848		848	848								231	995.8
760+96 TO 777+11		404			1485	1485								440	1271.5
777+11 TO 786+34	NO PASSING ZONE RT	231		923	923	923								252	1083.9
786+34 TO 788+01		42			167	167								46	140.5
788+01 TO 797+11		228	910		910	910								248	1068.7
797+11 TO 823+96		672			2685	2685								732	2258.1
823+96 TO 833+98	NO PASSING ZONE RT	251		1002	1002	1002								273	1176.8
833+98 TO 835+35		35			137	137								37	115.5
SUBTOTAL (1) =		6308.0	5710.0	8762.0	25435.0	25419.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7158.2	26264.1