

TEMPORARY PAVEMENT MARKING SCHEDULE (CONT'D)																
LOCATION	DESCRIPTION	TEMPORARY PAVEMENT MARKING - LINE 4"							TEMPORARY PAVEMENT MARKING - LINE 12"			TEMPORARY PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SHORT TERM PVMT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	
		CENTERLINE SKIP-DASH	CENTERLINE SOLID YELLOW		EDGE LINE SOLID WHITE		SOLID WHITE	YELLOW (DIAG)	WHITE	WHITE (DIAG)	WHITE (STOP BAR)	WHITE	MARKING	SQ FT	FOOT	SQ FT
		YELLOW	LEFT	RIGHT	LEFT	RIGHT	FOOT									
STA TO STA		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
835+35 TO 840+12	NO PASSING ZONE LT	120	477		477	477								132	561.0	
840+12 TO 841+42	NO PASSING ZONE LT & RT		130	130	130	130								35	185.2	
841+42 TO 846+34	NO PASSING ZONE RT	123		492	492	492								134	577.7	
846+30 TO 849+24	NO PASSING ZONE LT & RT		294	294	202	202								82	357.7	
849+24 TO 855+22	NO PASSING ZONE LT	150	598		513	513								163	645.7	
855+22 TO 879+52	SKIP DASH	608			2207	2207								663	1894.9	
879+52 TO 902+72	SKIP DASH	580			2184	2184								633	1860.2	
902+72 TO 909+17	NO PASSING ZONE LT	161	645		645	645								176	757.3	
909+17 TO 918+11	PAINTED MEDIAN		1788	1788	894	894		398						244	2267.3	
918+11 TO 919+10	LEFT TURN LANE (W/ 2 TURN ARROWS)		99	99		99	99.0							28	141.3	
919+10 TO 919+92						82								23	35.1	
919+92 TO 925+49	PAINTED MEDIAN		1226	1226	563	613		185						152	1445.0	
STA 886+70	CROSSWALK								120	614					734.0	
IL 3 INTERSECTION WITH IL ROUTE 4: EDGE LINES, STOP BARS, CENTERLINE, PAINTING AROUND MEDIAN										247	30	31.2			1445.0	
SUBTOTAL (2) =		1742	5257	4029	8307	8538	99	583	120	861	30	31.2	2465	12907.5		
SUBTOTAL (1+2)=		8050.0	10967.0	12791.0	33741.5	33956.5	99.0	583	120	861	30	31.2	9623.6	39171.5		
TOTAL (1+2)=		99605					1564					30	32	9624	39172	