

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE		
				100% STATE		
				ROADWAY	0001	URBAN
20200100	EARTH EXCAVATION	CU YD	236,698	236,698		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	18,846	18,846		
20400800	FURNISHED EXCAVATION	CU YD	58,917	58,917		
20800150	TRENCH BACKFILL	CU YD	1,537	1,537		
21000310	GRANULAR EMBANKMENT, SPECIAL	CU YD	18,379	18,379		
21301060	EXPLORATION TRENCH 60" DEPTH	FOOT	1000	1000		
* 25000210	SEEDING, CLASS 2A	ACRE	0.6	0.6		
* 25000305	SEEDING, CLASS 3A	ACRE	14.8	14.8		
* 25000310	SEEDING, CLASS 4	ACRE	0.1	0.1		
* 25000312	SEEDING, CLASS 4A	ACRE	6.9	6.9		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2,024	2,024		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2,024	2,024		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2,024	2,024		
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	44	44		
* 25100115	MULCH, METHOD 2	ACRE	7.6	7.6		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE		
				100% STATE		
				ROADWAY	0001	URBAN
* 25100630	EROSION CONTROL BLANKET	SO YD	71,820	71,820		
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	2,194	2,194		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9,520	9,520		
28000305	TEMPORARY DITCH CHECKS	FOOT	576	576		
28000400	PERIMETER EROSION BARRIER	FOOT	2,947	2,947		
28000500	INLET AND PIPE PROTECTION	EACH	39	39		
28100705	STONE DUMPED RIPRAP, CLASS A3	SO YD	91	91		
28100707	STONE DUMPED RIPRAP, CLASS A4	SO YD	453	453		
28100709	STONE DUMPED RIPRAP, CLASS A5	SO YD	2405	2405		
28100725	STONE DUMPED RIPRAP, CLASS B5	SO YD	528	528		
28200200	FILTER FABRIC	SO YD	2858	2858		
31001500	LIME	TON	10,547	10,547		
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SO YD	75	75		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1,920	1,920		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	30	30		
40603087	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N70	TON	20	20		

*SPECIALTY ITEM

Farnsworth GROUP, INC. 2709 McGraw Drive Bloomington, Illinois 61704 309/803-8435 309/803-1911 fax	DESIGNED - JJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE. 788 SECTION 520-1-2-1 COUNTY ST. CLAIR TOTAL SHEETS 121 SHEET NO. 3 CONTRACT NO. 76F70 ILLINOIS FED. AID PROJECT
	DRAWN - JJO CHECKED - PJM DATE 10/18/12	REVISED - REVISED - REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.		