

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY 0001	URBAN
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10	10	
44000100	PAVEMENT REMOVAL	SO YD	1400	1400	
50800105	REINFORCEMENT BARS	POUND	220	220	
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	187	187	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	18	18	
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	212	212	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	25	25	
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	44	44	
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	56	56	
54213450	END SECTIONS 15"	EACH	4	4	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	6	6	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY 0001	URBAN
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	74	74	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	733	733	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	134	134	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	93	93	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	90	90	
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	44	44	
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	283	283	
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	256	256	
550A0780	STORM SEWERS, CLASS A, TYPE 3 48"	FOOT	32	32	
550A1070	STORM SEWERS, CLASS A, TYPE 4 42"	FOOT	257	257	
60100080	FRENCH DRAINS	CU YD	39	39	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	17	17	
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SO YD	347	347	
60107100	PIPE UNDERDRAINS 6"	FT	340	340	
60240366	INLETS, TYPE B, WITH MEDIAN INLET (604106)	EACH	3	3	



DESIGNED: JJO
 DRAWN: JJO
 CHECKED: PJM
 DATE: 10/18/12

REVISIONS:
 REVISION 1: JJO
 REVISION 2: PJM
 REVISION 3: JJO

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 788	SECTION 520-1-2-1	COUNTY ST. CLAIR	TOTAL SHEETS 121	SHEET NO. 4
CONTRACT NO. 76F70			ILLINOIS FED. AID PROJECT	