

GUARDRAIL SCHEDULE								
STA.	TO	STA.	LENGTH	SIDE	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE I, (SPECIAL) TANGENT	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKERS DIRECT APPLIED
			(FOOT)		(FOOT)	(EACH)	(EACH)	(EACH)
87+42.5	TO	90+30	425	L	325	2	2	2
106+95	TO	110+70	375	L	275	2	3	2
107+00.	TO	110+62.5	362.5	R	262.5	2	3	2
119+43.5	TO	123+56	412.5	L	312.5	2	4	2
119+00	TO	124+50	550	R	450	2	6	2
126+00.	TO	130+50.	450	R	350	2	4	2
140+00.	TO	147+00.	700	L	600	2	8	2
139+51.5	TO	146+14.	662.5	R	562.5	2	7	2
237+50.	TO	244+50.	700	L	600	2	8	2
238+40.	TO	244+02.5	562.5	R	462.5	2	6	2
253+09.	TO	258+59.	550	R	450	2	6	2
253+89.	TO	259+39.	550	L	450	2	6	2
302+22.	TO	309+72.	750	L	650	2	8	2
300+94.	TO	309+81.5	887.5	R	787.5	2	10	2
323+44.	TO	328+19.	475	L	375	2	5	2
323+00.	TO	328+12.5	512.5	R	412.5	2	5	2
348+70.	TO	355+45.	675	L	575	2	7	2
348+00.	TO	354+50.	650	R	550	2	7	2
359+98.	TO	367+48.	750	L	650	2	8	2
359+42	TO	366+30	812.5	R	712.5	2	7	2
<b>TOTAL:</b>					9812.5	40	119	40

RESURFACING SCHEDULE											
STA.	TO	STA.	LENGTH	LT/RT	POLY HMA SURFACE COURSE, MIX "D", N90	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE REMOVAL 2 1/2"	HMA SHOULDERS 8"	AGGREGATE WEDGE SHOULDER, TYPE B	SHOULDER RUMBLE STRIPS, 8"
			FOOT		TON	TON	TON	SQ YD	SQ YD	TON	FOOT
61+80	TO	423+17	36137	LT/RT	12929	28.5	139		31122		71274
74+46	TO	79+82	536	LT/RT				1370			
164+92	TO	189+43	2451	LT/RT				6264			
255+06	TO	273+86	1880	LT/RT				4804			
410+00				LT						3.4	
<b>TOTAL:</b>					12929	29	139	12438	31722	3.4	71274

CONCRETE CURB AND GUTTER OUTLET		
STATION	LT/RT	CLASS SI CONCRETE (OUTLET)  CU YD
124+88	LT	3.1
217+95	LT/RT	3.1
420+48	LT/RT	6.2
<b>TOTAL:</b>		12.4