

EARTHWORK SCHEDULE #1						
STA	TO	STA	UNADJUSTED EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			(CU YD)	(CU YD)	(CU YD)	(CU YD)
62+00.00	TO	63+00.00	38.0	28.5	1.5	27.0
63+00.00	TO	64+00.00	23.3	17.5	2.1	15.4
64+00.00	TO	64+99.00	13.9	10.4	3.8	6.6
64+99.00	TO	66+00.00	18.3	13.7	3.0	10.7
66+00.00	TO	67+00.00	18.6	14.0	2.4	11.6
67+00.00	TO	68+05.00	17.2	12.9	147.3	-134.4
68+05.00	TO	69+00.00	18.2	13.7	132.1	-118.4
69+00.00	TO	70+00.00	22.0	16.5	1.4	15.1
70+00.00	TO	71+00.00	21.2	15.9	1.1	14.8
71+00.00	TO	72+00.00	38.4	28.8	2.7	28.1
72+00.00	TO	73+50.00	24.1	18.1	0.6	17.5
73+50.00	TO	74+50.00	17.9	13.4	8.7	4.7
74+50.00	TO	75+50.00	19.7	14.8	25.4	-10.6
75+50.00	TO	76+50.00	30.7	23.0	17.9	5.1
76+50.00	TO	77+50.00	348.2	261.2	2.1	259.1
77+50.00	TO	78+50.00	369.8	277.4	2.9	274.5
78+50.00	TO	79+50.00	62.3	46.7	4.7	42.0
79+50.00	TO	80+50.00	47.3	35.5	5.1	30.4
80+50.00	TO	81+50.00	50.1	37.6	2.4	35.2
81+50.00	TO	82+42.00	43.6	32.7	0.1	32.6
82+42.00	TO	82+50.00	4.1	3.1	0.0	3.1
82+50.00	TO	83+50.00	49.0	36.8	0.0	36.8
83+50.00	TO	84+50.00	37.6	28.2	1.2	27.0
84+50.00	TO	85+22.00	20.8	15.6	1.5	14.1
85+22.00	TO	86+00.00	22.2	16.7	2.2	14.5
86+00.00	TO	87+00.00	25.5	19.1	4.4	14.7
87+00.00	TO	88+00.00	24.6	18.5	49.8	-31.3
88+00.00	TO	89+22.00	31.3	23.5	216.8	-193.3
89+22.00	TO	90+00.00	17.6	13.2	147.6	-134.4
90+00.00	TO	90+41.00	4.5	3.4	25.5	-22.1
90+41.00	TO	90+72.00	2.4	1.8	1.3	0.5
90+72.00	TO	91+54.00	9.8	7.4	1.1	6.3
91+54.00	TO	92+50.00	8.1	6.1	2.7	3.4
92+50.00	TO	94+47.98	37.9	28.4	4.7	23.7
94+47.98	TO	95+00.00	44.8	33.6	7.0	28.6
95+00.00	TO	96+69.77	39.5	29.6	1.5	28.1
96+69.77	TO	98+00.00	10.6	8.0	2.4	5.6
98+00.00	TO	98+50.00	2.5	1.9	1.5	0.4
98+50.00	TO	99+50.00	16.3	12.2	6.1	6.1
99+50.00	TO	99+89.38	9.8	7.4	2.2	5.2
99+89.38	TO	100+72.23	22.6	17.0	1.4	15.6
100+72.23	TO	101+75.90	31.4	23.6	0.7	22.9
101+75.90	TO	102+50.00	16.3	16.3	1.0	15.3
102+50.00	TO	103+50.00	24.4	18.3	4.4	13.9
103+50.00	TO	104+50.00	24.4	18.3	5.1	13.2
104+50.00	TO	105+50.00	25.5	19.1	4.3	14.8
105+50.00	TO	106+71.24	33.2	24.9	3.7	21.2
TOTAL =			1844.9	1384.3	867.4	516.9

EARTHWORK SCHEDULE #2						
STA	TO	STA	UNADJUSTED EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			(CU YD)	(CU YD)	(CU YD)	(CU YD)
106+71.24	TO	108+00.00	37.7	28.3	74.9	-46.6
108+00.00	TO	109+03.36	35.1	26.3	62.9	-36.6
109+03.36	TO	109+50.00	17.0	12.8	2.5	10.3
109+50.00	TO	110+50.00	35.0	26.3	38.4	-12.1
110+50.00	TO	111+00.00	24.7	18.5	18.3	0.2
111+00.00	TO	112+00.00	51.4	38.6	247.1	-208.5
112+00.00	TO	113+00.00	43.4	32.6	407.2	-374.6
113+00.00	TO	114+00.00	37.0	27.8	161.0	-133.2
114+00.00	TO	115+18.94	38.4	28.8	1.1	27.7
115+18.94	TO	116+00.00	31.5	23.6	0.2	23.4
116+00.00	TO	117+00.00	35.8	26.9	0.2	26.7
117+00.00	TO	118+00.00	30.5	22.9	0.6	22.3
118+00.00	TO	119+00.00	64.0	48.0	0.1	47.9
119+00.00	TO	120+00.00	24.0	18.0	3.2	14.8
120+00.00	TO	121+00.00	21.8	16.4	1095.7	-1079.3
121+00.00	TO	121+60.34	17.3	13.0	661.2	-648.2
121+60.34	TO	122+00.00	9.4	7.1	11.1	-4.0
122+00.00	TO	123+00.00	23.1	17.3	26.2	-8.9
123+00.00	TO	124+35.87	22.6	17.0	2.2	14.8
124+35.87	TO	125+50.00	29.7	22.3	0.3	22.0
125+50.00	TO	126+50.00	43.3	32.5	0.6	31.9
126+50.00	TO	127+50.00	31.8	23.9	74.5	-50.6
127+50.00	TO	128+50.00	22.6	17.0	77.9	-60.9
128+50.00	TO	129+81.47	30.1	22.6	9.2	13.4
129+81.47	TO	131+00.00	29.1	21.8	5.5	16.3
131+00.00	TO	132+18.23	157.6	118.2	2.0	116.2
132+18.23	TO	133+00.00	129.6	97.2	0.7	96.5
133+00.00	TO	134+00.00	51.7	38.8	6.9	31.9
134+00.00	TO	135+00.00	25.9	19.4	11.2	8.2
135+00.00	TO	136+00.00	23.4	17.6	10.9	6.7
136+00.00	TO	137+00.00	22.0	16.5	12.8	3.7
137+00.00	TO	138+00.00	24.0	18.0	8.3	9.7
138+00.00	TO	139+17.55	35.0	26.3	1.8	24.5
139+17.55	TO	140+00.00	30.3	22.7	2.2	20.5
140+00.00	TO	141+00.00	43.3	32.5	3.1	29.4
141+00.00	TO	142+00.00	45.0	33.8	1.7	32.1
142+00.00	TO	142+50.00	65.3	49.0	1.9	47.1
142+50.00	TO	143+50.00	35.2	26.4	2.8	23.6
143+50.00	TO	144+50.00	29.5	22.1	41.1	-19.0
144+50.00	TO	145+50.00	31.2	23.4	39.8	-16.4
145+50.00	TO	146+44.92	101.4	76.1	4.1	72.0
146+44.92	TO	147+50.00	120.2	90.2	3.7	86.5
147+50.00	TO	148+50.00	38.3	28.7	5.2	23.5
148+50.00	TO	149+74.16	36.0	27.0	6.3	20.7
149+74.16	TO	151+00.00	43.5	32.6	0.5	32.1
151+00.00	TO	152+00.00	37.6	28.2	548.5	-520.3
152+00.00	TO	153+00.00	50.8	38.1	621.0	-582.9
TOTAL =			1963.1	1473.1	4318.6	-2845.5

EARTHWORK SCHEDULE #3						
STA	TO	STA	UNADJUSTED EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			(CU YD)	(CU YD)	(CU YD)	(CU YD)
153+00.00	TO	154+00.00	58.5	43.9	135.5	-91.6
154+00.00	TO	155+00.00	45.0	33.8	64.1	-30.3
155+00.00	TO	156+04.14	51.0	38.3	1.7	36.6
156+04.14	TO	157+00.00	43.5	32.6	3.9	28.7
157+00.00	TO	158+00.00	37.6	28.2	4.4	23.8
158+00.00	TO	159+00.00	41.3	31.0	1.4	29.6
159+00.00	TO	160+00.00	42.6	32.0	1.1	30.9
160+00.00	TO	161+00.00	43.6	32.7	1.2	31.5
161+00.00	TO	161+74.47	20.6	15.5	0.8	14.7
161+74.47	TO	162+50.00	14.0	10.5	1.8	8.7
162+50.00	TO	163+50.00	25.7	19.3	4.2	15.1
163+50.00	TO	163+93.89	12.4	9.3	1.2	8.1
163+93.89	TO	164+43.16	15.2	11.4	0.8	10.6
164+43.16	TO	165+00.00	16.6	12.5	0.7	11.8
165+00.00	TO	166+00.00	53.1	39.8	2.3	37.5
166+00.00	TO	167+50.00	48.8	36.6	2.1	34.5
167+50.00	TO	168+50.00	36.5	27.4	1.3	26.1
168+50.00	TO	169+50.00	125.9	94.4	3.1	91.3
169+50.00	TO	170+50.00	124.5	93.4	8.3	85.1
170+50.00	TO	171+50.00	35.5	26.6	19.6	7.0
171+50.00	TO	172+00.00	15.5	11.6	13.6	-2.0
172+00.00	TO	172+82.86	31.1	23.3	11.6	11.7
172+82.86	TO	173+50.00	25.3	19.0	5.7	13.3
173+50.00	TO	174+50.00	110.9	83.2	14.4	68.8
174+50.00	TO	175+50.00	198.3	148.7	7.4	141.3
175+50.00	TO	176+50.00	123.8	92.9	2.8	90.1
176+50.00	TO	177+94.80	59.7	44.8	64.0	-19.2
177+94.80	TO	178+76.52	416.1	312.1	408.2	-96.1
178+76.52	TO	179+50.00	368.4	276.3	388.2	-111.9
179+50.00	TO	180+50.00	31.6	23.7	78.7	-55.0
180+50.00	TO	181+50.00	36.9	27.7	11.3	16.4
181+50.00	TO	182+50.00	34.6	26.0	7.8	18.2
182+50.00	TO	183+50.00	40.3	30.2	4.3	25.9
183+50.00	TO	184+50.00	44.8	33.6	1.6	32.0
184+50.00	TO	185+50.00	41.4	31.1	2.0	29.1
185+50.00	TO	186+50.00	35.6	26.7	1.9	24.8
186+50.00	TO	187+50.00	29.9	22.4	34.4	-12.0
187+50.00	TO	188+50.00	31.6	23.7	34.3	-10.6
188+50.00	TO	189+50.00	29.3	22.0	3.3	18.7
189+50.00	TO	190+50.00	54.9	41.2	7.5	33.7
190+50.00	TO	191+41.79	20.8	15.6	3.8	11.8
191+41.79	TO	192+66.00	39.5	29.6	2.1	27.5
192+66.00	TO	193+50.00	25.6	19.2	1.9	17.3
193+50.00	TO	194+50.00	23.2	17.4	3.8	13.6
194+50.00	TO	195+50.00	27.9	20.9	1.9	19.0
195+50.00	TO	196+50.00	26.6	20.0	2.0	18.0
196+50.00	TO	197+50.00	20.6	15.5	3.5	12.0
TOTAL =			2836.1	2127.6	1381.5	746.1