

EARTHWORK SCHEDULE #4						
STA	TO	STA	UNADJUSTED EXCAVATION	EARTH EXCAVATION	EMBANKMENT	EARTHWORK
			(CU YD)	ADJUSTED FOR 25% SHINKAGE (CU YD)		BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
197+50.00	TO	198+50.00	20.0	15.0	3.8	11.2
198+50.00	TO	199+00.00	11.3	8.5	1.8	6.7
199+00.00	TO	201+00.00	62.1	46.6	5.6	41.0
201+00.00	TO	202+00.00	42.5	31.9	1.4	30.5
202+00.00	TO	203+22.36	55.8	41.9	1.4	40.5
203+22.36	TO	204+00.00	37.9	28.4	0.8	27.6
204+00.00	TO	204+73.34	36.6	27.5	0.9	26.6
204+73.34	TO	205+50.00	34.0	25.5	1.3	24.2
205+50.00	TO	206+60.49	55.4	41.6	1.1	40.5
206+60.49	TO	207+50.00	41.2	30.9	1.1	29.8
207+50.00	TO	208+00.00	14.3	10.7	0.5	10.2
208+00.00	TO	209+00.00	30.2	22.7	0.7	22.0
209+00.00	TO	210+18.48	57.7	43.3	1.8	41.5
210+18.48	TO	211+45.79	72.6	54.5	2.6	51.9
211+45.79	TO	212+50.00	46.1	34.6	1.9	32.7
212+50.00	TO	213+50.00	33.1	24.8	2.1	22.7
213+50.00	TO	214+71.39	33.9	25.4	2.0	23.4
214+71.39	TO	215+07.34	13.8	10.4	0.6	9.8
215+07.34	TO	216+00.00	42.1	31.6	3.1	28.5
216+00.00	TO	217+00.00	42.9	32.2	4.1	28.1
217+00.00	TO	217+95.97	61.4	46.1	3.7	42.4
217+95.97	TO	218+50.00	9.3	7.0	0.8	6.2
218+50.00	TO	219+50.00	18.4	13.8	3.3	10.5
219+50.00	TO	220+50.00	25.1	18.8	12.0	6.8
220+50.00	TO	221+50.00	20.5	15.4	49.1	-33.7
221+50.00	TO	222+50.00	17.4	13.1	114.4	-101.3
222+50.00	TO	224+50.00	43.9	32.9	153.4	-120.5
224+50.00	TO	225+59.65	36.4	27.3	1.5	25.8
225+59.65	TO	226+50.00	35.2	26.4	0.6	25.8
226+50.00	TO	227+50.00	35.7	26.8	5.9	20.9
227+50.00	TO	228+50.00	32.9	24.7	7.2	17.5
228+50.00	TO	229+50.00	32.7	24.5	4.9	19.6
229+50.00	TO	230+50.00	30.2	22.7	6.1	16.6
230+50.00	TO	231+50.00	31.3	23.5	8.7	14.8
231+50.00	TO	232+50.00	37.4	28.1	6.1	22.0
232+50.00	TO	233+50.00	43.0	32.3	1.4	30.9
233+50.00	TO	234+50.00	41.7	31.3	1.1	30.2
234+50.00	TO	235+50.00	40.7	30.5	0.4	30.1
235+50.00	TO	236+50.00	47.5	35.6	0.1	35.5
236+50.00	TO	237+50.00	51.4	38.6	0.0	38.6
237+50.00	TO	238+50.00	55.6	41.7	0.0	41.7
238+50.00	TO	239+50.00	46.6	35.0	0.2	34.8
239+50.00	TO	240+15.86	22.2	16.7	0.3	16.4
240+15.86	TO	241+50.00	37.7	28.3	131.2	-102.9
241+50.00	TO	242+50.00	21.7	16.3	147.9	-131.6
242+50.00	TO	243+50.00	23.0	17.3	206.8	-189.5
243+50.00	TO	245+00.00	26.8	20.1	236.5	-216.4
TOTAL =			1709.2	1282.8	1142.2	140.6

EARTHWORK SCHEDULE #5						
STA	TO	STA	UNADJUSTED EXCAVATION	EARTH EXCAVATION	EMBANKMENT	EARTHWORK
			(CU YD)	ADJUSTED FOR 25% SHINKAGE (CU YD)		BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
245+00.00	TO	246+02.59	27.5	20.6	1.3	19.3
246+02.59	TO	247+00.00	32.3	24.2	1.8	22.4
247+00.00	TO	248+00.00	22.0	16.5	3.8	12.7
248+00.00	TO	249+00.00	20.6	15.5	3.9	11.6
249+00.00	TO	250+00.00	21.4	16.1	3.9	12.2
250+00.00	TO	251+19.11	45.1	33.8	2.4	31.4
251+19.11	TO	251+46.21	17.7	13.3	0.0	13.3
251+46.21	TO	252+00.00	36.1	27.1	0.0	27.1
252+00.00	TO	253+00.00	57.8	43.4	1.9	41.5
253+00.00	TO	254+00.00	55.7	41.8	3.2	38.6
254+00.00	TO	255+00.00	373.4	280.1	1056.8	-776.7
255+00.00	TO	256+00.00	693.7	520.3	2111.1	-1590.8
256+00.00	TO	257+00.00	693.7	520.3	1234.4	-714.1
257+00.00	TO	258+00.00	357.6	268.2	187.3	80.9
258+00.00	TO	259+00.00	201.5	151.1	13.6	137.5
259+00.00	TO	260+00.00	381.5	286.1	9.3	276.8
260+00.00	TO	261+00.00	370.7	278.0	12.8	265.2
261+00.00	TO	262+00.00	225.6	169.2	11.5	157.7
262+00.00	TO	263+00.00	62.2	46.7	39.6	7.1
263+00.00	TO	264+00.00	29.4	22.1	45.1	-23.0
264+00.00	TO	265+00.00	24.9	18.7	16.4	2.3
265+00.00	TO	266+00.00	42.3	31.7	10.8	20.9
266+00.00	TO	267+00.00	74.6	56.0	4.7	51.3
267+00.00	TO	268+00.00	127.3	95.5	13.8	81.7
268+00.00	TO	269+00.00	162.6	122.0	14.7	107.3
269+00.00	TO	270+00.00	159.1	119.3	4.8	114.5
270+00.00	TO	271+00.00	91.9	68.9	14.2	54.7
271+00.00	TO	272+00.00	17.7	13.3	132.6	-119.3
272+00.00	TO	272+87.00	12.3	9.2	159.4	-150.2
272+87.00	TO	274+00.00	18.2	13.7	75.5	-61.8
274+00.00	TO	275+00.00	14.2	10.7	6.6	4.1
275+00.00	TO	276+00.00	14.3	10.7	5.3	5.4
276+00.00	TO	277+00.00	15.1	11.3	4.8	6.5
277+00.00	TO	278+00.00	17.4	13.1	3.8	9.3
278+00.00	TO	279+00.00	18.9	14.2	4.8	9.4
279+00.00	TO	279+28.12	7.4	5.6	1.0	4.6
279+28.12	TO	280+00.00	21.0	15.8	0.9	14.9
280+00.00	TO	281+00.00	24.1	18.1	1.9	16.2
281+00.00	TO	282+00.00	32.9	24.7	1.5	23.2
282+00.00	TO	283+00.00	33.2	24.9	2.9	22.0
283+00.00	TO	284+00.00	21.6	16.2	5.8	10.4
284+00.00	TO	284+74.00	16.8	12.6	3.8	8.8
284+74.00	TO	285+00.00	6.0	4.5	0.9	3.6
285+00.00	TO	286+00.00	17.7	13.3	3.6	9.7
286+00.00	TO	287+00.00	20.0	15.0	2.7	12.3
287+00.00	TO	288+00.00	17.3	13.0	9.1	3.9
288+00.00	TO	289+00.00	24.4	18.3	9.2	9.1
TOTAL =			4778.7	3584.7	5259.2	-1674.5

EARTHWORK SCHEDULE #6						
STA	TO	STA	UNADJUSTED EXCAVATION	EARTH EXCAVATION	EMBANKMENT	EARTHWORK
			(CU YD)	ADJUSTED FOR 25% SHINKAGE (CU YD)		BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
289+00.00	TO	290+00.00	42.2	31.7	319.3	-287.6
290+00.00	TO	291+00.00	57.3	43.0	343.4	-300.4
291+00.00	TO	292+00.00	70.0	52.5	26.2	26.3
292+00.00	TO	292+87.32	61.3	46.0	1.0	45.0
292+87.32	TO	294+00.00	50.0	37.5	26.8	10.7
294+00.00	TO	295+00.00	20.1	15.1	91.7	-76.6
295+00.00	TO	296+00.00	29.8	22.4	81.7	-59.3
296+00.00	TO	297+45.57	148.3	111.2	20.1	91.1
297+45.57	TO	298+04.93	62.7	47.0	0.6	46.4
298+04.93	TO	299+00.00	63.1	47.3	1.5	45.8
299+00.00	TO	300+40.58	60.3	45.2	0.9	44.3
300+40.58	TO	301+50.00	18.1	13.6	0.3	13.3
301+50.00	TO	303+00.00	49.5	37.1	2.1	35.0
303+00.00	TO	304+00.00	30.7	23.0	2.8	20.2
304+00.00	TO	305+00.00	30.8	23.1	2.6	20.5
305+00.00	TO	306+00.00	29.2	21.9	1.9	20.0
306+00.00	TO	306+57.81	12.6	9.5	4.5	5.0
306+57.81	TO	307+00.00	8.2	6.2	4.6	1.6
307+00.00	TO	308+00.00	35.8	26.9	4.2	22.7
308+00.00	TO	309+00.00	44.8	33.6	1.8	31.8
309+00.00	TO	310+23.64	56.8	42.6	2.2	40.4
310+23.64	TO	310+65.54	20.6	15.5	0.9	14.6
310+65.54	TO	311+00.00	14.0	10.5	1.6	8.9
311+00.00	TO	312+00.00	42.2	31.7	3.9	27.8
312+00.00	TO	313+00.00	47.6	35.7	2.1	33.6
313+00.00	TO	314+52.18	97.3	73.0	1.4	71.6
314+52.18	TO	316+00.00	84.7	63.5	1.8	61.7
316+00.00	TO	317+00.00	33.0	24.8	3.3	21.5
317+00.00	TO	318+00.00	27.2	20.4	5.7	14.7
318+00.00	TO	319+00.00	22.8	17.1	6.3	10.8
319+00.00	TO	320+00.00	22.7	17.0	6.2	10.8
320+00.00	TO	321+06.79	27.6	20.7	6.8	13.9
321+06.79	TO	322+00.00	23.9	17.9	4.9	13.0
322+00.00	TO	323+00.00	23.1	17.3	5.8	11.5
323+00.00	TO	324+00.00	23.8	17.9	6.2	11.7
324+00.00	TO	325+00.00	23.2	17.4	5.6	11.8
325+00.00	TO	326+37.88	30.0	22.5	17.8	4.7
326+37.88	TO	327+00.00	13.6	10.2	8.4	1.8
327+00.00	TO	328+00.00	25.7	19.3	5.9	13.4
328+00.00	TO	329+00.00	28.2	21.2	4.7	16.5
329+00.00	TO	330+00.00	30.6	23.0	4.8	18.2
330+00.00	TO	331+00.00	33.3	25.0	5.1	19.9
331+00.00	TO	332+00.00	34.2	25.7	3.9	21.8
332+00.00	TO	333+00.00	30.3	22.7	3.5	19.2
333+00.00	TO	334+00.00	31.9	23.9	3.4	20.5
334+00.00	TO	335+00.00	36.8	27.6	2.6	25.0
335+00.00	TO	336+00.00	33.9	25.4	3.9	21.5
TOTAL =			1843.8	1383.3	1066.7	316.6