

SHORT TERM PAVEMENT MARKING						
STA	TO	STA	R/L	Length	WHITE	YELLOW
					FOOT	
IL 3						
988+98.00		992+13.00	R	315	40.0	
992+13.00		995+53.00	R	340.0	234.0	
996+39.00		1000+16.00	R	377.0	124.0	
1000+44.00		1002+46.00	R	202.0	28.0	
988+98.00		995+53.00	L	655.0	88.0	
996+48.00		1000+19.00	L	371.0	213.0	
1000+19.00		1002+46.00	L	227.0	28.0	
1198+45.00		1202+00.00	R	355.0	48.0	16.0
1202+00.00		1204+10.00	R	210.0	156.0	8.0
1205+10.00		1213+07.71	R	797.7	104.0	32.0
1198+45.00		1204+10.31	L	565.3	76.0	24.0
1204+93.00		1206+35.14	L	142.1	136.0	4.0
1206+35.14		1213+07.71	L	672.6	88.0	28.0
1213+07.71		1230+49.09	R	1741.4	228.0	
1231+39.07		1311+96.52	R	8057.4	1056.0	
1312+82.12		1341+46.58	R	2864.5	376.0	
1373+22.18		1374+76.76	R/L	154.6	224.0	12.0
1375+62.06		1378+96.90	R/L	334.8	120.0	28.0
1378+96.90		1382+10.95	R/L	314.1	80.0	24.0
1382+10.95		1436+94.85	R	5483.9	720.0	
1489+00.00		1492+72.60	R/L	372.6	116.0	28.0
1492+72.60		1495+18.09	R/L	245.5	204.0	20.0
1495+81.71		1498+15.00	R/L	233.3	192.0	20.0
1498+15.00		1501+00.00	R/L	285.0	76.0	24.0
SUB-TOTALS					4755.0	268.0

\*CONTINUED TO THE RIGHT

PRISMATIC CURB REFLECTORS				
STA	TO	STA	LENGTH	EACH
IL 3				
988+98.00		995+71.00	673	63
996+39.00		1002+32.00	593	61
IL 143				
256+27.00		261+80.00	553	38
263+13.00		265+84.00	271	36
TOTAL				198

SHORT TERM PAVEMENT MARKING (CONTINUED)						
STA	TO	STA	R/L	Length	WHITE	YELLOW
					FOOT	
IL 143						
251+87.00		257+11.00	R	524.0	140.0	
258+12.00		260+31.00	R	219.0	28.0	
260+31.00		261+94.00	R	163.0	144.0	
262+86.00		265+85.00	R	299.0	40.0	
265+80.00		269+20.00	R/L	340.0	88.0	124.0
251+87.00		255+08.00	L	321.0	40.0	
255+08.00		256+80.00	L	172.0	40.0	
256+80.00		261+79.39	L	499.4	20.0	
262+82.00		265+85.00	L	303.0	197.0	
NB IL 3 TO WB IL 143 RAMP						
1001+54.00		1006+54.00		500.0	80.0	
01+26.00	*	07+59.00		633.0	24.0	24.0
*RAMP STATIONING STARTS AT IL 3 STA 1001+63 W/ 6 FT RT OFFSET						
EB IL 143 TO SB IL 3 RAMP						
00+00.00		02+00.00		200.0	8.0	
02+00.00		07+28.44		528.4	44.0	
07+28.44		17+02.60		974.2	40.0	40.0
17+02.60		19+09.00		206.4	16.0	
19+09.00		27+64.00		855.0	36.0	
CHAIN OF ROCKS RD.						
27+67.40		29+46.37	R/L	179.0	160.0	32.0
30+54.44		31+51.70	R/L	97.3	152.0	16.0
31+51.70		32+10.73	R/L	59.0		12.0
SUB-TOTALS					1297.0	248.0
SUB-TOTALS (TABLE @ LEFT)					4755.0	268.0
TOTAL*					10940.0	

\*Accounts for 2 applications within edge of pavement and 1 application on shoulders

CURB PAINT				
MEDIAN NOSE LOCATION	NOSE	SIDES	PAINT CURB	
			YELLOW	WHITE
IL 3	FEET	FOOT	FOOT	
995+58.00	58	48	106	
996+44.00	83	48	131	
1001+36.00	22	48	59	11
IL 143				
256+50.00		138	138	
257+11.00	69	48	117	
261+79.00	27	48	75	
263+13.00	29	48	77	
265+85.00	23	48	71	
SUBTOTAL			774	11
MEDIAN SUBTOTAL			785	

CURB PAINT				
ISLAND LOCATION	NOSE OFFSET	SIDES	PAINT CURB	
			YELLOW	WHITE
IL 3		FOOT	FOOT	
995+41.00	48 R	83		83
996+53.00	47 L	85		85
IL 143				
262+82.00	28 L	83		83
SUBTOTAL				251
ISLAND SUBTOTAL			251	

CURB PAINT	
MEDIAN SUBTOTAL	785
ISLAND SUBTOTAL	251
TOTAL	1036