

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE	
				ROADWAY 0005 URBAN	ROADWAY 0005 RURAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	33016	5876	27140
40600300	AGGREGATE (PRIME COAT)	TON	280	51	229
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	3	17
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	191	80	111
40600990	TEMPORARY RAMP	SQ YD	97	40	57
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	7732	1380	6352
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	15437	2752	12685
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	181738	31586	150152
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	17.4	8	9.4
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	1134.7	271.8	862.9
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	64	0	64
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	268.1	93.4	174.7
44200188	PAVEMENT PATCHING, TYPE I, 16 INCH	SQ YD	12	0	12
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	231.1	0	231.1

SHEET 1 OF 3

FILE NAME =	USER NAME = weembf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\weembf\0300388\7827.sht.plandgn		DRAWN -	REVISED -				332	(3,3-2,2)RS-3	WHITE	49	4
PLOT SCALE = 100,0000' / in.		CHECKED -	REVISED -		SCALE: SHEET 4 OF 49 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT CONTRACT NO. 7827				
PLOT DATE = 3/22/2013		DATE -	REVISED -								