

SUMMARY OF QUANTITIES

CONSTR. CODE
80% FED
20% STATE
ROADWAY
0005
URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3510	3510
40600300	AGGREGATE (PRIME COAT)	TON	58	58
40600909	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9, 5FG, N90	TON	1523	1523
40600990	TEMPORARY RAMP	SQ YD	1040	1,040
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3046	3,046
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	337	337
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	39,005	39,005
44201385	CLASS C PATCHES, TYPE I, 13 INCH	SQ YD	194	194
44201389	CLASS C PATCHES, TYPE II, 13 INCH	SQ YD	535	535
44201394	CLASS C PATCHES, TYPE III, 13 INCH	SQ YD	16	16
44201396	CLASS C PATCHES, TYPE IV, 13 INCH	SQ YD	40	40
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1