

78000600		
THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
Location	Foot	Remarks
Sta. 3+51 To Sta. 4+13	125.1	Solid (white)
Sta. 10+03 To Sta. 10+50	101.1	"
Sta. 14+20 To Sta. 14+42	63.1	"
Sta. 14+52 To Sta. 15+34	246.2	Solid (white)
Sta. 15+43 To Sta. 15+67	70.1	"
Sta. 30+87 To Sta. 31+12	81.7	"
Sta. 47+35 To Sta. 47+74	146.1	Solid (white)
Sta. 47+91	4.0	Stop Bar (white)
Sta. 54+96 To Sta. 55+83	292.3	Solid (white)
Sta. 56+03	4.0	Stop Bar (white)
Sta. 64+27 To Sta. 65+15	302.7	Solid (white)
Sta. 65+36	4.0	Stop Bar (white)
Sta. 75+91 To Sta. 77+02	373.4	Solid (white)
Sta. 77+27	4.0	Stop Bar (white)
Sta. 82+29	4.0	"
Sta. 84+25	4.0	"
Sta. 127+85	4.0	Stop Bar (white)
Sta. 127+93 To Sta. 128+63	183.4	Solid (white)
Sta. 133+28 To Sta. 133+78	142.9	Solid (white)
Sta. 144+00	4.0	Stop Bar (white)
Sta. 144+08 To Sta. 144+59	122.8	Solid (white)
Sta. 144+79	4.0	Stop Bar (white)
Sta. 151+98	4.0	Stop Bar (white)
Sta. 152+15 To Sta. 152+45	104.9	Solid (white)
Sta. 152+63	4.0	Stop Bar (white)
Sta. 162+01 To Sta. 162+31	102.6	Solid (white)
Sta. 162+49	4.0	Stop Bar (white)
Sta. 166+05	4.0	Stop Bar (white)
Sta. 166+19 To Sta. 166+49	101.9	Solid (white)
Sta. 171+94	4.0	Stop Bar (white)
TOTAL	2,616.3	

78000650		
THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
Location	Foot	Remarks
14.4' Lt. Sta. 14+32	19.8	Stop Bar (white)
6.0' Rt. Sta. 15+14	23.4	Stop Bar (white)
4.0' Rt. Sta. 15+55	23.1	Stop Bar (white)
TOTAL	66.3	

78001130		
PAINT PAVEMENT MARKING - LINE 6"		
Location	Foot	Remarks
Sta. 83+05 To Sta. 84+17	181.9	Solid (white)
Sta. 138+23 To Sta. 139+08	166.0	"
Sta. 139+26 To Sta. 139+51	42.3	"
Sta. 170+86 To Sta. 171+80	203.4	Solid (white)
TOTAL	593.6	

78001150			
PAINT PAVEMENT MARKING - LINE 12"			
Location	Foot	Remarks	
Sta. 83+05 To Sta. 84+17	313.0	Solid (white)	
Sta. 138+23 To Sta. 139+08	248.9	"	
Sta. 139+26 To Sta. 139+51	63.9	"	
Sta. 170+86 To Sta. 171+80	300.3	Solid (white)	
Sta. 3+48	4.0	Stop Bar (white)	
Sta. 10+59	4.0	"	
Sta. 14+15	4.0	"	
Sta. 15+74	4.0	"	
Sta. 30+81	4.0	"	
Sta. 31+19	4.0	"	
Sta. 47+21	4.0	"	
Sta. 54+82	4.0	"	
Sta. 64+12	4.0	"	
Sta. 75+74	4.0	"	
Sta. 102+88	4.0	"	
Sta. 103+57	4.0	"	
Sta. 111+30	4.0	Stop Bar (white)	
Sta. 112+16	4.0	"	
Sta. 128+69	4.0	"	
Sta. 133+24	4.0	"	
Sta. 133+81	4.0	"	
Sta. 138+15	4.0	"	
Sta. 139+59	4.0	"	
Sta. 161+90	4.0	"	
Sta. 166+63	4.0	"	
Sta. 170+76	4.0	Stop Bar (white)	
TOTAL	1,014.1		

78001180			
PAINT PAVEMENT MARKING - LINE 24"			
Location	Foot	Remarks	
19.3' Lt. Sta. 138+58	36.0	Stop Bar (white)	
TOTAL	36.0		

78300100			
PAVEMENT MARKING REMOVAL			
Location	Sq Ft	Remarks	
11.9' Rt. Sta. 14+30	39.9		
1.7' Lt. Sta. 15+15	39.9		
22.5' Lt. Sta. 15+55	39.7		
15.8' Lt. Sta. 138+58	69.9		
TOTAL	189.4		

81028200			
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.			
Location	Foot	Remarks	
12.4' Lt. Sta. 14+06 To 2.0' Rt. Sta. 14+14	17		
10.0' Lt. Sta. 15+38 To 17.6' Lt. Sta. 15+40	7		
10.6' Lt. Sta. 15+71 To 2.0' Rt. Sta. 15+75	13		
2.0' Rt. Sta. 75+82 To 29.8' Rt. Sta. 75+99	35		
11.1' Rt. Sta. 77+07 To 2.0' Rt. Sta. 77+11	10		
15.5' Lt. Sta. 84+04 To 10' Lt. Sta. 84+08	8		
2.0' Rt. Sta. 138+16 To 8.8' Lt. Sta. 138+19	11		
12.0' Lt. Sta. 139+60 To 13.5' Lt. Sta. 139+63	3		
5.3' Lt. Sta. 170+77 To 2.0' Rt. Sta. 170+77	8		
TOTAL	112		

81028220		
UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.		
Location	Foot	Remarks
13.1' Rt. Sta. 77+07 To 2.0' Rt. Sta. 77+32	27	
TOTAL	27	

85700200		
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET		
Location	Each	Remarks
17.6' Lt. Sta. 14+02	1	
TOTAL	1	

87502480		
TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.		
Location	Each	Remarks
2' Rt. Sta. 14+14	1	
17.5' Lt. Sta. 15+39.5	1	
2' Rt. Sta. 15+75	1	
2' Rt. Sta. 75+82	1	
2' Rt. Sta. 77+11	1	
10' Lt. Sta. 84+08	1	
2' Rt. Sta. 138+16	1	
2' Rt. Sta. 139+19.5	1	
12' Lt. Sta. 139+60	1	
TOTAL	9	

87800115		
CONCRETE FOUNDATION, TYPE A		
Location	Each	Remarks
2' Rt. Sta. 14+14	1	
17.5' Lt. Sta. 15+39.5	1	
2' Rt. Sta. 15+75	1	
2' Rt. Sta. 75+82	1	
2' Rt. Sta. 77+11	1	
10' Lt. Sta. 84+08	1	
2' Rt. Sta. 138+16	1	
2' Rt. Sta. 139+19.5	1	
12' Lt. Sta. 139+60	1	
TOTAL	9	

87800200		
CONCRETE FOUNDATION, TYPE D		
Location	Foot	Remarks
17.6' Lt. Sta. 14+02	3	
TOTAL	3	

87800415		
CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER		
Location	Foot	Remarks
2' Rt. Sta. 77+31.8	13	
2' Rt. Sta. 170+77	13	
TOTAL	26	

87900200		
DRILL EXISTING HANDHOLE		
Location	Each	Remarks
14.7' Lt. Sta. 14+06	1	
10.0' Lt. Sta. 15+38	1	
10.6' Lt. Sta. 15+71	1	
29.8' Rt. Sta. 75+99	1	
11.1' Rt. Sta. 77+07	1	
13.1' Rt. Sta. 77+07	1	
15.5' Lt. Sta. 84+04	1	
8.8' Lt. Sta. 138+19	1	
13.5' Lt. Sta. 139+63	1	
TOTAL	9	

88102717		
PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER		
Location	Each	Remarks
2' Rt. Sta. 14+14	1	
2' Rt. Sta. 15+75	1	
2' Rt. Sta. 75+82	1	
2' Rt. Sta. 77+11	1	
39.1' Rt. Sta. 83+05	1	
10' Lt. Sta. 84+08	1	
2' Rt. Sta. 138+16	1	
12' Lt. Sta. 139+60	1	
TOTAL	8	

88102747		
PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER		
Location	Each	Remarks
17.0' Lt. Sta. 14+44	1	
17.5' Lt. Sta. 15+39.5	1	
2' Rt. Sta. 139+19.5	1	
TOTAL	3	

88800100		
PEDESTRIAN PUSH-BUTTON		
Location	Each	Remarks
2' Rt. Sta. 14+14	1	
2' Rt. Sta. 15+75	1	
2' Rt. Sta. 75+82	1	
2' Rt. Sta. 77+11	1	
39.1' Rt. Sta. 83+05	1	
10' Lt. Sta. 84+08	1	
2' Rt. Sta. 138+16	1	
12' Lt. Sta. 139+60	1	
TOTAL	8	

89500100		
RELOCATE EXISTING SIGNAL HEAD		
Location	Each	Remarks
2' Rt. Sta. 139+19.5	2	
TOTAL	2	

89501300		
RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE		
Location	Each	Remarks
2' Rt. Sta. 77+31.8	1	
2' Rt. Sta. 170+77	1	
TOTAL	2	

FILE = S:\PROJECTS\2001\1139001_PHASE II\DESIGN\PHASE 2 SUMMARY OF QUANTITIES.DGN

REVISION	DATE	BY	REMARKS
*1	03/22/13	TJA	100% COMMENTS FROM JAN. 28, 2013

DRAWN	T.J.A.
CHECKED	C.J.B.
APPROVED	C.J.B.

WINNEBAGO COUNTY
VILLAGE OF CHERRY VALLEY
PERRYVILLE PATH SOUTHEAST CONNECTION



PERRYVILLE PATH
SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01-00302-00-BT	WINNEBAGO	124	8
STA.	STA.		
WHA #:	DATE:		
1139001	03/01/2013		