SUMMARY OF QUANTITIES

	Code No.	Item	Unit	Total Quantity	80% FED 20% STATE 0005	100% STATE 0005	80% FED 20% STATE 0021	100% APS JOLIET RICHARDS ST WASHINGTON ST 0021		
	20200100	EARTH EXCAVATION	CU YD	45	45					
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	25	25					
	25200110	SODDING, SALT TOLERANT	SQ YD	25	25					
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	6500	6500					
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	4710	4710					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	200	200					
	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	1214	1214					
	42001300	PROTECTIVE COAT	SQ YD	30	30					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4560	4560	1				
	42400800	DETECTABLE WARNINGS	SQ FT	320	320					
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	14445	14445					
	44000600	SIDEWALK REMOVAL	SQ FT	1250	1250	1				
	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	225	225					
	44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	250	250					
	44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	50	50					
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4					
	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2					
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4					
	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3					
	60406001	FRAMES AND LIDS, TYPE 1,ADA COMPLIANT, OPEN LID	EACH	2	2					
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3					
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125					
	63200310	GUARDRAIL REMOVAL	FOOT	125	125					
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	45	45					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3					
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1					
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1					
*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	10	10					
	67100100	MOBILIZATION	L SUM	1	1					
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102634	TRAFFIC CONTROL AND PROTECTION, STANDARD 701611	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	2250	2250					
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	750	750					
	70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	720	720					
	70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	3000	3000					
	70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	1800	1800					
	70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	FOOT	240	240					
	70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	2400	2400					
*	70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	700	700					

SUMMARY OF QUANTITIES

	Code No.	Item	Unit	Total Quantity	80% FED 20% STATE 0005	100% STATE 0005	80% FED 20% STATE 0021	100% APS JOLIET RICHARDS ST WASHINGTON ST 0021		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	360	360					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1500	1500					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	900	900					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	120	120					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1200	1200					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	210	210					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120	120					
	78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	1980	1980					
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	59			22	37		
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1914			471	1443		
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1040			733	307		
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1914			471	1443		
*	87900200	DRILL EXISTING HANDHOLE	EACH	8			4	4		
*	89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	1			1			
*	89502200	MODIFY EXISTING CONTROLLER	EACH	3			2	1		
*	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	20			20			
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4			2	2		
	X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1					
	~~X0327611~~	~~REMOVE AND REINSTALL BRICK PAVER~~	~~SQ FT~~	~~200~~	~~200~~					
	X0327989	REMOVE EXISTING BRICK PAVERS	SQ FT	3310	3310	1				
*	X1400378	PEDESTRIAN SIGNAL POST, 5 FT.	EACH	8			4	4		
	X4400501	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET	FOOT	195	195					
	X4400503	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT GREATER THAN 10 FEET	FOOT	30	30					
	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	200		200				
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	49	49					
	X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	8	8					
*	X8140238	REBUILD EXISTING DOUBLE HANDHOLE	EACH	1				1		
*	X8760200	ACCESSIBLE PEDESTRIAN SIGNALS	EACH	30			16	14		
*	X8780012	CONCRETE FOUNDATION, TYPE A 12-INCH DIAMETER	FOOT	32			16	16		
*	X8860105	DETECTOR LOOP REPLACEMENT	FOOT	2940			2940			
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30		30				
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8					

* SPECIALTY ITEM

1 REVISED SHEET 5/31/2024

MODEL: SOQ02 [Sheet]
FILE NAME: pw://ildot-pw.bentley.com:PWIDOT/Documents/IDOT Offices/District 1/ORD Projects/D127622/CADData/CADsheets/-sht-SOQ.dgn

USER NAME = Fritz.Guillaume	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = $SCALE$	CHECKED -	REVISED -	
PLOT DATE = 4/3/2024	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
COLLINS ST. (ART SCHULTZ DR. TO US 6)

SCALE: 1"=50' | SHEET 000 OF 4 SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	FAP 0607 22 RS2	WILL	49	3

CONTRACT NO. 62T55

ILLINOIS | FED. AID PROJECT