If you plan to submit a bid directly to the Department of Transportation

PREQUALIFICATION

Any contractor who desires to become pre-qualified to bid on work advertised by IDOT must submit the properly completed pre-qualification forms to the Bureau of Construction no later that 4:30 p.m. prevailing time twenty-one days prior to the letting of interest. This pre-qualification requirement applies to first time contractors, contractors renewing expired ratings, contractors maintaining continuous pre-qualification or contractors requesting revised ratings. To be eligible to bid, existing pre-qualification ratings must be effective through the date of letting.

REQUESTS FOR AUTHORIZATION TO BID

Contractors downloading and/or ordering CD-ROM's and are wanting to bid on items included in a particular letting must submit the properly completed "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) and the ORIGINAL, signed and notarized, "Affidavit of Availability" (BC 57) to the proper office no later than 4:30 p.m. prevailing time, three (3) days prior to the letting date.

WHO CAN BID?

Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction.

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID? When a prospective prime bidder submits a "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Proposal Denial and/or Authorization Form, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Proposal Denial and/or Authorization Form will indicate the reason for denial.

ABOUT AUTHORIZATION TO BID: Firms that have not received an authorization form within a reasonable time of complete and correct original document submittal should contact the department as to status. This is critical in the week before the letting. These documents must be received three days before the letting date. Firms unsure as to authorization status should call the Prequalification Section of the Bureau of Construction at the number listed at the end of these instructions.

ADDENDA AND REVISIONS: It is the contractor's responsibility to determine which, if any, addenda or revisions pertain to any project they may be bidding. Failure to incorporate all relevant addenda or revisions may cause the bid to be declared unacceptable.

Each addendum will be placed with the contract number. Addenda and revisions will also be placed on the Addendum/Revision Checklist and each subscription service subscriber will be notified by e-mail of each addendum and revision issued.

The Internet is the Department's primary way of doing business. The subscription server e-mails are an added courtesy the Department provides. It is suggested that bidder check IDOT's website http://www.dot.il.gov/desenv/delett.html before submitting final bid information.

IDOT is not responsible for any e-mail related failures.

Addenda Questions may be directed to the Contracts Office at (217)782-7806 or D&Econtracts@dot.il.gov

Technical Questions about downloading these files may be directed to Tim Garman (217)524-1642 or garmantr@dot.il.gov.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

ABOUT SUBMITTING BIDS: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

| Questions Regarding | Call |
|--|---------------|
| Prequalification and/or Authorization to Bid | (217)782-3413 |
| Preparation and submittal of bids | (217)782-7806 |
| Mailing of plans and proposals | (217)782-7806 |
| Electronic plans and proposals | (217)524-1642 |

ADDENDUMS AND REVISIONS TO THE PROPOSAL FORMS

Planholders should verify that they have received and incorporated the addendum and/or revision prior to submitting their bid. Failure by the bidder to include an addendum could result in a bid being rejected as irregular.

83

| ILLIOUN WITH BID |
|-----------------------|
| Proposal Submitted By |
| |
| Name |
| |
| Address |
| |
| City |

Letting June 15, 2007

NOTICE TO PROSPECTIVE BIDDERS

This proposal can be used for bidding purposes by only those companies that request and receive written AUTHORIZATION TO BID from IDOT's Central Bureau of Construction. (SEE INSTRUCTIONS ON THE INSIDE OF COVER)

Notice To Bidders, Specifications, Proposal, Contract and Contract Bond



Springfield, Illinois 62764

Contract No. 44959
Various Counties
Section D1 H-T PVT MKG REP 2007-08
District 1 Construction Funds
Various Routes

| PLEASE MARK THE APPROPRIATE BOX BELOW: | |
|---|--|
| ☐ A <u>Bid Bond</u> is included. | |
| ☐ A <u>Cashier's Check</u> or a <u>Certified Check</u> is included. | |

Plans Included Herein

Prepared by

S

Checked by

Printed by authority of the State of Illinois)

BIDDERS NEED NOT RETURN THE ENTIRE PROPOSAL (See instructions inside front cover)

INSTRUCTIONS

ABOUT IDOT PROPOSALS: All proposals issued by IDOT are potential bidding proposals. Each proposal contains all Certifications and Affidavits, a Proposal Signature Sheet and a Proposal Bid Bond required for Prime Contractors to submit a bid after written **Authorization to Bid** has been issued by IDOT's Central Bureau of Construction.

WHO CAN BID?: Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction. To request authorization, a potential bidder <u>must complete and submit Part B of the Request for Authorization to Bid/or Not For Bid Status form (BDE 124 INT) and submit an original Affidavit of Availability (BC 57).</u>

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Request for Proposal Forms and Plans" he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Proposal Denial and/or Authorization Form, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Proposal Denial and/or Authorization Form will indicate the reason for denial. If a contractor has requested to bid but has not received a Proposal Denial and/or Authorization Form, they should contact the Central Bureau of Construction in advance of the letting date.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

ABOUT SUBMITTING BIDS: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

Call

WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Pagarding

| Questions Negarang | Call |
|---|--|
| Prequalification and/or Authorization to Bid Preparation and submittal of bids Mailing of CD-ROMS | 217/782-3413 217/782-7806 217/782-7806 |
| | |



PROPOSAL

TO THE DEPARTMENT OF TRANSPORTATION

| 1. Proposal of | |
|---|------------------------------------|
| Taxpayer Identification Number (Mandatory) | a |
| for the improvement identified and advertised for b | ids in the Invitation for Bids as: |
| Contract No. 44959 Various Counties Section D1 H-T PVT MKG REP 2007-08 Various Routes District 1 Construction Funds | |

Removal and replacement of various types, sizes and widths of pavement markings to be done by individual work orders.

2. The undersigned bidder will furnish all labor, material and equipment to complete the above described project in a good and workmanlike manner as provided in the contract documents provided by the Department of Transportation. This proposal will become part of the contract and the terms and conditions contained in the contract documents shall govern performance and payments.

- 3. **ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER.** The undersigned further declares that he/she has carefully examined the proposal, plans, specifications, form of contract and contract bond, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he/she waives all right to plead any misunderstanding regarding the same.
- 4. **EXECUTION OF CONTRACT AND CONTRACT BOND.** The undersigned further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bond satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
- 5. **PROPOSAL GUARANTY.** Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

| <u>A</u> | mount o | of Bid | Proposal <u>Guaranty</u> | <u>Am</u> | ount c | of Bid | Proposal <u>Guaranty</u> |
|-------------|---------|-------------|-----------------------------|--------------|--------|--------------|-----------------------------|
| Up to | | \$5,000 | \$150 | \$2,000,000 | to | \$3,000,000 | \$100,000 |
| \$5,000 | to | \$10,000 | \$300 | \$3,000,000 | to | \$5,000,000 | \$150,000 |
| \$10,000 | to | \$50,000 | \$1,000 | \$5,000,000 | to | \$7,500,000 | \$250,000 |
| \$50,000 | to | \$100,000 | \$3,000 | \$7,500,000 | to | \$10,000,000 | \$400,000 |
| \$100,000 | to | \$150,000 | \$5,000 | \$10,000,000 | to | \$15,000,000 | \$500,000 |
| \$150,000 | to | \$250,000 | \$7,500 | \$15,000,000 | to | \$20,000,000 | \$600,000 |
| \$250,000 | to | \$500,000 | \$12,500 | \$20,000,000 | to | \$25,000,000 | \$700,000 |
| \$500,000 | to | \$1,000,000 | \$25,000 | \$25,000,000 | to | \$30,000,000 | \$800,000 |
| \$1,000,000 | to | \$1,500,000 | \$50,000 | \$30,000,000 | to | \$35,000,000 | \$900,000 |
| \$1,500,000 | to | \$2,000,000 | \$75,000 | over | | \$35,000,000 | \$1,000,000 |

Bank cashier's checks or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois, when the state is awarding authority; the county treasurer, when a county is the awarding authority; or the city, village, or town treasurer, when a city, village, or town is the awarding authority.

| If a combination bid is submitted, | the proposal guaranties which | accompany the individual | proposals making up the | combination will be consi | idered as |
|------------------------------------|-------------------------------|--------------------------|-------------------------|---------------------------|-----------|
| also covering the combination bid. | | | | | |

The amount of the proposal guaranty check is _______\$(). If this proposal is accepted and the undersigned shall fail to execute a contract bond as required herein, it is hereby agreed that the amount of the proposal guaranty shall become the property of the State of Illinois, and shall be considered as payment of damages due to delay and other causes suffered by the State because of the failure to execute said contract and contract bond; otherwise, the bid bond shall become void or the proposal guaranty check shall be returned to the undersigned.

Attach Cashier's Check or Certified Check Here

In the event that one proposal guaranty check is intended to cover two or more proposals, the amount must be equal to the sum of the proposal guaranties which would be required for each individual proposal. If the guaranty check is placed in another proposal, state below where it may be found.

| The proposal quarant | ty check will be found in the proposal for: | Item | |
|----------------------|--|---------|--|
| The proposal guaran | ly check will be loured in the proposal for. | 11.0111 | |

Section No.

County

Mark the proposal cover sheet as to the type of proposal guaranty submitted.

BD 354 (Rev. 11/2001)

6. **COMBINATION BIDS.** The undersigned further agrees that if awarded the contract for the sections contained in the following combination, he/she will perform the work in accordance with the requirements of each individual proposal comprising the combination bid specified in the schedule below, and that the combination bid shall be prorated against each section in proportion to the bid submitted for the same. If an error is found to exist in the gross sum bid for one or more of the individual sections included in a combination, the combination bid shall be corrected as provided in the specifications.

When a combination bid is submitted, the schedule below must be completed in each proposal comprising the combination.

If alternate bids are submitted for one or more of the sections comprising the combination, a combination bid must be submitted for each alternate.

Schedule of Combination Bids

| Combination | | Combination Bid | | |
|-------------|----------------------------------|-----------------|-------|--|
| No. | Sections Included in Combination | Dollars | Cents | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

- 7. SCHEDULE OF PRICES. The undersigned bidder submits herewith, in accordance with the rules and instructions, a schedule of prices for the items of work for which bids are sought. The unit prices bid are in U.S. dollars and cents, and all extensions and summations have been made. The bidder understands that the quantities appearing in the bid schedule are approximate and are provided for the purpose of obtaining a gross sum for the comparison of bids. If there is an error in the extension of the unit prices, the unit prices shall govern. Payment to the contractor awarded the contract will be made only for actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as provided elsewhere in the contract.
- 8. **CERTIFICATE OF AUTHORITY.** The undersigned bidder, if a business organized under the laws of another State, assures the Department that it will furnish a copy of its certificate of authority to do business in the State of Illinois with the return of the executed contract and bond. Failure to furnish the certificate within the time provided for execution of an awarded contract may be cause for cancellation of the award and forfeiture of the proposal guaranty to the State.

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 44959

State Job # - C-60-001-08
PPS NBR - 0-00488-0000
County Name - VARIOUS- -

Code - 0 - - District - 1 - -

Section Number - D 1 H-T PVT MKG REP 2007-08

| Project Number | Route |
|----------------|---------|
| | VARIOUS |

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|------------|---|------------|---|-------------|
| X7800500 | POLYUREA PM LT-SY SPL | SQ FT | 1,100.000 | | | | |
| X7800510 | POLYUREA PM SPL LN 4 | FOOT | 26,000.000 | | | | |
| X7800520 | POLYUREA PM SPL LN 5 | FOOT | 11,000.000 | | | | |
| X7800530 | POLYUREA PM SPL LN 6 | FOOT | 3,800.000 | | | | |
| X7800540 | POLYUREA PM SPL LN 8 | FOOT | 3,800.000 | | | | |
| X7800550 | POLYUREA PM SPL LN 12 | FOOT | 3,800.000 | | | | |
| X7800580 | POLYUREA PM SPL LN 24 | FOOT | 3,800.000 | | | | |
| X7800600 | URETHANE PM LT-SY SPL | SQ FT | 1,000.000 | | | | |
| X7800610 | URETH PAVT MK LINE 4 | FOOT | 4,800.000 | | | | |
| X7800620 | URETH PAVT MK LINE 5 | FOOT | 4,800.000 | | | | |
| X7800630 | | FOOT | 4,800.000 | | | | |
| X7800640 | | FOOT | 4,800.000 | | | | |
| X7800650 | URETH PAVT MK LINE 12 | FOOT | 2,800.000 | | | | |
| X7800680 | | FOOT | 1,000.000 | | | | |
| 67100100 | | L SUM | 1.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 44959

State Job # - C-60-001-08
PPS NBR - 0-00488-0000
County Name - VARIOUS- -

Code - VARIO

Code - 0 -
District - 1 - -

Section Number - D 1 H-T PVT MKG REP 2007-08

| Project Number | Route |
|----------------|---------|
| | VARIOUS |

| Item Number | Pay Item Description | Unit of Measure | Quantity | х | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-------------|---|------------|---|-------------|
| 70101700 | TRAF CONT & PROT | L SUM | 1.000 | | | | |
| 78000100 | THPL PVT MK LTR & SYM | SQ FT | 20,000.000 | | | | |
| 78000200 | THPL PVT MK LINE 4 | FOOT | 257,000.000 | | | | |
| 78000300 | THPL PVT MK LINE 5 | FOOT | 26,000.000 | | | | |
| 78000400 | THPL PVT MK LINE 6 | FOOT | 39,000.000 | | | | |
| 78000500 | THPL PVT MK LINE 8 | FOOT | 8,400.000 | | | | |
| 78000600 | THPL PVT MK LINE 12 | FOOT | 12,400.000 | | | | |
| 78000650 | THPL PVT MK LINE 24 | FOOT | 8,400.000 | | | | |
| 78000815 | HS THPL PM LN 4 | FOOT | 95,000.000 | | | | |
| 78000825 | HS THPL PM LN 5 | FOOT | 47,000.000 | | | | |
| 78000845 | HS THPL PM LN 8 | FOOT | 17,000.000 | | | | |
| 78003100 | PREF PL PM TB LTR-SYM | SQ FT | 350.000 | | | | |
| 78003110 | PREF PL PM TB LINE 4 | FOOT | 400.000 | | | | |
| 78003120 | | FOOT | 400.000 | | | | |
| 78003130 | PREF PL PM TB LINE 6 | FOOT | 400.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 44959 **NUMBER -**

C-60-001-08 State Job # -PPS NBR -0-00488-0000 County Name -

VARIOUS--

Code -0 - -District -1 - -

Section Number -D 1 H-T PVT MKG REP 2007-08

| Project Number | Route |
|----------------|---------|
| | VARIOUS |

| Item Number | Pay Item Description | Unit of Measure Quantity | | | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------------|-------------|--|------------|---|-------------|
| 78003140 | PREF PL PM TB LINE 8 | FOOT | 400.000 | | | | |
| 78003150 | PREF PL PM TB LINE 12 | FOOT | 400.000 | | | | |
| 78003180 | PREF PL PM TB LINE 24 | FOOT | 270.000 | | | | |
| 78006100 | PREF THPL PM LTR-SYM | SQ FT | 370.000 | | | | |
| 78006110 | PREF THPL PM LINE 4 | FOOT | 450.000 | | | | |
| 78006120 | PREF THPL PM LINE 5 | FOOT | 450.000 | | | | |
| 78006130 | PREF THPL PM LINE 6 | FOOT | 450.000 | | | | |
| 78006140 | PREF THPL PM LINE 8 | FOOT | 450.000 | | | | |
| 78006150 | PREF THPL PM LINE 12 | FOOT | 450.000 | | | | |
| 78006180 | PREF THPL PM LINE 24 | FOOT | 450.000 | | | | |
| 78008210 | POLYUREA PM T1 LN 4 | FOOT | 59,000.000 | | | | |
| 78008220 | | FOOT | 19,000.000 | | | | |
| 78008230 | | FOOT | 6,900.000 | | | | |
| 78008240 | | FOOT | 6,900.000 | | | | |
| 78300100 | PAVT MARKING REMOVAL | SQ FT | 165,000.000 | | | | |

| CON | ITD | ACT | A I I | 1841 | |
|-----|------|-----|-------|-------|-----|
| CON | II K | ACI | Nι | וואוע | SER |

44959

NOTES:

- 1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.
- 2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.
- 3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.
- 4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.

STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

I. GENERAL

- **A.** Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. By execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances has been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for termination of the contract and the suspension or debarment of the bidder.

II. ASSURANCES

A. The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous assurance, and the surety providing the performance bond shall be responsible for the completion of the contract.

B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any state agency from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-10.

C. Conflicts of Interest

1. The Illinois Procurement Code provides in pertinent part:

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois Toll Highway authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$150,700.00. Sixty percent of the salary is \$90,420.00.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code and Executive Order Number 3 (1998). Information concerning the exemption process is available from the Department upon request.

D. Negotiations

1. The Illinois Procurement Code provides in pertinent part:

Section 50-15. Negotiations.

- (a) It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.
- 2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

E. Inducements

1. The Illinois Procurement Code provides:

Section 50-25. Inducement. Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

F. Revolving Door Prohibition

1. The Illinois Procurement Code provides:

Section 50-30. Revolving door prohibition. Chief procurement officers, associate procurement officers, State purchasing officers, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

G. Reporting Anticompetitive Practices

1. The Illinois Procurement Code provides:

Section 50-40. Reporting anticompetitive practices. When, for any reason, any vendor, bidder, contractor, chief procurement officer, State purchasing officer, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offerors, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the chief procurement officer.

2. The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

H. Confidentiality

1. The Illinois Procurement Code provides:

Section 50-45. Confidentiality. Any chief procurement officer, State purchasing officer, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

2. The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

I. Insider Information

1. The Illinois Procurement Act provides:

Section 50-50. Insider information. It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

2. The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

III. CERTIFICATIONS

A. The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous certification, and the surety providing the performance bond shall be responsible for completion of the contract.

B. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
 - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
 - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
 - (1) the business has been finally adjudicated not guilty; or
 - (2) the business demonstrates to the governmental entity with which it seeks to contract, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State shall contain a certification by the contractor that the contractor is not barred from being awarded a contract or subcontract under this Section. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The bidder certifies that it is not barred from being awarded a contract under Section 50.5.

C. Educational Loan

- 1. Section 3 of the Educational Loan Default Act provides:
- § 3. No State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.
- 2. The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

D. Bid-Rigging/Bid Rotating

1. Section 33E-11 of the Criminal Code of 1961 provides:

§ 33E-11. (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article. The State and units of local government shall provide the appropriate forms for such certification.

(b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

2. The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33E-4.

E. International Anti-Boycott

- 1. Section 5 of the International Anti-Boycott Certification Act provides:
- § 5. State contracts. Every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.
- 2. The bidder makes the certification set forth in Section 5 of the Act.

F. Drug Free Workplace

- 1. The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.
- 2. The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace by:
- (a) Publishing a statement notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the contractor's workplace; specifying the actions that will be taken against employees for violations of such prohibition; and notifying the employee that, as a condition of employment on such contract, the employee shall abide by the terms of the statement, and notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
- (b) Establishing a drug free awareness program to inform employees about the dangers of drug abuse in the workplace; the contractor's policy of maintaining a drug free workplace; any available drug counseling, rehabilitation, and employee assistance programs; and the penalties that may be imposed upon employees for drug violations.
- (c) Providing a copy of the statement required by subparagraph (1) to each employee engaged in the performance of the contract and to post the statement in a prominent place in the workplace.
- (d) Notifying the Department within ten (10) days after receiving notice from an employee or otherwise receiving actual notice of the conviction of an employee for a violation of any criminal drug statute occurring in the workplace.
- (e) Imposing or requiring, within 30 days after receiving notice from an employee of a conviction or actual notice of such a conviction, an appropriate personnel action, up to and including termination, or the satisfactory participation in a drug abuse assistance or rehabilitation program approved by a federal, state or local health, law enforcement or other appropriate agency.
- (f) Assisting employees in selecting a course of action in the event drug counseling, treatment, and rehabilitation is required and indicating that a trained referral team is in place.
- (g) Making a good faith effort to continue to maintain a drug free workplace through implementation of the actions and efforts stated in this certification.

G. Debt Delinquency

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder certifies that it, or any affiliate, is not barred from being awarded a contract under 30 ILCS 500. Section 50-11 prohibits a person from entering into a contract with a State agency if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The contractor further acknowledges that the contracting State agency may declare the contract void if this certification is false or if the contractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

H. Sarbanes-Oxley Act of 2002

1. The Illinois Procurement Code provides:

Section 50-60(c).

The contractor certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 for a period of five years prior to the date of the bid or contract. The contractor acknowledges that the contracting agency shall declare the contract void if this certification is false.

I. Addenda

The contractor or bidder certifies that all relevant addenda have been incorporated in to this contract. Failure to do so may cause the bid to be declared unacceptable.

J. Section 42 of the Environmental Protection Act

The contractor certifies in accordance with 30 ILCS 500/50-12 that the bidder or contractor is not barred from being awarded a contract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The contractor acknowledges that the contracting agency may declare the contract void if this certification is false.

K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

L. Executive Order Number 1 (2007) Regarding Lobbying on Government Procurements

The bidder hereby warrants and certifies that they have complied and will comply with the requirements set forth in this Order. The requirements of this warrant and certification are a material part of the contract, and the contractor shall require this warrant and certification provision to be included in all approved subcontracts.

TO BE RETURNED WITH BID

IV. DISCLOSURES

A. The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous disclosure, and the surety providing the performance bond shall be responsible for completion of the contract.

B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all bids of more than \$10,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies. **The forms must be included with each bid or incorporated by reference.**

C. <u>Disclosure Form Instructions</u>

Form A: For bidders that have previously submitted the information requested in Form A

The Department has retained the Form A disclosures submitted by all bidders responding to these requirements for the April 24, 1998 or any subsequent letting conducted by the Department. The bidder has the option of submitting the information again or the bidder may sign the following certification statement indicating that the information previously submitted by the bidder is, as of the date of signature, current and accurate. The Certification must be signed and dated by a person who is authorized to execute contracts for the bidding company. Before signing this certification, the bidder should carefully review its prior submissions to ensure the Certification is correct. If the Bidder signs the Certification, the Bidder should proceed to Form B instructions.

CERTIFICATION STATEMENT

| I have determined that the Form A disclosure information previously submitted is current and accurate, and all forms are hereby incorporated by reference in this bid. Any necessary additional forms or amendments to previously submitted forms are attached to this bid. | | | | | | | | | |
|---|--------------------------|----------------------------|--|--|--|--|--|--|--|
| - | (Bidding Company) | | | | | | | | |
| - | Name of Authorized Repre | esentative (type or print) | Title of Authorized Representative (type or print) | | | | | | |
| | | Date | | | | | | | |

Form A: For bidders who have NOT previously submitted the information requested in Form A

D.

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note: These questions are for assistance only and are not required to be completed.

| 1. | Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO |
|-----------------------------------|--|
| 2. | Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than \$90,420.00? YES NO |
| 3. | Does anyone in your organization receive more than \$90,420.00 of the bidding entity's or parent entity's distributive income? (Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.) YES NO |
| 4. | Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than \$90,420.00? YES NO |
| | (Note: Only one set of forms needs to be completed <u>per person per bid</u> even if a specific individual would require a yes answer to more than one question.) |
| bidding e authorize | answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is ed to execute contracts for your organization. Photocopied or stamped signatures are not acceptable . The person signing can be, but have to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided. |
| | swer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by that is authorized to execute contracts for your company. |
| bidding e | Identifying Other Contracts & Procurement Related Information Disclosure Form B must be completed for each bid submitted by the entity. It must be signed by an individual who is authorized to execute contracts for the bidding entity. Note: Signing the NOT ABLE STATEMENT on Form A does not allow the bidder to ignore Form B. Form B must be completed, signed and dated or the bidder considered nonresponsive and the bid will not be accepted. |
| ongoing | ler shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the box on the bottom of Form B. If "Yes" is checked, the bidder must do one of the following: |
| agency p attached and are r | If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois pending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts not to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development ust be included. Bidders who submit Affidavits of Availability are suggested to use Option II. |
| "See Affi | If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type davit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of Illinois lending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases. |
| Bidders | Submitting More Than One Bid |
| | submitting multiple bids may submit one set of forms consisting of all required Form A disclosures and one Form B for use with all bids. Indicate in the space provided below the bid item that contains the original disclosure forms and the bid items which incorporate the forms note. |
| | ne bid submitted for letting item contains the Form A disclosures or Certification Statement and the Form B sclosures. The following letting items incorporate the said forms by reference: |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form A Financial Information & Potential Conflicts of Interest Disclosure

| Contractor Name | | |
|--|--|--|
| Legal Address | | |
| City, State, Zip | | |
| Telephone Number | Email Address | Fax Number (if available) |
| (30 ILCS 500). Vendors desiring to enternance and potential conflict of interest information the publicly available contract file. This ended contracts. A publicly traded contraction of the requirements set for | er into a contract with the State ion as specified in this Disclos s Form A must be completed company may submit a 10 | - |
| terms of ownership or distributive incom | ne share in excess of 5%, or a ary as of 7/1/01). (Make copic n individual meeting these re | ow has an interest in the BIDDER (or its parent) in interest which has a value of more than es of this form as necessary and attach a equirements) |
| ADDRESS | | |
| Type of ownership/distributable i | ncome share: | |
| stock sole proprietor % or \$ value of ownership/distributa | | other: (explain on separate sheet): |
| | | No" to indicate which, if any, of the following question is "Yes", please attach additional page: |
| | | ding contractual employment of services. YesNo |
| If your answer is yes, please ar | nswer each of the following qu | estions. |
| Are you currently an of Highway Authority? | ficer or employee of either the | Capitol Development Board or the Illinois Toll YesNo |
| currently appointed to | or employed by any agency of | agency of the State of Illinois? If you are the State of Illinois, and your annual salary as of 7/1/01) provide the name the State |

agency for which you are employed and your annual salary.

| | 3. | If you are currently appointed to or employed by any agency of the S salary exceeds \$90,420.00, (60% of the Governor's salary as of 7/1 (i) more than 7 1/2% of the total distributable income of your firm, corporation, or (ii) an amount in excess of the salary of the Governor | /01) are you entitled to receive partnership, association or |
|-----|------------------|--|--|
| | 4. | If you are currently appointed to or employed by any agency of the Salary exceeds \$90,420.00, (60% of the Governor's salary as of 7/1 or minor children entitled to receive (i) more than 15 % in the aggreincome of your firm, partnership, association or corporation, or (ii) are the salary of the Governor? | /01) are you and your spouse egate of the total distributable |
| (b) | | oyment of spouse, father, mother, son, or daughter, including contractions 2 years. | tual employment services |
| | If your answ | wer is yes, please answer each of the following questions. | YesNo |
| | 1. | Is your spouse or any minor children currently an officer or employee Board or the Illinois Toll Highway Authority? | of the Capitol Development YesNo |
| | 2. | Is your spouse or any minor children currently appointed to or employ of Illinois? If your spouse or minor children is/are currently appagency of the State of Illinois, and his/her annual salary exceed Governor's salary as of 7/1/01) provide the name of your spouse are of the State agency for which he/she is employed and his/her annual | pointed to or employed by any ls \$90,420.00, (60 % of the nd/or minor children, the name |
| | 3. | If your spouse or any minor children is/are currently appointed to or State of Illinois, and his/her annual salary exceeds \$90,420.00, (60% as of 7/1/01) are you entitled to receive (i) more then 71/2% of the tof firm, partnership, association or corporation, or (ii) an amount in Governor? | 6 of the salary of the Governor tal distributable income of your |
| | 4. | If your spouse or any minor children are currently appointed to or er State of Illinois, and his/her annual salary exceeds \$90,420.00, (60% 7/1/01) are you and your spouse or minor children entitled to rece aggregate of the total distributable income of your firm, partnership, (ii) an amount in excess of 2 times the salary of the Governor? | of the Governor's salary as of eive (i) more than 15 % in the association or corporation, or |
| | | | YesNo |
| | unit of | re status; the holding of elective office of the State of Illinois, the gover local government authorized by the Constitution of the State of Illinois currently or in the previous 3 years. | |
| | | onship to anyone holding elective office currently or in the previous 2 yr daughter. | rears; spouse, father, mother, YesNo |
| | Americ of the | ntive office; the holding of any appointive government office of the States, or any unit of local government authorized by the Constitution of the State of Illinois, which office entitles the holder to compensation in except and that office currently or in the previous 3 years. | ne State of Illinois or the statutes |
| | ` ' | nship to anyone holding appointive office currently or in the previous 2 daughter. | years; spouse, father, mother, YesNo |
| | (g) Emplo | yment, currently or in the previous 3 years, as or by any registered lob | obyist of the State government. YesNo |

| (h) Relationship to a son, or daughter. | inyone who is or was a registered lobbyist in the previous 2 years; spou YesN | | | | | | | |
|---|--|--|--|--|--|--|--|--|
| (i) Compensated employment, currently or in the previous 3 years, by any registered election or reelect committee registered with the Secretary of State or any county clerk of the State of Illinois, or any politic action committee registered with either the Secretary of State or the Federal Board of Elections. Yes No | | | | | | | | |
| last 2 years by ar county clerk of the | nyone; spouse, father, mother, son, or daughter; who was a compensa by registered election or re-election committee registered with the Secre e State of Illinois, or any political action committee registered with eith eral Board of Elections. Yes N | etary of State or any er the Secretary of | | | | | | |
| | | | | | | | | |
| | APPLICABLE STATEMENT | | | | | | | |
| This Disclosure Fo | rm A is submitted on behalf of the INDIVIDUAL named on previous | s page. | | | | | | |
| | · | | | | | | | |
| Completed by: | Name of Authorized Representative (type or print) | | | | | | | |
| Completed by: | Name of Authorized Representative (type of printy | | | | | | | |
| Completed by: | Title of Authorized Representative (type or print) | | | | | | | |
| Completed by: | | | | | | | | |
| | Signature of Individual or Authorized Representative | Date | | | | | | |
| | NOT APPLICABLE STATEMENT | | | | | | | |
| | that no individuals associated with this organization meet the crite tion of this Form A. | eria that would | | | | | | |
| This Disclosure Fo | rm A is submitted on behalf of the CONTRACTOR listed on the pre | evious page. | | | | | | |
| | Name of Authorized Representative (type or print) | | | | | | | |
| | Title of Authorized Representative (type or print) | | | | | | | |
| | Signature of Authorized Representative | Date | | | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

Form B Other Contracts & Procurement Related Information Disclosure

| | | | Diodiodar | |
|--|-------------------------------|--------------------------------|---|---|
| Contractor Name | | | | |
| Legal Address | | | | |
| City, State, Zip | | | | |
| Telephone Number | | Email Address | Fax Number (i | f available) |
| | ation shall become p | art of the publicly availa | | Illinois Procurement Act (3) rm B must be completed fo |
| DISCLOS | URE OF OTHER CO | ONTRACTS AND PRO | CUREMENT RELATED I | NFORMATION |
| pending contracts (incl of Illinois agency: Y | uding leases), bids, es No | proposals, or other ong | ation. The BIDDER shall id oing procurement relation are box on the bottom of the statement relation. | nship with any other State |
| | such as bid or proje | | g State of Illinois agency ional pages as necessary | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | THE FOL | LOWING STATEMENT | MUST BE SIGNED | |
| | Na | ame of Authorized Representa | tive (type or print) | |
| | Т | itle of Authorized Representat | ive (type or print) | |
| | | Signature of Authorized Re | epresentative | Date |

SPECIAL NOTICE TO CONTRACTORS

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



Contract No. 44959
Various Counties
Section D1 H-T PVT MKG REP 2007-08
Various Routes
District 1 Construction Funds

| | | | | | | | | | Distr | ict 1 | Cons | tructio | n Fu | ınds | | | | |
|---|-------------|------------------------|------------------|------------|-----------|----------|--------|--------------|------------|--------|---------|-----------------|-------|-------|--------------|------|---------------|----------------|
| PART I. IDENTIFIC | CATION | | | | | | | | | | | | | | | | | |
| Dept. Human Right | ts # | | | | | | _ Dur | ation o | f Proje | ect: | | | | | | | | |
| Name of Bidder: _ | | | | | | | | | | | | | | | | | | |
| PART II. WORKFO A. The undersigned which this contract we projection including a | d bidder ha | as analyz e perform | ed mir ed, an | d for that | ne locati | ons fro | m whic | h the b | idder re | cruits | employe | es, and h | erebý | submi | its the foll | owin | ig workfo | n orce |
| | | TOTA | AL Wo | rkforce | e Projec | tion for | Contra | ıct | | | | | | C | URRENT | | | ES . |
| | | | | MIN | ORITY I | EMPL C | YEES | | | TR | AINEES | | | | TO BE | | IGNED RACT | |
| JOB CATEGORIES | | TAL OYEES | BL | ACK | HISP | | | HER IOR. | APP TIC | | ON T | HE JOB INEES | | | TAL OYEES | ,,,, | MINC | ORITY OYEES |
| | М | F | М | F | М | F | М | F | М | F | М | F | | М | F | | М | F |
| OFFICIALS (MANAGERS) | | | | | | | | | | | | | | | | | | |
| SUPERVISORS | | | | | | | | | | | | | | | | | | |
| FOREMEN | | | | | | | | | | | | | | | | | | |
| CLERICAL | | | | | | | | | | | | | | | | | ı | |
| EQUIPMENT OPERATORS | | | | | | | | | | | | | | | | | | |
| MECHANICS | | | | | | | | | | | | | | | | | | |
| TRUCK DRIVERS | | | | | | | | | | | | | | | | | | |
| IRONWORKERS | | | | | | | | | | | | | | | | | | |
| CARPENTERS | | | | | | | | | | | | | | | | | — | |
| CEMENT MASONS | | | | | | | | | | | | | | | | | | |
| ELECTRICIANS PIPEFITTERS, PLUMBERS | | | | | | | | | | | | | | | | | | |
| PAINTERS | | | | | | | | | | | | | | | | | | |
| LABORERS, SEMI-SKILLED | | | | | | | | | | | | | | | | | | |
| LABORERS, UNSKILLED | | | | | | | | | | | | | | | | | | |
| TOTAL | | | | | | | | | | | | | | | | | <u> </u> | |
| | | BLE C | | | | | | | - 1 | | F | OR DEP | ARTN | ЛENT | USE ON | ILY | | |
| | TOTAL Tr | | ojectio T | n for C | Contract | | *^- | | 4 | | | | | | - | | | |
| EMPLOYEES IN | | TAL OYEES | BL | ACK | HISE | ANIC | | THER NOR. | | | | | | | | | | |
| TRAINING | M | F | M | F | M | F | M | F | | | | | | | | | | |
| APPRENTICES | | | | | | | | | | | | | | | | | | |

*Other minorities are defined as Asians (A) or Native Americans (N).

ON THE JOB TRAINEES

Please specify race of each employee shown in Other Minorities column.

Note: See instructions on the next page

BC 1256 - Pg 1 (Rev. 3/98) IL 494-0454

Contract No. 44959
Various Counties
Section D1 H-T PVT MKG REP 2007-08
Various Routes
District 1 Construction Funds

PART II. WORKFORCE PROJECTION - continued

| B. | | led in "Tot the unders | | | | | | | al num | ber c | of new | hire | s tha | at wou | ld b | e em | oloyed | in the | ! |
|----------|--|---|--|--|--|-------------------------------|--|-------------------------------------|---|--------------------------------------|--------------------------------------|-----------------------------------|---------------------------------|---|--------------------------------|--------------------------------|--|--|---|
| | be i | ndersigne recruited | from | the | area | t: (num in w _ new l | hich | the | contr | act | proje | ct is | s I | | ; | and/o | r (nı | umber) |) |
| | office | or base of | operatio | on is lo | ocated. | | | | | | | | | | | | | | |
| C. | | led in "Tota signed bid | | | | | | | | | | | | | | | | by the | ! |
| | be dir | ndersigned ectly employed by sul | oyed by | the p | ates tha | at (num Intractor | ber) _ r and f | that (r | umber |) | | | | | | pe | persons | ons will will be | ; |
| PART | III. AFF | IRMATIVE | E ACTIO | N PL | AN | | | | | | | | | | | | | | |
| A. | utiliza in any comm (geare utiliza | indersigner tion project project tencement and to the tion are compartment | tion inclugory, and of work completion of the co | uded of the contract of the co | under P ne even velop an tages o h Affirm | ART II that the subroif the c | is detended in the contract in | ermine dersig writte t) wh | ed to be ned bion n Affirm ereby | e an u Ider i native defici | underu s awa e Actic encies | tilizat rded on Pla in n | ion o this an ir ninoi | of mino contra- ncludin rity and | rity ct, h g a d/or | perso e/she spec fema | ns or v will, p ific tim lle em | women orior to netable ployee |) |
| B. | submi | indersigne itted hereir part of the | n, and th | e goa | als and | timetab | | | | | | | | | | | | | |
| Comp | any | | | | | | | | ٦ | ГеІер | hone N | Numb | er _ | | | | | | |
| Addre | ess | | | | | | | | | | | | | | | | | | |
| Ī | | | | | | NOTIC | EREG | ARDI | NG SIG | NATU | JRE | | | | | | | | |
| | | der's signat be comple | | | | | | vill con | stitute t | he sig | ning of | this fo | orm. | The fo | llowi | ng sig | nature | block | |
| | Signatu | re: | | | | | | . 1 | itle: | | | | | Dat | e: _ | | | | |
| Instruct | tions: | All tables m | nust include | e subco | ontractor p | personnel | l in addi | tion to p | orime cor | ntracto | r person | nel. | | | | | | | |
| Table A | ۸ - | Include bot (Table B) the should include | nat will be | allocate | ed to con | tract work | k, and ir | nclude a | all apprei | ntices | and on- | the-job | train | ees. Th | e "To | tal Em | ployees' | ' column | |
| Table E |) | | | | | | | | | | | | | | | | | trainage | ; |
| |) - | Include all e currently en | | curren | tly emplo | yed that v | will be a | llocated | to the c | ontrac | t work ir | ncludin | g any | apprent | ices | and on | -the-job | lialliees | |

Contract No. 44959
Various Counties
Section D1 H-T PVT MKG REP 2007-08
Various Routes
District 1 Construction Funds

PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 3 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

| | Firm Name | |
|--|---------------------|--|
| (IF AN INDIVIDUAL) | | |
| | | |
| | | |
| | | |
| | Firm Name | |
| | | |
| (IF A CO-PARTNERSHIP) | | |
| , | | |
| | | Name and Address of All Members of the Firm: |
| _ | | |
| - | | |
| | | |
| | | |
| | Ву | Signature of Authorized Representative |
| | | Typed or printed name and title of Authorized Representative |
| (IF A CORPORATION) | | |
| (IF A JOINT VENTURE, USE THIS SECTION | Attest | Signature |
| FOR THE MANAGING PARTY AND THE SECOND PARTY SHOULD SIGN BELOW) | Business Address | |
| , | | |
| | | |
| | Corporate Name | |
| | Ву | - |
| | | Signature of Authorized Representative |
| | | Typed or printed name and title of Authorized Representative |
| (IF A JOINT VENTURE) | A 11 1 | |
| | Attest | Signature |
| | Business Address | |
| | | |
| If more than two parties are in the joint venture | nlease attach an ac | Iditional signature sheet |



Division of Highways Proposal Bid Bond

(Effective November 1, 1992)

| | Item No. |
|--|---|
| | Letting Date |
| WHOM ALL MEN BY THESE PROPERTY TO WE | |
| KNOW ALL MEN BY THESE PRESENTS, That We | |
| | |
| DDINCIDAL and | - |
| as PRINCIPAL, and | |
| | as SURETY, are |
| Article 102.09 of the "Standard Specifications for Road and Bridg | NOIS in the penal sum of 5 percent of the total bid price, or for the amount specified in the Construction" in effect on the date of invitation for bids, whichever is the lesser sum, well nent of which we bind ourselves, our heirs, executors, administrators, successors and assigns. |
| | IS SUCH, That Whereas, the PRINCIPAL has submitted a bid proposal to the STATE OF he improvement designated by the Transportation Bulletin Item Number and Letting Date |
| the bidding and contract documents, submit a DBE Utilization Pla PRINCIPAL shall enter into a contract in accordance with the terr coverages and providing such bond as specified with good and surlabor and material furnished in the prosecution thereof; or if, in the into such contract and to give the specified bond, the PRINCIPAL | proposal of the PRINCIPAL; and if the PRINCIPAL shall, within the time and as specified in in that is accepted and approved by the Department; and if, after award by the Department, the ins of the bidding and contract documents including evidence of the required insurance efficient surety for the faithful performance of such contract and for the prompt payment of the event of the failure of the PRINCIPAL to make the required DBE submission or to enter apays to the Department the difference not to exceed the penalty hereof between the amount to Department may contract with another party to perform the work covered by said bid shall remain in full force and effect. |
| paragraph, then Surety shall pay the penal sum to the Depa | RINCIPAL has failed to comply with any requirement as set forth in the preceding rtment within fifteen (15) days of written demand therefor. If Surety does not make bring an action to collect the amount owed. Surety is liable to the Department for igation in which it prevails either in whole or in part. |
| In TESTIMONY WHEREOF, the said PRINCIPAL officers this day of | and the said SURETY have caused this instrument to be signed by their respective |
| PRINCIPAL | SURETY |
| (Company Name) | (Company Name) |
| By: | By: |
| By: (Signature & Title) | By: (Signature of Attorney-in-Fact) |
| | |
| STATE OF ILLINOIS, COUNTY OF | ry Certification for Principal and Surety |
| I. | , a Notary Public in and for said County, do hereby certify that |
| and | |
| | als signing on behalf of PRINCIPAL & SURETY) |
| who are each personally known to me to be the same personal | ons whose names are subscribed to the foregoing instrument on behalf of person and acknowledged respectively, that they signed and delivered said |
| Given under my hand and notarial seal this da | y of, A.D |
| My commission expires | |
| My commission expires | Notary Public |
| In lieu of completing the above section of the Proposal Bid F is ensuring the identified electronic bid bond has been executed conditions of the bid bond as shown above. | Form, the Principal may file an Electronic Bid Bond. By signing below the Principal uted and the Principal and Surety are firmly bound unto the State of Illinois under the |
| Electronic Bid Bond ID# Company/Bidder Name | Signature and Title |

PROPOSAL ENVELOPE



PROPOSALS

for construction work advertised for bids by the Illinois Department of Transportation

| Item No. | Item No. |
|----------|----------|
| | |
| | |
| | |
| | |
| | |
| | |
| | |

Submitted By:

| Name: |
|-----------|
| Address: |
| |
| |
| Phone No. |

Bidders should use an IDOT proposal envelope or affix this form to the front of a 10" x 13" envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 326 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

NOTICE

Individual bids, including Bid Bond and/or supplemental information if required, should be securely stapled.

CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

NOTICE

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.

Contract No. 44959
Various Counties
Section D1 H-T PVT MKG REP 2007-08
Various Routes
District 1 Construction Funds



Illinois Department of Transportation

NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation at the Harry R. Hanley Building, 2300 South Dirksen Parkway, in Springfield, Illinois until 10:00 o'clock a.m., June 15, 2007. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- **2. DESCRIPTION OF WORK**. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 44959
Various Counties
Section D1 H-T PVT MKG REP 2007-08
Various Routes
District 1 Construction Funds

Removal and replacement of various types, sizes and widths of pavement markings to be done by individual work orders.

- 3. INSTRUCTIONS TO BIDDERS. (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
 - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Milton R. Sees, Acting Secretary

BD 351 (Rev. 01/2003)

INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2007

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS, frequently used RECURRING SPECIAL PROVISIONS, and LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS.

No ERRATA this year.

SUPPLEMENTAL SPECIFICATIONS

Std. Spec. Sec. Page No.

No Supplemental Specifications this year.

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

| CHE | <u>CK</u> | SHEET# | PAGE NO. |
|-----|-----------|--|----------|
| 1 | | Additional State Requirements For Federal-aid Construction Contracts (Eff. 2-1-69) (Rev. 1-1-07) | 1 |
| 2 | | Subletting of Contracts (Federal-aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93) | 3 |
| 3 | Χ | EEO (Eff. 7-21-78) (Rev. 11-18-80) | 4 |
| 4 | Χ | Specific Equal Employment Opportunity Responsibilities NonFederal-aid Contracts | |
| | | (Eff. 3-20-69) (Rev. 1-1-94) | 14 |
| 5 | Χ | Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1-1-07) | 19 |
| 6 | | Reserved | 24 |
| 7 | | National Pollutant Discharge Elimination System Permit (Eff. 7-1-94) (Rev. 1-1-03) | 25 |
| 8 | | Haul Road Stream Crossings, Other Temporary Stream Crossings and In-Stream Work Pads | |
| | | (Eff. 1-2-92) (Rev. 1-1-98) | |
| 9 | | Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-07) | |
| 10 | | Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-07) | |
| 11 | | Use of Geotextile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-07) | |
| 12 | | Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 1-1-07) | 35 |
| 13 | | Hot-Mix Asphalt Surface Removal (Cold Milling) (Eff. 11-1-87) (Rev. 1-1-07) | |
| 14 | | Pavement and Shoulder Resurfacing (Eff. 2-1-00) (Rev. 1-1-07) | 41 |
| 15 | | PCC Partial Depth Hot-Mix Asphalt Patching (Eff. 1-1-98) (Rev. 1-1-07) | |
| 16 | | Patching with Hot-Mix Asphalt Overlay Removal (Eff. 10-1-95) (Rev. 1-1-07) | |
| 17 | | Polymer Concrete (Eff. 8-1-95) (Rev. 3-1-05) | |
| 18 | | PVC Pipeliner (Eff. 4-1-04) (Rev. 1-1-07) | 47 |
| 19 | | Pipe Underdrains (Eff. 9-9-87) (Rev. 1-1-07) | |
| 20 | | Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97) | |
| 21 | | Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-07) | 53 |
| 22 | | Temporary Modular Glare Screen System (Eff. 1-1-00) (Rev. 1-1-07) | |
| 23 | | Temporary Portable Bridge Traffic Signals (Eff. 8-1-03) (Rev. 1-1-07) | |
| 24 | | Work Zone Public Information Signs (Eff. 9-1-02) (Rev. 1-1-07) | |
| 25 | | Night Time Inspection of Roadway Lighting (Eff. 5-1-96) | |
| 26 | | English Substitution of Metric Bolts (Eff. 7-1-96) | |
| 27 | | English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03) | 62 |
| 28 | | Calcium Chloride Accelerator for Portland Cement Concrete (Éff. 1-1-01) | |
| 29 | | Quality Control of Concrete Mixtures at the Plant-Single A (Eff. 8-1-00) (Rev. 1-1-04) | |
| 30 | | Quality Control of Concrete Mixtures at the Plant-Double A (Eff. 8-1-00) (Rev. 1-1-04) | |
| 31 | | Quality Control/Quality Assurance of Concrete Mixtures (Eff. 4-1-92) (Rev. 1-1-07) | 78 |

TABLE OF CONTENTS

| LOCATION OF IMPROVEMENT | 1 |
|---|----|
| DURATION OF CONTRACT | 1 |
| DESCRIPTION OF IMPROVEMENTS | 1 |
| TRAFFIC CONTROL PLAN | 1 |
| KEEPING THE EXPRESSWAY OPEN TO TRAFFIC | 2 |
| TRAFFIC CONTROL AND PROTECTION | 2 |
| WORK ORDERS | 7 |
| FAILURE TO COMPLETE A WORK ORDER ON TIME | 7 |
| QUANTITIES | |
| FINAL CLEAN UP | |
| FINAL INSPECTION AND PAYMENT | 8 |
| 45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING | |
| INTERSECTION POLYUREA PAVEMENT MARKING | 17 |
| URETHANE PAVEMENT MARKING | 23 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) | 28 |
| ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE) | 35 |
| PAYMENTS TO SUBCONTRACTORS (BDE) | 37 |
| REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) | 38 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) | 39 |
| THERMOPLASTIC PAVEMENT MARKINGS (BDE) | |

SPECIAL PROVISIONS

STATE OF ILLINOIS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction, Adopted January 1, 2007", the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Supplemental Specifications and Recurring Special Provisions" indicated on the Check Sheet included herein, which apply to and govern the construction of Various Routes, Section D1 H-T PVT MKG REP 2007-08, in Various Counties, Contract 44959 and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF IMPROVEMENT

The work to be done under this contract will be performed on various highways throughout District 1 and as directed by the Engineer.

DURATION OF CONTRACT

The contract shall become effective **July 1**, **2007** or following the execution and acceptance of the contract, whichever is later, and will continue in effect until **June 30**, **2008**.

DESCRIPTION OF IMPROVEMENTS

The work to be accomplished under this contract shall consist of repairing various widths of thermoplastic, polyurea, urethane and hot spray thermoplastic pavement marking lines, letters and symbols and the removal of existing pavement markings within the limits specified on each individual work order.

TRAFFIC CONTROL PLAN

Effective: September 30, 1985 Revised: July 1, 1994

Traffic control shall be in accordance with the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, the Traffic Specifications and the Special Provisions contained herein.

Special attention is called to Article 107.09 and Section 701 of the Standard Specifications and the following Highway Standards, Details Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contract the District One Bureau of Traffic at least **96 hours** in advance of beginning work.

Standards - 702001, 701311, 701400, 701406, 701411, 701501, 701606, 701601, 701701, 701426

Directional Indicator barricades shall be used as described in the Supplemental Specifications.

Special Provisions - Traffic Control and Protection

- Traffic Control Deficiency Deduction
- Keeping the Expressway Open to Traffic
- Reflective Sheeting on Channelizing Devices

KEEPING THE EXPRESSWAY OPEN TO TRAFFIC

Whenever work is in progress on or adjacent to an expressway, the Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required. The traffic control shall be in accordance with these Special Provisions, the Standard Specifications, the State Standards, and the District Freeway Lane Closure Standards and details. All Contractor's personnel shall be limited to these barricaded work zones and shall not cross the expressway.

The Contractor shall request and gain approval from the Illinois Department of Transportation's Expressway Traffic Operations Engineer (847)-705-4155 or 4151) twenty-four (24) hours in advance of all daily partial ramp and shoulder closures. And seventy-two (72) hours in advance of all permanent and weekend closures on all Freeways and/or Expressways in District One.

Shoulder closures or partial ramp closures will <u>not</u> be permitted on weekdays (Monday through Friday) from 5:00 a.m. to 9:00 a.m. or from 3:00 p.m. to 7:00 p. m. Since this is a "various locations" project, lane closures have not been approved for this project, and are normally <u>not</u> permitted during the day. The Contractor must notify the Expressway Traffic Operations Engineer a minimum of 10 working days prior to the beginning of the work on the Expressway, so exact lane closures and the traffic control needed, can be determined.

All daily closures shall be removed during adverse weather conditions such as rain, snow, and/or fog as determined by the Engineer.

Additional hour restrictions for closures may have to be imposed to facilitate the flow of traffic to and from major sporting events and/or other events.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at the locations approved by the Engineer.

TRAFFIC CONTROL AND PROTECTION

Effective: September 30, 1985 Revised: January 13, 1995

This item of work shall include furnishing, installing, maintaining, replacing, relocating and removing all traffic control devices used for the purpose of regulating, warning or directing traffic during the construction or maintenance of this improvement.

Traffic control and protection shall be provided as called for in the plans, these Special Provisions, applicable Highway Standards, applicable sections of the Standard Specifications, or as directed by the Engineer.

The governing factor in the execution and staging of work for this project is to provide the motoring public with the safest possible travel conditions along the roadway through the construction zone. The Contractor shall arrange his operations to keep the closing of any lane of the roadway to a minimum.

Traffic control devices include signs and their supports, signals, pavement markings, barricades with sand bags, channelizing devices, warning lights, arrowboards, flaggers, or any other device used for the purpose of regulating, detouring, warning or guiding traffic through or around the construction zone.

The Contractor is required to conduct routine inspections of the work-site at a frequency that will allow for the prompt replacement of any traffic control device that has become displaced, worn, or damaged to the extent that it no longer conforms to the shape, dimensions, color, and operational requirements of the MUTCD, the Traffic Control Standards, or will no longer present a neat appearance to motorists. A sufficient quantity of replacement devices, based on vulnerability to damage, shall be readily available to meet this requirement.

The Contractor shall be responsible for the proper location, installation and arrangement of all traffic control devices. Special attention shall be given to advance warning signs during construction operations in order to keep lane assignment consistent with barricade placement at all times. The Contractor shall immediately remove, cover or turn from the view of the motorists all traffic control devices which are inconsistent with detour or lane assignment patterns and conflicting conditions during the transition from one construction stage to another. When the Contractor elects to cover conflicting or inappropriate signing, materials used shall totally block out reflectivity of the sign and shall cover the entire sign. The method used for covering the signing shall meet with the approval of the Engineer.

The Contractor shall coordinate all traffic control work on this project with adjoining or overlapping projects, including barricade placement necessary to provide a uniform traffic detour pattern. When directed by the Engineer, the Contractor shall remove all traffic control devices, which were furnished, installed and maintained by him under this contract, and such devices shall remain the property of the Contractor. All traffic control devices shall remain in place until specific authorization for relocation or removal is received from the Engineer.

The Contractor shall ensure that all traffic control devices installed by him are operational, functional and effective 24 hours a day, including Sundays and holidays.

<u>Signs:</u> All signs except those referring to daily lane closures shall be post mounted in accordance with Standard 702001 for all projects that exceed four days.

Construction signs referring to daytime lane closures during working hours shall be removed, covered or turned away from the view of the motorists during non-working hours.

Prior to the beginning of construction operations, the Contractor will be provided a sign log of all existing signs within the limits of the construction zone. The Contractor is responsible for

verifying the accuracy of the sign log. Throughout the duration of this project, all, existing traffic signs shall be maintained by the Contractor. All provisions of Article 107.25 of the Standard Specifications shall apply except the third paragraph shall be revised to read: The Contractor shall maintain, furnish, and replace at his own expense, any traffic sign or post which has been damaged or lost by the Contractor or a third party. The Contractor will not be held liable for third party damage to large freeway guide signs."

"Fresh Oil" signs (W21-2) shall be used when prime is applied to pavement that is open to traffic. The signs are to remain until tracking of the prime ceases. The sign shall be erected a minimum of 150 m (500 feet) preceding the start of the prime and on all side roads within the posted area. The "Fresh Oil" sign on the side road shall be posted a minimum of 60 m (200 feet) from the mainline pavement.

"Rough Grooved Surface" signs (W8-I107) shall be used when the road has been cold milled and open to traffic. The signs shall remain in place until the milled surface condition no longer exists. These signs shall be erected a minimum of 150 m (500 feet) preceding the start of the milled pavement and on all side roads within the posted area. The "Rough Grooved Surface" signs on the side roads shall be posted 60 m (200 feet) from the mainline pavement. All signs shall have a 450 mm x 450 mm (18" x 18") orange flag and an amber flashing light attached.

Whenever a lane is closed to traffic using Standard 701601, 701606, or 701701, the pavement width transition sign (W4-2R or W4-2L) shall be used in lieu of "Workers" sign (W21-1 or W21-1a).

Whenever any vehicle, equipment, workers or their activities infringe on the shoulder or within 4.5 m (15 feet) of the traveled way and the traveled way remains unobstructed, then the applicable Traffic Control Standard shall be 701006, 701011, 701101, or 701701. "Shoulder Work Ahead" sign (W21-5(0)-48) shall be used in lieu of the "Workers" sign (W21-1 or W21-1a).

<u>Barricades:</u> Any drop off greater than 75 mm (three inches), but less than 150 mm (six inches) within 2.5 m (eight feet) of the pavement edge shall be protected by Type I or II barricades equipped with mono-directional steady burn lights at 30 m (100-foot) center-to-center spacing. If the drop off within 2.5 m (eight feet) of the pavement edge exceeds 150 mm (six inches), the barricades mentioned above shall be placed at 15 m (50-foot) center-to-center spacing. Barricades that must be placed in excavated areas shall have leg extensions installed such that the top of the barricade is in compliance with the height requirements of Standard 702001.

All Type I and II barricades and vertical panels shall be equipped with a steady burn light when used during hours of darkness unless otherwise stated herein.

Check barricades shall be placed in work areas, perpendicular to traffic, every 300 m (1,000 feet), one per lane and per shoulder, to prevent motorists from using work areas as a traveled way. Two additional check barricades shall be placed in advance of each patch excavation or any other hazard in the work area, the first at the edge of the open traffic lane and the second centered in the closed lane. Check barricades shall be Type I or II and equipped with a flashing light.

<u>Arrow Boards:</u> A flashing arrow board shall be operating at all times when a lane is closed to traffic on a multilane highway. Arrow boards shall be provided and located in a head-on position within each lane closure taper.

On expressway construction projects where the lane closures are in effect longer than 8 hours, the advance arrow board is required. This arrow board shall be placed at the location shown on the District Lane Closure Standard or as directed by the Engineer.

<u>Temporary Concrete Barrier Vertical Panels and Lights:</u> Whenever temporary concrete barrier wall is specified in the plans, vertical panels and steady burning lights, meeting the requirements of Articles 702.03 and 702.04 of the Standard Specifications, and Standard 702001, shall be installed on the barrier wall at 15 m (50-foot) centers minimum or at the spacing shown on the plans. The method of mounting shall be approved by the Engineer.

Upon conclusion of the work, the panels and lights shall be removed and shall remain the property of the Contractor.

<u>Pedestrian Sidewalk Control:</u> The Contractor shall install, maintain and remove necessary signs and barricades needed to direct pedestrians to usable sidewalks and walkways during the construction in accordance with Traffic Control Standard 701801.

All barricades shall be Type I or II equipped with flashing lights. At each point of closure, sufficient numbers of barricades shall be used to completely close the sidewalk to pedestrian movement. Where construction activities involve sidewalks on both sides of the street, the work shall be staged so that both sidewalks are not out of service at the same time.

<u>Public Convenience and Safety:</u> The Contractor shall provide a telephone number where a responsible individual can be contacted on a 24-hour-a-day basis to receive notification of any deficiencies regarding traffic control and protection. The Contractor shall dispatch men, materials and equipment to correct any such deficiencies. The Contractor shall respond to any call from the Department concerning any request for improving or correcting traffic control devices and begin making the requested repairs within two hours from the time of notification.

Personal vehicles shall not park within the right-of-way except in specific areas designated by the Engineer.

The Contractor shall maintain one lane of traffic at all times on two lane roads and one lane in each direction on four or more lane roads, during the construction of this project. The Contractor shall also maintain entrances and side roads along the proposed improvement. Interference with traffic movements and inconveniences to owners of abutting property and the public shall be kept to a minimum. Any delays or inconveniences caused to the Contractor by complying with these requirements shall be considered incidental to the contract, and no additional compensation will be allowed.

On two lane roads, the Contractor is to plan his work so that there will be no open holes in the pavement and that all barricades will be removed from the pavement during non-working hours.

On four or more lane highways, there shall be no open holes in the pavement being used by the traveling public. Lane closures, if allowed, will be in accordance with the applicable standards, any staging details shown in the plans and other applicable contract documents.

The Contractor shall remove all equipment from the shoulders and medians after work hours.

No road closure or restrictions shall be permitted except, those covered by the Standard Designs, without written approval by the Engineer.

<u>Method of Measurement:</u> This item of work will be measured on a lump sum basis for furnishing, installing, maintaining, replacing, relocating and removing the traffic control devices required in the plans and these Special Provisions.

<u>Basis of Payment:</u> This work will be paid for at the contract lump sum price, for TRAFFIC CONTROL AND PROTECTION, which price shall be payment in full, for all labor, materials, transportation, handling and incidentals necessary to furnish, install, maintain, replace, relocate and remove all traffic control devices indicated in the plans and specifications. The salvage value of the materials removed shall be reflected in the bid price for this item.

Delays to the Contractor caused by complying with these requirements will be considered incidental to the item for Traffic Control and Protection, and no additional compensation will be allowed.

<u>Payment Adjustments:</u> The Engineer may require additional traffic control to be installed in accordance with standards and/or designs other than those included in the plans. In such cases, the standards and/or designs will be made available to the Contractor at least one week in advance of the change in traffic control. Payment for any additional traffic control required will be in accordance with Article 109.04 of the Standard Specifications.

Revisions in the phasing of construction or maintenance operations, requested by the Contractor, may require traffic control to be installed in accordance with standards and/or designs other than those included in the plans. The Contractor shall submit any revisions or modifications to the traffic control shown in the contract to the Engineer for approval. No additional payment will be made for a Contractor requested modification.

In the event the sum total value of all the work items for which traffic control and protection is required is increased or decreased by more than ten percent (I0%), the contract bid price for Traffic Control and Protection will be adjusted as follows:

Adjusted contract price = .25P + .75P [1 + (X-0.1)]

Where "P" is the contract price for Traffic Control and Protection.

Difference between original and final sum total value of all the work items for which traffic control and protection is required.

Original sum total value of all work items for which traffic control and protection is required.

Where "X" =

The value of the work items used in calculating the increase or decrease will include only the items which have been added to or deducted from the contract under Article 104.02 of the Standard Specifications and only items which require use of Traffic Control and Protection.

In the event the Department cancels or alters any portion of the contract, which results in elimination or non-completion of any portion of the work, payment for partially completed work will be made in accordance with Article 109.06 of the Standard Specification

WORK ORDERS

No work of any kind is to be performed by the Contractor, unless a work order authorizing the work, has been issued by the Engineer. A work order will show the date of issue, job number, location, code number(s), pay item(s), and quantity of such pay item. Only the amount of replacement or repairs shown on the work order is to be done by the Contractor. If at the time, work is being done, it appears that additional work is needed, a revised work order must be obtained. The Contractor shall notify the Engineer at least **72 hours** before beginning any work in the field and shall obtain permission to begin such work.

Each work order may involve several locations within the district. Some work orders may require the Contractor to perform the work during hours of darkness.

The Contractor shall complete all work on a work order within **45 days** after the date of issue of the work order, excluding Saturdays, Sundays and holidays, unless otherwise extended in the work order or agreed to in writing between the Contractor and the Engineer.

FAILURE TO COMPLETE A WORK ORDER ON TIME

Should the Contractor fail to complete a work order on time, or such extended time as may have been allowed by the Department, the Contractor shall be liable to the Department, not as a penalty, but as liquidated damages in the amount of **\$75.00** per calendar day of overrun per work order, rather than the amount indicated in Article 108.09, of the "Standard Specifications for Road and Bridge Construction".

A calendar day shall be defined as any day on the calendar. No calendar day will be counted under the following conditions:

- (a) When adverse weather at the field work site prevents work on the controlling item of a work order.
- (b) When job conditions at the field work site due to recent weather conditions prevent work on the controlling item of a work order.
- (c) When work on the controlling item has been suspended by an act or omission by the Department or Engineer.

Should the Contractor fail to complete all work orders issued on or before November 1, 2004, he shall be suspended from the list of approved epoxy and thermoplastic contractors (maintained by the Engineer of Operations) for a period of four months.

QUANTITIES

The quantities specified in this contract indicate the estimated amount of work required for the duration of this contract. This is merely an estimate to allow Contractors to establish unit prices and permit the Department to determine the low bidder. It shall be understood that the unit prices of this contract shall prevail throughout the period of this contract regardless of the quantity.

FINAL CLEAN UP

The Contractor shall be responsible for cleaning up the debris generated from the removal of existing pavement markings, to the satisfaction of the Engineer, before placing the new markings. This work may be completed by a vacuum system. The Contractor shall dispose of the collected debris outside of the State right-of-way. Each time the Contractor accomplishes work at any location, he will be required to clean up the work area before payment for that work will be made. All costs due to compliance with this Special Provision will be incidental to the contract and no additional compensation will be allowed.

FINAL INSPECTION AND PAYMENT

No payment will be made for a work order, until it is inspected and approved in writing by the Engineer.

45 Mil Hot Spray Thermoplastic Pavement Marking

Effective February 28, 1994 - Revised December 4, 2006

This work shall consist of furnishing and applying spray thermoplastic pavement marking lines, sizes and colors as shown on the plans. The material shall be a mixture of resins and other materials providing an essentially nonvolatile thermoplastic compound especially developed for traffic markings. Spray thermoplastic pavement markings shall be applied only by contractors on the list of Approved Spray Thermoplastic Contractors maintained by the Engineer of Operations and in effect on the date of advertisement for bids.

Ingredient Materials:

- (a) Binder. The binder shall consist of a mixture of synthetic resins, at least one of which is solid at room temperature. The total binder content of the thermoplastic compound shall be well distributed throughout the compound. The binder shall be free from all foreign objects or ingredients that would cause bleeding, staining or discoloration. The binder shall be 25 percent minimum by weight of the thermoplastic compound. The binder shall be characterized by an IR Spectra. Future shipments of binder will be checked by an IR Spectra to verify that the binder has not been changed.
- (b) Pigment. The pigment used for the white thermoplastic compound shall be a high-grade pure (minimum 93 percent) titanium dioxide (TiO₂). The white pigment content shall not be less than 10 percent by weight and shall be uniformly distributed throughout the thermoplastic compound.

The pigments used for the yellow thermoplastic compound shall not contain any hazardous materials listed in the Environmental Protection Agency Code of Federal Regulations (CFR) 40, Section 261.24, Table 1. The Combined total RCRA listed heavy metals shall not exceed 100 ppm when tested by X-ray fluorescence spectroscopy. The pigments shall also be heat resistant, UV stable and color fast yellows, golds, and oranges, which shall produce a compound which shall match Federal Standard 595 Color No. 33538. The pigment shall be uniformly distributed throughout the thermoplastic.

- (c) Filler: The filler to be incorporated with the resins as a binder shall be a white calcium carbonate, silica, or an approved substitute. Any filler, which is insoluble in 6N hydrochloric acid, shall be of such particle size as to pass a 150 um (No. 100) sieve.
- (d) Glass Beads:
 - (1) Scope:

This specification covers glass beads to be used for reflectorizing pavement marking lines.

Type A – uncoated

Type B - moisture resistant, silicone coated

Type A shall be used as intermix beads with thermoplastic pavement marking materials. They shall be uniformly mixed throughout the material at the rate of not less than 25 percent by weight (retained on the 150 um (No. 100) sieve) of thermoplastic compound.

Type B shall be used as drop-on beads with thermoplastic pavement marking materials and shall be applied uniformly at a minimum rate of 2.9 kilograms per 10 square meters (6 pounds per 100 square feet).

(2) Properties:

The glass beads furnished under this specification shall consist essentially of transparent, water-white glass particles of a spherical shape. They shall be manufactured from a glass of a composition designed to be highly resistant to traffic wear and to the effects of weathering. The glass beads shall conform to the following requirements:

(a) <u>Sieve Analysis</u>. The glass beads shall meet the following sieve requirements:

Total Percent (By Weight)

| Sieve Size. | Passing |
|-----------------|---------|
| 850 um (No. 20) | 100 |
| 600 um (No. 30) | 75-100 |
| 300 um (No. 50) | 15-40 |
| 150 um (No.100) | 0-5 |
| 75 um (No.200) | 0-1 |

- (b) <u>Imperfections</u>. The surface of the glass beads shall be free of pits and scratches. The glass beads shall be spherical in shape and shall contain not more than 20 percent by weight of irregular shapes when tested by the standard method using a vibratile inclined glass plate as adopted by the Department.
- (c) <u>Index of Refraction.</u> The index of refraction of the glass beads shall be not less than 1.50 when tested by the immersion method at 25° C (77° F).
- (d) <u>Silica Content.</u> The glass beads shall contain not less than 65 percent silica (SiO₂).
- (e) <u>Chemical Stability.</u> Glass beads which a show tendency toward decomposition, including surface etching, when exposed to paint or thermoplastic constituents will be rejected. The glass beads shall be tested by Federal Specification TT-B-1325B, Section 4.3.9 (water resistance) and evaluated for compliance with Section 3.2.9, with the following exceptions:

The size of the sample to be tested shall be 25 grams and the reflux time shall be 5 hours.

(f) <u>Flowing Properties.</u> The glass beads shall flow uniformly through dispensing equipment in atmospheric humidity up to 94%.

Intermix beads shall pass the following test: One hundred grams of glass beads, spread evenly and thinly in a suitable container, shall be conditioned at 25° C (77° F) for 4 hours over a solution of sulfuric acid (Sp. Gr. 1.10) in a closed desicator. After 4 hours, the glass beads shall flow readily through a clean glass analytical funnel, 60°, 75mm. diameter and 105mm. stem. Inside diameter of the stem shall be a nominal 6.35mm. (1/4 inch).

The drop-on beads shall have a silicone, moisture resistant coating and pass the following test: One hundred grams of beads are placed in a 600 ml beaker and an equivalent volume of distilled water shall be added to the beaker. The beaker will then stand for 5 minutes, at the end of which time the water shall be carefully poured off and the beads transferred to a clean dry beaker and allowed to stand for 5 minutes. The beads will then be poured slowly into a standard glass funnel (Corning 6120), 127mm. diameter, 102mm. stem length and 11 mm. stem inside diameter. The beads shall flow through the funnel stem without stoppage. Slight initial agitation to start the flow through the funnel at the beginning of the test is permissible.

(g) <u>Packaging.</u> The Type B glass beads may be delivered in approved moisture proof bags or in weather resistant bulk boxes.

Moisture proof bags shall consist of a least five-ply paper construction unless otherwise specified. Each bag shall contain 22.7 kg (50 pounds) net, and shall be legibly marked with the manufacturer, specifications and type, lot number, and the month and year the glass beads were packaged.

Bulk weather resistance boxes must conform to Federal Specification PPP-8-640D Class II or latest revision. Boxes are to be weather resistant, triple wall, fluted, corrugated-fiber board. Cartons shall be strapped with two (2) metal straps. Straps shall surround the outside perimeter of the carton. The first strap shall be located approximately two (2) inches from the bottom of the carton and the second strap shall be placed approximately in the middle of the carton. All cartons shall be shrink wrapped for protection from moisture. Cartons must be lined with a minimum 4 mil polyester bag and meet ICC requirements. Carton shall be approximately 38 x 38 inches, contain 2,000 lbs. of beads and be supported on a wooden pallet with fiber straps. Each carton shall be legibly marked with the manufacturer, specifications and type, lot number, and the month and year the glass beads were packaged.

Thermoplastic Compound:

- (a) Characteristic Requirements:
 - (1) In the plastic state, the material shall not give off fumes that are toxic or otherwise injurious to persons or property. The manufacturer shall provide material safety data sheets for the product.
 - (2) The temperature versus viscosity characteristic of the plastic material shall remain constant and the material shall not deteriorate in any manner during re-heating processes.
 - (3) There shall be no obvious change in color of the material as a result of repeated heating or from batch to batch. The maximum elapsed time after application after which normal traffic will leave no impression or imprint on the new stripe shall be 30 seconds when the air and road surface temperature is approximately 21° ± 2° C (70° ± 3° F). After application and proper drying, the material shall show no appreciable deformation or discoloration, shall remain free from tack, and shall not lift from the pavement under normal traffic conditions within a road temperature range of -28.9° to 65.6° C (-20° to 150° F). The stripe shall maintain its original dimensions and placement.

Cold ductility of the material shall be such as to permit normal dimensional distortion as a result of traffic impact within the temperature range specified.

(4) The material shall provide a stripe that has a uniform thickness throughout its cross section and has the density and character to provide a sharp edge of the line.

(5) The thermoplastic compound after heating for 4 hours ± 5 min at 190.6° ± 2° C (375° ± 3° F) and cooled at 25° C (77° F) shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45° circumferential/0° geometry, illuminant C, and 2° observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral band-pass of I0 nm.

White: Daylight Reflectance, 75 percent minimum *Yellow: Daylight Reflectance, 45 percent Minimum

*Shall meet the coordinates of the following color tolerance chart.

| Χ | 0.490 | 0.475 | 0.485 | 0.530 |
|---|-------|-------|-------|-------|
| У | 0.470 | 0.438 | 0.425 | 0.456 |

- (6) Specific Gravity the specific gravity of the thermoplastic material shall not exceed 2.15.
- (7) Softening Point After heating the thermoplastic material for 4 hours ± 5 min. at 190.6° ± 2° C (375° ± 3° F) and testing in accordance with ASTM E28, the material shall have a minimum softening point of 82.2° C (I80° F) as measured by the ring and ball method.
- (8) Tensile Bond Strength After heating the thermoplastic material for 4 hours ± 5 min. at 190.6° C (375° F), the tensile bond strength to unprimed, sandblasted Portland cement concrete block, 1.587mm. (0.0625-inch) thick film drawn down 190.6° C (375° F), tested at 23.9° ± I ° C (75° F ± 2° F) shall exceed 1.24 Mpa (I80 psi) when tested in accordance with ASTM D4796-88.
- (9) Impact Resistance After heating the thermoplastic material for 4 hours ± 5 min at I90.6° ± 2° C (375° ± 3° F) the impact resistance shall be a minimum of 0.576 kilogram meters (50 inch pounds) with no cracks or bond loss when 1.587mm. (0.0625 inch) thick film drawdown is made at 190.6° C (375° F) on an unprimed sandblasted Portland cement concrete block, male indentor 15.875 mm.(5/8 inch), no female Die, tested at 23.9° ± 1° C (75° ± 2° F) when tested in accordance with ASTM D2794 minimum.
- (10) Yellowness Index The white thermoplastic material shall not exceed a yellowness index of 12 when tested in accordance with ASTM D1925.
- (11) Accelerated Weathering After heating the thermoplastic for 4 hours ± 5 min. at 190.6° C (375° F) the thermoplastic shall be applied to a steel wool abraded aluminum alloy panel (Federal Test Std. No. 141, Method 2013) at a film thickness of 30 mils (0.70 mm) and allowed to cool for 24 hours at room temperature. The coated panel shall be subjected to accelerated weathering using the light and water exposure apparatus (fluorescent UV condensation type) for 75 hours according to ASTM G 53 (equipped with UVB-313 lamps).

The cycle shall consist of 4 hours UV exposure at 122° F (50° C) followed by 4 hours of condensation at 104° F (40° C). UVB 313 bulbs shall be used. At the end of the exposure periods, the panel shall not exceed 10 Hunter Lab Delta E units from the original material

(b) Identification

Each package of material shall be stenciled with the manufacturer's name, the type of material and IDOT specification number, the month and year the material was packaged and lot number. Lot numbers must begin with the last two digits of the year manufactured and be sequential with Lot 1. The letters and numbers used in the stencils shall be a minimum of 12.7 mm (1/2 inch) in height.

(c) Packaging

The thermoplastic material shall be packaged in suitable containers, which will not adhere to the product during shipment and storage. The container of thermoplastic material shall weigh approximately22.7 kg (50 lbs). Each container shall designate the color, binder (alkyd or hydrocarbon), spray and user information. The label shall warn the user that the material shall be heated in the range of 177° - 204° C (350° - 400° F).

(d) Storage Life

The material shall meet the requirements of this specification for a period of one year. The thermoplastic must also melt uniformly with no evidence of skins or unmelted particles for this one-year period. The manufacturer shall replace any material that does not meet the above requirements.

Sampling and Testing:

- (a) Unless otherwise provided, all materials shall be sampled and tested in accordance with the latest published standard methods of the American Society for Testing and Materials, and revisions thereof, in effect on the date of invitation for bids, where such standard methods exist. In case there are no ASTM Standards which apply, applicable standard methods of the American Association of State Highway and Transportation Officials, or the Federal Government, or of other recognized standardizing agencies shall be used.
- (b) The right is reserved to inspect the material either at the place of manufacture or at the destination or at both places. If inspected at the place of manufacture, the manufacturer shall furnish such facilities as may be required for collecting and forwarding samples, and shall also furnish facilities for testing the material during the process of manufacture, if required. Tests will be made by and at the expense of the Department. All material samples, for acceptance tests, shall be taken or witnessed by a representative of the Bureau of Materials and Physical Research, and shall be submitted to the Engineer of Materials and Physical Research, 126 East Ash Street, Springfield, Illinois 62704-4766 at least 30 days in advance of the pavement marking operations. Random check samples may be taken at the job site at the discretion of the Engineer.

- (c) The Engineer will test and approve the basic ingredients.
- (d) The sample(s) shall be labeled with the lot number, date, quantity and any other pertinent information. Samples shall be submitted in the following manner:
 - (1) Ingredient Materials:
 - (a) Glass beads: At least three randomly selected bags or containers shall be obtained from each lot or shipment of glass beads. The content of each bag or container shall be passed through a large Riffle Sampler, thus splitting the material down until a representative 1-liter (1-quart) sample is obtained. The sample from each container shall be submitted for testing.

(b) Binder: 0.5 liter (One pint).

(c) <u>Pigments</u>: 0.5 liter (One pint).

(d) Filler: 0.5 liter (One pint).

(2) Thermoplastic:

At least three randomly selected containers shall be obtained from each lot. A 4.5 kg (I0-pound) composite sample of the three containers shall be submitted for testing and acceptance. The lot size shall be approximately 20,000 kg (44,000 pounds) unless the total order is less than this amount.

Manufacturer's Responsibility:

- (a) The manufacturer shall perform tests on a minimum of one sample per 4,500 kg (10,000) pounds of thermoplastic produced. Minimum tests required shall be a softening point determination and color. Manufacturer's test results shall be submitted along with the thermoplastic sample to the Bureau of Materials and Physical Research.
- (b) The manufacturer shall retain the test sample for a minimum period of 18 months.
- (c) The manufacturer shall furnish the Bureau of Materials and Physical Research with copies of bills of lading for all material inspected. Bills of lading shall indicate the consignee and destination, date of shipment, lot numbers, quantity, type of material, name and location of source.

Material Acceptance:

Final acceptance of a particular lot of thermoplastic will be based on the following:

- (a) Compliance of ingredient materials with the specifications.
- (b) Compliance of thermoplastic material with the specifications.
- (c) Manufacturer's test results for each lot of thermoplastic have been received.

(d) Identification requirements are satisfactory.

Notification:

The Contractor shall notify the Engineer 72 hours prior to the placement of the thermoplastic markings in order that an inspector can be present during the operation. At the time of this notification, the Contractor shall indicate the manufacturer and lot numbers of thermoplastic and glass beads that he intends to use. The Engineer will ensure that the approved lot numbers appear on the material package. Failure to comply with this provision may be cause for rejection.

<u>Installation Requirements:</u>

- (a) Before applying thermoplastic, the Contractor shall remove any dirt, glaze, grease, or any other material that would reduce the adhesion of the thermoplastic to the pavement.
- (b) This thermoplastic material shall be readily renewable by placing an overlay of new material directly over old markings of the same material. Such new material shall bond itself to the old markings in such a manner that no splitting or separation takes place. The contractor shall remove all existing material that might cause premature failure of the new material.
- (c) The thermoplastic material shall be installed in a molten state by the spray method at a minimum temperature of 177° C (350° F) and a maximum temperature of 204° C (400° F). Scorching or discoloration of material shall be cause for rejection by the Engineer. The machinery shall be constructed so that all mixing and conveying parts, up to and including the spray gun maintain the material in the molten state.
- (d) Thermoplastic pavement marking materials shall not be applied by the spray method when air and pavement surface temperatures are below 10° C (50° F) or when the surface of the pavement contains any evidence of moisture.
- (e) Unless directed by the Engineer, lines shall not be laid directly over a longitudinal crack or joint. The edge of the center line or lane line shall be offset a minimum distance of 50 mm (2 inches) from a longitudinal crack or joint. Edge lines shall be approximately 50 mm (2 inches) from the edge of pavement. The finished center and lane lines shall be straight, with the lateral deviation of any 3 meter (10-foot) line not to exceed 25 mm (1 inch).
- (f) A primer sealer of the type recommended by the manufacturer of the thermoplastic material shall be applied on all Portland concrete pavement surfaces, and if recommended by the manufacturer, on other types of pavement surface, prior to the installation of the thermoplastic material. The primer shall be free of solvent and water prior to the thermoplastic application.
- (g) The thermoplastic material shall be applied at a thickness of not less than 1.143mm. (0.045-inch), but in no case shall it exceed a thickness of 1.27mm. (0.050-inch). Finished lines shall be within a 6.35mm. (1/4-inch) of the width specified in the plans.

- (h) The Contractor shall place the thermoplastic markings with adequate drop on glass in accordance with the above requirements, uniformly applied to assure nighttime reflectivity. It shall be the Contractor's responsibility to use compatible combination of thermoplastic material and beads to preclude the surface beads from sinking deeply into the thermoplastic.
- (i) The thickness of the markings will be measured above the pavement surface at such random points as the Engineer selects to determine conformance to these specifications. If the measurements show less than 1.143mm. (0.045 inch), the Engineer will "chip" the edges of the markings at random points and measure the thickness of the chips to determine if the overall thickness of the markings is at least 1.143mm. (0.045 inch). If the overall thickness or the thickness above the pavement surface is substantially in conformance with the thickness requirements, payment will be made at 100 percent of the contract unit prices involved. When the thickness at a given location is less than 1.143mm. (0.045 inch), additional measurements will be taken on each side of such location at such intervals

as the Engineer may select to determine the extent of the deficient portion of the marking. The Contractor shall then apply additional thermoplastic material and beads to bring the thickness of the markings to at least 1.143mm. (0.045 inch).

Equipment Requirements:

- (a) The application equipment used for placing lane and edge line on freeways shall be permanently mounted on a truck of sufficient size and stability to insure smooth, straight application. The truck shall be equipped to carry a minimum of 1800 kilograms (4,000 pounds) of molten thermoplastic. The equipment shall have the capability of automatically placing intermittent and continuous lines. The equipment shall be so constructed as to provide the various widths of pavement marking lines specified. The mounting shall be such as to allow the spray equipment to accurately follow road irregularities and produce lines of uniform dimensions.
- (b) The equipment used to install hot applied thermoplastic material shall provide continuous uniform heating to temperatures exceeding 204° C (400° F) and shall provide mixing and agitation of the material. Conveying parts of the equipment between the main material reservoir and the dispensing device shall prevent accumulation and clogging. All parts of the equipment, which comes in contact with the material, shall be constructed for easy accessibility and exposure for cleaning and maintenance. The equipment shall operate so that all mixing and conveying parts including the line dispensing device, maintains the material at the plastic temperature. The use of pans, aprons, or similar devices to prevent die overruns will not be permitted.
- (c) Glass beads applied to the surface of the completed marking shall be applied by an automatic bead dispenser attached to the marking machine so that the beads are dispensed closely behind the installed marking. The glass bead dispenser shall be equipped with an automatic cut-off control synchronized with the cut-off of the thermoplastic material.

- (d) A special kettle shall be provided for uniformly melting and heating the thermoplastic material. The kettle must be equipped with an automatic thermostat control device and material thermometer for positive temperature control and to prevent overheating or under-heating of the material. The heating kettle and application equipment shall meet the requirements of the National Fire Underwriters and the National Fire Protection Association.
- (e) The Contractor shall provide an accurate temperature measuring device which shall be capable of measuring the pavement temperature prior to installation of the thermoplastic and the temperature of the molten thermoplastic material immediately after it is applied.

Inspection:

The 45 mil hot spray thermoplastic pavement markings will be inspected following installation, but no later than November 1, and inspected following a winter performance period that extends 180 days from November 1 in accordance with the provisions of Article 780.10 of the Standard Specification.

Method of Measurement:

The lines will be measured for payment in feet of thermoplastic pavement marking lines applied and accepted, measured in place. Double yellow lines will be measured as two separate lines.

Basis of Payment:

This work will be paid for at the contract unit prices per foot of applied line for HOT SPRAY THERMOPLASTIC PAVEMENT MARKING - LINE 4, 5, 6, or 8 inches measured as specified herein.

INTERSECTION POLYUREA PAVEMENT MARKING

Effective: September 2, 2003

This work shall consist of furnishing and applying intersection polyurea pavement marking lines, letters & symbols of the sizes and colors as shown on the plans. Polyurea-based liquid pavement markings shall be applied only by contractors on the list of Approved Polyurea Contractors maintained by the Engineer of Operations and in effect on the date of advertisement for bids.

All materials shall meet the following specifications:

(A) The intersection polyurea pavement markings shall consist of essentially 100 percent solid two-part system formulated and designed to provide a simple volumetric mixing ratio of two-components. The mixing ratio of the two-components must be either two volumes of Part A to one volume of Part B or three volumes of part A to one volume of part B. No volatile or polluting solvents or fillers will be allowed.

(B) Pigment Content: Determine the pigment content by weight of Component A by low temperature ashing ASTM D 3723. The pigment content shall not vary more than \pm 2 percent from the pigment content of the original qualified paint.

White Pigment must be Titanium Dioxide meeting ASTM D-476 Type II, Rutile. Yellow Pigment must be an Organic Yellow and contain no heavy metals.

- (C) Upon heating to application temperature, the material shall not give off fumes that are toxic or injurious to persons or property. The manufacturer shall provide material safety data sheets for the product
- (D) Daylight Reflectance: The daylight directional reflectance of the cured polyurea material (without reflective media) shall not be less than 80 percent (white) and 50 percent (yellow) relative to magnesium oxide when tested using a color spectrophotometer with a 45 degrees circumferential /zero degrees geometry, illuminant C, and two degrees observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm. In addition, the color of the yellow polyurea shall

visually match Color Number 33538 of Federal Standard 595a and chromaticity limits as follows:

| Χ | 0.490 | 0.475 0.485 | 0.539 |
|---|-------|-------------|-------|
| Υ | 0.470 | 0.438 0.425 | 0.456 |

- (E) Weathering Resistance: The polyurea marking material, when mixed in the proper ratio and applied at 0.35 mm to 0.41 mm (14 to 16 mils) wet film thickness to an aluminum alloy panel and allowed to cure for 72 hours at room temperature, shall be subjected to accelerated weathering for 72 hours. The accelerated weathering shall be completed by using the light and water exposure apparatus (fluorescent UV condensation type) testing in accordance with ASTM G 53 using a cycle which consists of 4 hours UV exposure at 50° C (122° F) and 4 hours of condensation at 40° C (104° F). UVB 313 Bulbs shall be used. At the end of the exposure period, the material shall show no substantial change in color or gloss.
- (F) Dry Time: When installed at a field temperature of 25° C (77° F), at a wet film thickness of 20 ± 1 mils and reflectorized with glass beads, the polyurea markings shall reach a no-track condition in 10 minutes or less. Dry to "no-tracking" shall be considered as the condition where no visual deposition of the polyurea marking to the pavement surface is observed when viewed from a distance of 50 feet, after a traveling vehicle's tires have passed over the line.
- (G) Adhesion: The catalyzed polyurea pavement marking materials when applied to a 100 mm x 100 mm x 50 mm (4 in. x 4 in. x 2 in.) concrete block shall have a degree of adhesion which results in a 100 percent concrete failure in the performance of this test. The concrete block shall be brushed on one side and

have a minimum strength of 24,100 kPa (3500 psi). A 50 mm (2 in.) square film of the mixed polyurea shall be applied to the brushed surface and allowed to cure for 72 hours at room temperature. A 50 mm (2 in.) square cube is then affixed to the surface of the polyurea by means of an epoxy glue. After the glue has cured for 24 hours, the polyurea specimen is placed on a dynamic testing machine in such a fashion so that the specimen block is in a fixed position and the 50 mm (2 in.) cube (glued to the polyurea surface) is attached to the dynamometer head. Slowly apply direct upward pressure until the

polyurea system fails. Record the location of the break and the amount of concrete failure.

- (H) Hardness: The polyurea pavement marking materials when tested according to ASTM D2240, shall have a shore D hardness of between 70 and 100. Films shall be cast on a rigid substrate at 0.35 mm to 0.41 mm (14 to 16 mils) in thickness and allowed to cure at room temperature for 72 hours before testing.
- (I) Abrasion: The abrasion resistance shall be evaluated according to ASTM D 4060 using a Taber Abrader with a 1,000 gram load and CS 17 wheels. The duration of test shall be 1,000 cycles. The loss shall be calculated by difference and be less than 110 mgs. The tests shall be run on cured

samples of polyurea material which have been applied at a film thickness of 0.35 mm to 0.41 mm (14 to 16 mils) to code S-16 stainless steel plates. The films shall be allowed to cure at room temperature for at least 72 hours before testing.

(J) The reflective media shall meet the following requirements:

The glass beads shall meet the requirements of Article 1095.07 and the following requirements:

(a) The first drop glass beads shall be tested by the standard visual method of large glass spheres adopted by the Department. The beads shall have a silane coating and meet the following sieve requirements:

| Sieve | U.S. Standard | % Passing |
|---------|---------------|-------------|
| Size | Sieve Number | (By Weight) |
| 1.70 mm | 12 | 95-100 |
| 1.40 mm | 14 | 75-95 |
| 1.18 mm | 16 | 10-47 |
| 1.00 mm | 18 | 0-7 |
| 850 µm | 20 | 0-5 |

- (b) The second drop glass beads shall meet the requirements of Type B.
- (K) Packaging: Glass beads shall be delivered in approved moisture proof bags or weather resistant bulk boxes.

Moisture proof bags shall consist of at least five-ply paper construction unless otherwise specified. Each bag shall contain 22.7 kg (50 pounds) net, and shall be legibly marked with the manufacturer, specifications and type, lot number, and the month and year the glass beads were packaged. The letters and numbers used in the stencils shall be a minimum of 12.7 mm. (1/2 inch) in height.

Bulk weather resistance boxes must conform to Federal Specification PPP-8-640D Class II or latest revision. Boxes are to be weather resistant, triple wall, fluted, corrugated-fiber board. Cartons shall be strapped with two (2) metal straps. Straps shall surround the outside perimeter of the carton. The first strap shall be located approximately 2 inches from the bottom of the carton and the second strap shall be placed approximately in the middle of the carton. All cartons shall be shrink wrapped for protection from moisture. Cartons must be lined with a minimum 4 mil polyester bag and meet ICC requirements. Cartons shall be approximately 38 X 38 inches, contain 2,000 lbs. of glass beads and be supported on a wooden pallet with fiber straps. Each carton shall be legibly marked with the manufacturer, specifications and type, lot number, and the month and year the glass beads were packaged. The letters and numbers used in the stencils shall be a minimum of 12.7 mm (1/2 inch) in height.

- (L) The material shall be shipped to the job site in substantial containers and shall be plainly marked with the manufacturer's name and address, the name and color of the material, date of manufacture, and batch number.
- (M) Prior to approval and use of the polyurea pavement marking materials, the manufacturer shall submit a notarized certification of an independent laboratory, together with the results of all tests, stating these materials meet the requirements as set forth herein. The certification test report shall state the lot tested, manufacturer's name, brand name of polyurea and date of manufacture.

After approval by the Department, certification by the polyurea manufacturer shall be submitted for each batch used. New independent laboratory certified test results shall be submitted any time the manufacturing process or paint formulation is changed. All costs of testing shall be borne by the manufacturer.

(N) The manufacturer shall retain the test sample for a minimum of 18 months.

APPLICATION EQUIPMENT

The polyurea pavement marking compounds shall be applied through equipment specifically designed to apply two component liquid materials in 2 to 1 volumetric ratio. The equipment may be equipped to dispense glass beads. If the equipment is not equipped to dispense glass beads, an auxiliary method of dispensing the beads will be required. The two-component liquid materials shall be applied after being accurately metered and then mixed with a static mix tube or airless impingement mixing guns.

The equipment shall have a metering device to register the accumulated installed quantities for each gun, each day.

The mobile applicator shall include the following features:

The mobile applicator shall provide individual material reservoirs, or space for the storage of Part A and Part B of the resin composition. The material reservoir for Part B shall be provided with a means to exclude moisture, such as a nitrogen blanket or air input that has been dried with a desiccant.

The applicator shall be equipped with heating equipment of sufficient capacity to reduce the viscosity of Part A and Part B. If so, the heating should allow the maintenance of a temperature range of 38 to 66° C (100 to 150° F) and should never allow the material to attain a temperature greater than 68° C (155° F). The equipment shall be capable of heating and maintaining the Part A and Part B liquid components at separate, controllable temperatures to enable proper loading, mixing and spraying of the material.

The applicator may be equipped with glass bead dispensing equipment capable of dispensing the glass beads after the liquid has been applied. If the applicator is not equipped to dispense beads, an alternative means of dispensing glass beads will be required.

The application equipment shall be equipped with metering devices or pressure gauges on the proportioning pumps as well as stroke counters to monitor volumetric usage. Metering devices or pressure gauges and stroke counters shall be visible to the engineer.

APPLICATION

The pavement shall be cleaned by a method approved by the Engineer, or as recommended by the manufacturer of the material, to remove all dirt, grease, glaze or any other material that would reduce the adhesion of the markings with minimum or no damage to the pavement. New PCC pavements shall be blast-cleaned to remove all latents.

Prior to the application of the polyurea pavement markings, over any existing pavement markings, the existing pavement markings shall to removed as approved by the Engineer or as recommended by the manufacturer of the material. The removal of the existing pavement markings shall be paid for in accordance with Section 783 of the Standard Specifications for Road and Bridge Construction.

Markings shall be applied to the cleaned surfaces on the same calendar day. If this cannot be accomplished, the surface shall be re-cleaned prior to applying the markings. No markings shall be applied until the Engineer approves the cleaning.

Widths, lengths and shapes of the cleaned surface shall be of sufficient size to include the full area of the specified pavement marking to be placed.

The pavement markings shall be applied to the cleaned road surface, during conditions of dry weather and subsequently dry pavement surfaces at a minimum uniform wet thickness of **20 mils** in accordance with the manufacturer's installation instructions and at the widths and patterns shown on the contract plans. On open grade friction course surface, the pavement markings shall be applied at a minimum uniform wet thickness of **25 mils**. At the time of installation the pavement

surface temperature and the ambient temperature shall be above 4° C (40° F) and rising. The pavement markings shall not be applied if the pavement shows any visible signs of moisture or it is anticipated that damage causing moisture, such as rain showers, may occur during the installation and set periods. The Engineer shall determine the atmospheric conditions and pavement surface conditions that produce satisfactory results.

The specified reflective media (glass beads) as specified by the manufacturer shall dropped onto the liquid marking (within one minute of spraying the liquid onto the pavement surface) and applied at a rate of 0.12 pounds per square foot (54 grams per square foot).

Using the application equipment the pavement markings shall be applied in the following manner, as a simultaneous operation:

- (1) The surface is air-blasted to remove any dirt and residue if present.
- (2) The resin, mixed and heated in accordance with the manufacturer's recommendations, is sprayed onto the pavement surface. Part A shall be thoroughly mixed (mechanical agitation is strongly recommended) prior to use.
- (3) Unless directed by the Engineer, lines shall not be laid directly over a longitudinal crack or joint. The edge of the center line or lane line shall be offset a minimum distance of 50 mm (2 inches) from a longitudinal crack or joint.

Notification:

The Contractor shall notify the Engineer 72 hours prior to the placement of the markings in order that an inspector can be present during the operation. At the time of this notification, the Contractor shall indicate the manufacturer and lot numbers of polyurea and reflective media that he intends to use. The Engineer will ensure that the approved lot numbers appear on the material package. Failure to comply with this provision may be cause for rejection.

The Contractor shall provide an accurate temperature-measuring device(s) that shall be capable of measuring the pavement temperature prior to application of the material, the material temperature at the gun tip and the material temperature prior to mixing.

Inspection:

The polyurea pavement markings will be inspected following installation, but no later than December 15, and inspected following a winter performance period that extends 180 days from December 15 in accordance with the provisions of Article 780.10 of the Standard Specification for Road and Bridge Construction.

Method of Measurement:

The lines will be measured for payment in feet of polyurea pavement marking lines applied and accepted, measured in place. Double yellow lines will be measured as two separate lines. Words, letters and symbols shall conform to the size and dimensions specified in the Illinois Manual on Uniform Traffic Control Devices, Standard 780001 and will be measured based on the total areas indicated in Table 1 of Section 780 of the Standard Specifications for Road and Bridge Construction or as specified in the plans.

Basis of Payment:

This work will be paid for at the contract unit prices per foot of applied line for POLYUREA PAVEMENT MARKING SPECIAL - LINE 4, 5, 6, 8, 12 or 24 inches or per square foot for POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL.

URETHANE PAVEMENT MARKING

Effective March 25, 2005

<u>Description</u>: This work shall consist of furnishing and applying a reflectorized modified urethane, plural component, durable liquid pavement marking lines, sizes and colors as shown on the plans.

Materials: All materials shall meet the following specifications:

- (a) Modified Urethane Marking: The modified urethane pavement marking material shall consist of a homogeneous blend of modified urethane resins and pigments designed to provide a simple volumetric mixing ratio of two components (must be two volumes of Part A to one volume of Part B). No volatile solvent or fillers will be allowed.
- (b) Pigmentation: The pigment content by weight of Component A shall be determined by low temperature ashing according to ASTM D 3723. The pigment content shall not vary more then + two percent from the pigment content of the original qualified paint.

White Pigment shall be Titanium Dioxide meeting ASTM D 476 Type II, Rutile.

Yellow Pigment shall be Organic Yellow and contain no heavy metals.

- (c) Environmental: Upon heating to application temperature, the material shall not exude fumes, which are toxic or injurious to persons or property when handled according to manufacturer specifications. The modified urethane pavement marking material compositions shall not contain free isocyanate functionality.
- (d) Daylight Reflectance: The daylight directional reflectance of the cured modified urethane material (without reflective media) shall be a minimum of 80 percent (white) and 50 percent (yellow) relative to magnesium oxide when tested using a color spectrophotometer with a 45 degree circumferential / zero degrees geometry, illuminant C, and two degrees observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm. In addition, the color of the yellow modified urethane shall visually match Color Number 33538 of Federal Standard 595a with chromaticity limits as follows:

| Х | 0.490 | 0.475 | 0.485 | 0.539 |
|---|-------|-------|-------|-------|
| У | 0.470 | 0.438 | 0.425 | 0.456 |

(e) Weathering Resistance: The modified urethane, when mixed in the proper ratio and applied at 0.35 to 0.41 mm (14 to 16 mils) wet film thickness to an aluminum alloy panel

(Federal Test Std. No. 141, Method 2013) and allowed to cure for 72 hours at room temperature, shall be subjected to accelerated weathering for 75 hours. The accelerated weathering shall be completed by using the light and water exposure apparatus (fluorescent UV – condensation type) and tested according to ASTM G 53.

The cycle shall consist of four hours UV exposure at 50 °C (122 °F) and four hours of condensation at 40 °C (104 °F). UVB 313 bulbs shall be used. At the end of the exposure period, the material shall show no substantial change in color or gloss.

- (f) Drying Time: The modified urethane material, when mixed in the proper ratio and applied at 0.35 to 0.41 mm (14 to 16 mils) wet film thickness and with the proper saturation of glass spheres, shall exhibit a no-tracking time of three minutes or less when tested according to ASTM D 711.
- (g) Adhesion: The catalyzed modified urethane pavement marking materials when applied to a 100 x 100 x 50 mm (4 x 4 x2 in) concrete block shall have a degree of adhesion which results in a 100 percent concrete failure in the performance of this test.

The concrete block shall be brushed on one side and have a minimum strength of 24,100 kPa (3,500 psi). A 50 mm (2 in) square film of the mixed modified urethane shall be applied to the brushed surface and allowed to cure for 72 hours at room temperature. A 50 mm (2 in) square cube shall be affixed to the surface of the modified urethane by means of an epoxy glue. After the glue has cured for 24 hours, the modified urethane specimen shall be placed on a dynamic testing machine in such a fashion so that the specimen block is in a fixed position and the 50 mm (2 in) cube (glued to the modified urethane surface) is attached to the dynamometer head. Direct upward pressure shall be slowly applied until the modified urethane system fails. The location of the break and the amount of concrete failure shall be recorded.

- (h) Hardness: The modified urethane marking materials, when tested according to ASTM D-2240, shall have a Shore D Hardness greater than 75. Films shall be cast on a rigid substrate at 0.35 to 0.41 mm (14 to 16 mils) in thickness and allowed to cure at room temperature for 72 hours before testing.
- (i) Abrasion: The abrasion resistance shall be evaluated on a Taber Abrader with a 1,000 gram load and CS-17 wheels. The duration of test shall be 1,000 cycles. The wear index shall be calculated based on ASTM test method D-4060 and the wear index for the catalyzed material shall not be more than 80. The tests shall be run on cured samples of modified urethane material which have been applied at a film thickness of 0.35 to 0.41 (14 to 16 mils) to code S-16 stainless steel plates. The films shall be allowed to cure at room temperature for at least 72 hours and not more than 96 hours before testing.
- (j) Tensile: When tested according to ASTM D-638, the modified urethane pavement marking materials shall have an average tensile strength of not less than 6,000 pounds per square inch. The Type IV Specimens shall be pulled at a rate of ¼" per minute by a suitable dynamic testing machine. The samples shall be allowed to cure at 75 °F± 2°F for a minimum of 24 hours and a maximum of 72 hours prior to performing the indicated tests.

- (k) Compressive Strength: When tested according to ASTM D-695, the catalyzed modified urethane pavement marking materials shall have a compressive strength of not less than 12,000 pounds per square inch. The cast sample shall be conditioned at 75°F± 2°F for a minimum of 72 hours before performing the indicated tests. The rate of compression of these samples shall be no more than ¼"per minute.
- (I) Glass Spheres: The glass spheres shall meet the requirements of Article 1095.04(m) and Article 1095.07 of the Standard Specifications for first drop and second drop glass beads.
- (m) The material shall be shipped to the job site in substantial containers and shall be plainly marked with the manufacturer's name and address, the name and color of the material, date of manufacture and batch number.
- (n) Prior to approval and use of the modified urethane pavement marking materials, the manufacturer shall submit a notarized certification of an independent laboratory, together with the results of all tests, stating these materials meet the requirements as set forth herein. The certification test report shall state the lot tested, manufacturer's name, brand name of modified urethane and date of manufacture. The certification shall be accompanied by one half-liter (one-pint) samples each of Part A and Part B. Samples shall be sent in the appropriate volumes for complete mixing of Part A and Part B.

After approval by the Department, certification by the modified urethane manufacturer shall be submitted for each batch used. New independent laboratory certified test results and samples for testing by the Department shall be submitted any time the manufacturing process or paint formulation is changed. All costs of testing (other than tests conducted by the Department) shall be borne by the manufacturer.

- (o) Acceptance samples shall consist of one half-liter (one-pint) samples of Part A and Part B, of each lot of paint. Samples shall be sent in the appropriate volumes for complete mixing of Part A and Part B. The samples shall be submitted to the Department for testing, together with a manufacturer's certification. The certification shall state the formulation for the lot represented is essentially identical to that used for qualification testing. All, acceptance samples shall be taken by a representative of the Illinois Department of Transportation. The modified urethane pavement marking materials shall not be used until tests are completed and they have met the requirements as set forth herein.
- (p) The manufacturer shall retain the test sample for a minimum of 18 months.

APPLICATION EQUIPMENT

The modified urethane pavement marking compounds shall be applied through equipment specifically designed to precisely meter the two components in the ratio of 2:1 and approved by the manufacturer of the material. This equipment shall produce the required amount of heat at the mixing head and gun tip and maintain those temperatures within the tolerances specified. This equipment shall also have as an integral part of the gun carriage, a high pressure air spray capable of cleaning the pavement immediately prior to the marking application.

The equipment shall be capable of spraying both yellow and white urethane, according to the manufacturer's recommended proportions and be mounted on a truck of sufficient size and stability with an adequate power source to produce lines of uniform dimensions and prevent application failure. The truck shall have at least two urethane tanks each of 415 L (110 gal) minimum capacity and shall be equipped with hydraulic systems. It shall be capable of placing stripes on the left and right sides and placing two lines on a three-line system simultaneously with either line in a solid or intermittent pattern, in yellow or white, and applying glass beads by the double drop pressurized bead system. The system shall apply both the first drop glass beads and the second drop glass beads at a rate of 1.2 kg per L (10 lb/gal). The equipment shall be equipped with pressure gauges for each proportioning pump. All guns shall be in full view of operators at all times. The equipment shall have a metering device to register the accumulated installed quantities for each gun, each day. Each vehicle shall include at least one operator who shall be a

technical expert in equipment operations and urethane application techniques. Certification of equipment shall be provided at the preconstruction conference.

APPLICATION

The pavement shall be cleaned by a method approved by the Engineer to remove all dirt, grease, glaze or any other material that would reduce the adhesion of the markings with minimum or no damage to the pavement. New PCC pavements shall be blast-cleaned to remove all curing compounds.

Markings shall be applied to the cleaned surfaces on the same calendar day. If this cannot be accomplished, the surface shall be re-cleaned prior to applying the markings. Existing pavement markings shall be at least 90 percent removed. No markings shall be applied until the Engineer approves the cleaning.

Widths, lengths and shapes of the cleaned surface shall be prepared wider then the modified urethane pavement marking material to be applied, such that a prepared area is on all sides of the urethane pavement marking material after application.

New asphalt concrete and seal coated surfaces shall be in place a minimum of two weeks prior to marking applications.

The cleaning operation shall be a continuous moving operation process with minimum interruption to traffic.

The pavement markings shall be applied to the cleaned road surface, during conditions of dry weather and subsequently dry pavement surfaces at a minimum uniform wet thickness of 20 mils in accordance with the manufacturer's installation instructions and at the widths and patterns shown on the contract plans. The application and combination of reflective media (glass beads and/or reflective elements) shall be applied at a rate specified by the manufacturer. At the time of installation the pavement surface temperature shall be 40 ° F and rising and the ambient temperature shall be 35° F and rising. The pavement surface temperature and the ambient temperatures shall be determined and documented before the start of each of marking operation. The pavement markings shall not be applied if the pavement shows any visible signs of moisture or it is anticipated that damage causing moisture, such as

rain showers, may occur during the installation and curing periods. The Engineer shall determine the atmospheric conditions and pavement surface conditions that produce satisfactory results.

Unless directed by the Engineer, lines shall not be laid directly over a longitudinal crack or joint. The edge of the center line or lane line shall be offset a minimum distance of 50 mm (2 inches) from a longitudinal crack or joint. Edge lines shall be approximately 50 mm (2 inches) from the edge of pavement. The finished center and lane lines shall be straight, with the lateral deviation of any 3 meter (10-foot) line not to exceed 25 mm (1 inch).

Notification:

The Contractor shall notify the Engineer 72 hours prior to the placement of the markings in order that an inspector can be present during the operation. At the time of this notification, the Contractor shall indicate the manufacturer and lot numbers of urethane and reflective media that he intends to use. The Engineer will ensure that the approved

lot numbers appear on the material package. Failure to comply with this provision may be cause for rejection.

The Contractor shall provide an accurate temperature-measuring device(s) that shall be capable of measuring the pavement temperature prior to application of the material, the material temperature at the gun tip and the material temperature prior to mixing.

Inspection:

The urethane pavement markings will be inspected following installation, but no later than December 15, and inspected following a winter performance period that extends 180 days from December 15 in accordance with the provisions of Article 780.10 of the Standard Specification for Road and Bridge Construction.

Method of Measurement:

The lines will be measured for payment in feet of urethane pavement marking lines applied and accepted, measured in place. Double yellow lines will be measured as two separate lines. Words and symbols shall conform to the size and dimensions specified in the Manual on Uniform Traffic Control Devices and Standard 780001 and will be measured based on total areas indicated in table 1 or as specified in the plans.

Basis of Payment:

This work will be paid for at the contract unit prices per foot of applied line for URETHANE PAVEMENT MARKING - LINE 4, 5, 6, 8, 12, 24 inches or per square foot for URETHANE PAVEMENT MARKING – LETTERS AND SYMBOLS measured as specified herein.

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000 Revised: January 1, 2007

<u>FEDERAL OBLIGATION</u>. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR part 26 and listed in the DBE Directory or most recent addendum.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE</u>. The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor:

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE firms performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. This determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform 5.0% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this

contract, the Department will award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set forth in this Special Provision:

- (a) The bidder documents that firmly committed DBE participation has been obtained to meet the goal; or
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

<u>DBE LOCATOR REFERENCES</u>. Bidders may consult the DBE Directory as a reference source for DBE companies certified by the Department. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's web site at www.dot.il.gov.

<u>BIDDING PROCEDURES</u>. Compliance with the bidding procedures of this Special Provision is required prior to the award of the contract and the failure of the as-read low bidder to comply will render the bid not responsive.

- (a) In order to assure the timely award of the contract, the as-read low bidder shall submit a Disadvantaged Business Utilization Plan on Department form SBE 2026 within seven working days after the date of letting. To meet the seven day requirement, the bidder may send the Plan by certified mail or delivery service within the seven working day period. If a question arises concerning the mailing date of a Plan, the mailing date will be established by the U.S. Postal Service postmark on the original certified mail receipt from the U.S. Postal Service or the receipt issued by a delivery service. It is the responsibility of the bidder to ensure that the postmark or receipt date is affixed within the seven working days if the bidder intends to rely upon mailing or delivery to satisfy the submission day requirement. The Plan is to be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). It is the responsibility of the bidder to obtain confirmation of telefax delivery. The Department will not accept a Utilization Plan if it does not meet the seven day submittal requirement and the bid will be declared not responsive. In the event the bid is declared not responsive due to a failure to submit a Plan or failure to comply with the bidding procedures set forth herein, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty, and may deny authorization to bid the project if re-advertised for bids. The Department reserves the right to invite any other bidder to submit a Utilization Plan at any time for award consideration or to extend the time for award.
- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE

participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number, and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.

- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. The signatures on these forms must be original signatures. All elements of information indicated on the said form shall be provided, including but not limited to the following:
 - (1) The name and address of each DBE to be used;
 - (2) A description, including pay item numbers, of the commercially useful work to be done by each DBE;
 - (3) The price to be paid to each DBE for the identified work specifically stating the quantity, unit price, and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
 - (4) A commitment statement signed by the bidder and each DBE evidencing availability and intent to perform commercially useful work on the project; and
 - (5) If the bidder is a joint venture comprised of DBE firms and non-DBE firms, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s).
- (d) The contract will not be awarded until the Utilization Plan submitted by the bidder is approved. The Utilization Plan will be approved by the Department if the Plan commits sufficient commercially useful DBE work performance to meet the contract goal. The Utilization Plan will not be approved by the Department if the Plan does not commit sufficient DBE performance to meet the contract goal unless the bidder documents that it made a good faith effort to meet the goal. The good faith procedures of Section VIII of this special provision apply. If the Utilization Plan is not approved because it is deficient in a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no less than a five working day period in order to cure the deficiency.

<u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE firm does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE firm does not count toward the DBE goal.
- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contact. Credit will be given for the full value of all such DBE trucks operated using DBE employed drivers. Goal credit will be limited to the value of the reasonable fee or commission received by the DBE if trucks are leased from a non-DBE company.
- (e) DBE as a material supplier:
 - (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
 - (2) 100 percent goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
 - (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.

GOOD FAITH EFFORT PROCEDURES. If the bidder cannot obtain sufficient DBE commitments to meet the contract goal, the bidder must document in the Utilization Plan the good faith efforts made in the attempt to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which could reasonably be expected to obtain sufficient DBE participation. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere *pro forma* efforts are not good faith efforts; rather, the bidder is expected to have taken those efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

(a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.

- (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
- (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
- (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
- (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
 - b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.
- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.
- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.

- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines that the bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that a good faith effort has not been made, the Department will notify the bidder of that preliminary determination by contacting the responsible company official designated in the Utilization Plan. The preliminary determination shall include a statement of reasons why good faith efforts have not been found, and may include additional good faith efforts that the bidder could take. The notification will designate a five working day period during which the bidder shall take additional efforts. The bidder is not limited by a statement of additional efforts, but may take other action beyond any stated additional efforts in order to obtain additional DBE commitments. The bidder shall submit an amended Utilization Plan if additional DBE commitments to meet the contract goal are secured. If additional DBE commitments sufficient to meet the contract goal are not secured, the bidder shall report the final good faith efforts made in the time allotted. All additional efforts taken by the bidder will be considered as part of the bidder's good faith efforts. If the bidder is not able to meet the goal after taking additional efforts, the Department will make a pre-final determination of the good faith efforts of the bidder and will notify the designated responsible company official of the reasons for an adverse determination.
- (c) The bidder may request administrative reconsideration of a pre-final determination adverse to the bidder within the five working days after the notification date of the determination by delivering the request to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The pre-final determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issue of whether an adequate good faith effort was made to meet the contract goal. In addition, the request shall be considered a consent by the bidder to extend the time for award. The request will be forwarded to the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal.

- (a) No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217) 785-4611. Telefax number (217) 785-1524.
- (b) All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the Participation Statement. The Contractor shall not terminate for convenience a DBE listed in the Utilization Plan and then perform the work of the terminated DBE with its own forces, those of an affiliate or those of another subcontractor, whether DBE or not, without first obtaining the written consent of the Bureau of Small Business Enterprises to amend the Utilization Plan. If a DBE listed in the Utilization Plan is terminated for reasons other than convenience, or fails to complete its work on the contract for any reason, the Contractor shall make good faith efforts to find another DBE to substitute for the terminated DBE. The good faith efforts shall be directed at finding another DBE to perform at least the same amount of work under the contract as the DBE that was terminated, but only to the extent needed to meet the contract goal or the amended contract goal. The Contractor shall notify the Bureau of Small Business Enterprises of any termination for reasons other than convenience, and shall obtain approval for inclusion of the substitute DBE in the Utilization Plan. If good faith efforts following a termination of a DBE for cause are not successful, the Contractor shall contact the Bureau and provide a full accounting of the efforts undertaken to obtain substitute DBE participation. The Bureau will evaluate the good faith efforts in light of all circumstances surrounding the performance status of the contract, and determine whether the contract goal should be amended.
- (c) The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefor to the DBE by the Contractor, but not later than thirty calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Report on Department form SBE 2115 to the Regional Engineer. If full and final payment has not been made to the DBE, the Report shall indicate whether a disagreement as to the

payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Plan, the Department will deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages.

- (d) The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (e) Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department.

ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE)

Effective: January 1, 2007 Revised: April 1, 2007

- Page 60 Article 109.07(a). In the second line of the first paragraph change "amount" to "quantity".
- Page 207 Article 406.14. In the second line of the second paragraph change "MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS, of the mixture composition specified;" to "MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS;".
- Page 345 Article 505.08(I). In the third line of the first paragraph change "1/8 mm" to "1/8 in.".
- Page 345 Article 505.08(I). In the nineteenth line of the first paragraph change "is" to "in".
- Page 383 Article 516.04(b)(1). In the fifth line of the first paragraph change "drillingpouring" to "pouring".
- Page 390 Article 520.02(h). Change "1027.021" to "1027.01".
- Page 398 Article 540.07(b). Add the following two paragraphs after the third paragraph:

"Excavation in rock will be measured for payment according to Article 502.12.

Removal and disposal of unstable and/or unsuitable material below plan bedding grade will be measured for payment according to Article 202.07."

Page 398 Article 540.08. Add the following two paragraphs after the fifth paragraph:

"Excavation in rock will be paid for according to Article 502.13.

Removal and disposal of unstable and/or unsuitable material below plan bedding grade will be paid for according to Article 202.08."

- Page 435 Article 542.04(b). Delete the last sentence of the last paragraph.
- Page 465 Article 551.06. In the second line of the first paragraph change "or" to "and/or".
- Page 585 Article 701.19(a). Add "701400" to the second line of the first paragraph.
- Page 586 Article 701.19(c). Delete "701400" from the second line of the first paragraph.
- Page 586 Article 701.19. Add the following subparagraph to this Article:
 - "(f) Removal of existing pavement markings and raised reflective pavement markers will be measured for payment according to Article 783.05."
- Page 587 Article 701.20(b). Delete "TRAFFIC CONTROL AND PROTECTION 701400;" from the first paragraph.
- Page 588 Article 701.20. Add the following subparagraph to this Article.
 - "(j) Removal of existing pavement markings and raised reflective pavement markers will be paid for according to Article 783.06."
- Page 762 Article 1020.04. In Table 1 Classes of Portland Cement Concrete and Mix Design Criteria, add to the minimum cement factor for Class PC Concrete "5.65 (TY III)", and add to the maximum cement factor for Class PC Concrete "7.05 (TY III)".
- Page 765 Article 1020.04. In Table 1 Classes of Portland Cement Concrete and Mix Design Criteria (metric), add to the minimum cement factor for Class PC Concrete "335 (TY III)", and add to the maximum cement factor for Class PC Concrete "418 (TY III)".
- Page 800 Article 1030.05(a)(12). Revise "Dust Collection Factor" to "Dust Correction Factor".
- Page 800 Article 1030.05(a)(14). Revise the first occurrence of Article 1030.05(a)(14) to Article 1030.05(a)(13).
- Page 809 Article 1030.05. Revise the subparagraph "(a) Quality Assurance by the Engineer." to read "(e) Quality Assurance by the Engineer.".

Page 946 Article 1080.03(a)(1). In the third line of the first paragraph revise " $(300 \mu m)$ " to " $(600 \mu m)$ ".

Page 963 Article 1083.02(b). In the second line of the first paragraph revise "ASTM D 4894" to "ASTM D 4895".

Page 1076 In the Index of Pay Items delete the pay item "BITUMINOUS SURFACE REMOVAL – BUTT JOINT".

PAYMENTS TO SUBCONTRACTORS (BDE)

Effective: June 1, 2000 Revised: January 1, 2006

Federal regulations found at 49 CFR §26.29 mandate the Department to establish a contract clause to require Contractors to pay subcontractors for satisfactory performance of their subcontracts and to set the time for such payments.

State law also addresses the timing of payments to be made to subcontractors and material suppliers. Section 7 of the Prompt Payment Act, 30 ILCS 540/7, requires that when a Contractor receives any payment from the Department, the Contractor shall make corresponding, proportional payments to each subcontractor and material supplier performing work or supplying material within 15 calendar days after receipt of the Department payment. Section 7 of the Act further provides that interest in the amount of two percent per month, in addition to the payment due, shall be paid to any subcontractor or material supplier by the Contractor if the payment required by the Act is withheld or delayed without reasonable cause. The Act also provides that the time for payment required and the calculation of any interest due applies to transactions between subcontractors and lower-tier subcontractors and material suppliers throughout the contracting chain.

This Special Provision establishes the required federal contract clause, and adopts the 15 calendar day requirement of the State Prompt Payment Act for purposes of compliance with the federal regulation regarding payments to subcontractors. This contract is subject to the following payment obligations.

When progress payments are made to the Contractor according to Article 109.07 of the Standard Specifications, the Contractor shall make a corresponding payment to each subcontractor and material supplier in proportion to the work satisfactorily completed by each subcontractor and for the material supplied to perform any work of the contract. The proportionate amount of partial payment due to each subcontractor and material supplier throughout the contracting chain shall be determined by the quantities measured or otherwise determined as eligible for payment by the Department and included in the progress payment to the Contractor. Subcontractors and material suppliers shall be paid by the Contractor within 15 calendar days after the receipt of payment from the Department. The Contractor shall not hold retainage from the subcontractors. These obligations shall also apply to any payments made by subcontractors and material suppliers to their subcontractors and material suppliers; and to all payments made to lower tier subcontractors and material suppliers throughout the contracting chain. Any payment or portion of a payment subject to this provision may only be withheld from the subcontractor or material supplier to whom it is due for reasonable cause.

This Special Provision does not create any rights in favor of any subcontractor or material supplier against the State or authorize any cause of action against the State on account of any payment, nonpayment, delayed payment, or interest claimed by application of the State Prompt Payment Act. The Department will not approve any delay or postponement of the 15 day requirement except for reasonable cause shown after notice and hearing pursuant to Section 7(b) of the State Prompt Payment Act. State law creates other and additional remedies available to any subcontractor or material supplier, regardless of tier, who has not been paid for work properly performed or material furnished. These remedies are a lien against public funds set forth in Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c), and a recovery on the Contractor's payment bond according to the Public Construction Bond Act, 30 ILCS 550.

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE)

Effective: April 1, 2007

Revise the seventh paragraph of Article 1106.02 of the Standard Specifications to read:

"At the time of manufacturing, the retroreflective prismatic sheeting used on channelizing devices shall meet or exceed the initial minimum coefficient of retroreflection as specified in the following table. Measurements shall be conducted according to ASTM E 810, without averaging. Sheeting used on cones, drums and flexible delineators shall be reboundable as tested according to ASTM D 4956. Prestriped sheeting for rigid substrates on barricades shall be white and orange.

| Initial Minimum Coefficient of Retroreflection candelas/foot candle/sq ft (candelas/lux/sq m) of material | | | | |
|---|-----------------------|-------|--------|-----------------------|
| Observation Angle (deg.) | Entrance Angle (deg.) | White | Orange | Fluorescent Orange |
| 0.2 | -4 | 365 | 160 | 150 |
| 0.2 | +30 | 175 | 80 | 70 |
| 0.5 | -4 | 245 | 100 | 95 |
| 0.5 | +30 | 100 | 50 | 40" |

Revise the first sentence of the first paragraph of Article 1106.02(c) of the Standard Specifications to read:

Revise the third sentence of the first paragraph of Article 1106.02(d) of the Standard Specifications to read:

[&]quot;Barricades and vertical panels shall have alternating white and orange stripes sloping downward at 45 degrees toward the side on which traffic will pass."

[&]quot;The bottom panels shall be 8 x 24 in. (200 x 600 mm) with alternating white and orange stripes sloping downward at 45 degrees toward the side on which traffic will pass."

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: April 2, 2005

To account for the preparatory work and operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting in accordance with Article 108.01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

THERMOPLASTIC PAVEMENT MARKINGS (BDE)

Effective: January 1, 2007

Revise Article 1095.01(a)(2) of the Standard Specifications to read:

"(2) Pigment. The pigment used for the white thermoplastic compound shall be a high-grade pure (minimum 93 percent) titanium dioxide (TiO₂). The white pigment content shall be a minimum of ten percent by weight and shall be uniformly distributed throughout the thermoplastic compound.

The pigments used for the yellow thermoplastic compound shall not contain any hazardous materials listed in the Environmental Protection Agency Code of Federal Regulations (CFR) 40, Section 261.24, Table 1. The combined total of RCRA listed heavy metals shall not exceed 100 ppm when tested by X-ray fluorescence spectroscopy. The pigments shall also be heat resistant, UV stable and color-fast yellows, golds, and oranges, which shall produce a compound which shall match Federal Standard 595 Color No. 33538. The pigment shall be uniformly distributed throughout the thermoplastic compound."

Revise Article 1095.01(b)(1)e. of the Standard Specifications to read:

"e. Daylight Reflectance and Color. The thermoplastic compound after heating for four hours ± five minutes at 425 ± 3 °F (218.3 ± 2 °C) and cooled at 77 °F (25 °C) shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45 degree circumferential/zero degree geometry, illuminant C, and two degree observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm.

White: Daylight Reflectance75 percent min. *Yellow: Daylight Reflectance45 percent min.

*Shall meet the coordinates of the following color tolerance chart.

Various Routes Section D1 H-T PVT MKG REP 2007-08 Various Counties Contract No. 44959

| Χ | 0.490 | 0.475 | 0.485 | 0.530 |
|---|-------|-------|-------|--------|
| V | 0.470 | 0.438 | 0.425 | 0.456" |

Revise Article 1095.01(b)(1)k. of the Standard Specifications to read:

"k. Accelerated Weathering. After heating the thermoplastic for four hours ± five minutes at 425 ± 3 °F (218.3 ± 2 °C) the thermoplastic shall be applied to a steel wool abraded aluminum alloy panel (Federal Test Std. No. 141, Method 2013) at a film thickness of 30 mils (0.70 mm) and allowed to cool for 24 hours at room temperature. The coated panel shall be subjected to accelerated weathering using the light and water exposure apparatus (fluorescent UV - condensation type) for 75 hours according to ASTM G 53 (equipped with UVB-313 lamps).

The cycle shall consist of four hours UV exposure at 122 °F (50 °C) followed by four hours of condensation at 104 °F (40 °C). UVB 313 bulbs shall be used. At the end of the exposure period, the panel shall not exceed 10 Hunter Lab Delta E units from the original material."

Various Routes D 1 H-T PVT MKG REP 2007-08 Various Counties Sheet 1 of 8 Contract No.: 44959

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION D 1 H-T PVT MKG REP 2007-08 C-60-001-08

Index of Sheets

- 1 Cover Sheet
- 2-5 Summary of Quantities
- 6-8 Typical Work order Forms

Highway Standards

| 701311-02 | 701501-03 |
|-----------|-----------|
| 701400-02 | 701601-04 |
| 701406-04 | 701606-04 |
| 701411-03 | 701701-04 |
| 701426-02 | 702001-06 |
| | 780001-01 |

Contract No. 44959

Various Routes
D 1 H-T PVT MKG REP 2007-08
Various Counties
Sheet 2 of 8
Contract No. 44959

SUMMARY OF QUANTITIES

100% STATE

| CODE | | | URBAN SFTY-1D |
|----------|--|-------|------------------|
| NUMBER | ITEM | LINI | QUANTTY |
| X7800500 | POLYUREA PAVEMENT MARKING LETTERS AND SYMBOLS, SPECIAL | SQ FT | 1,100 |
| X7800510 | POLYUREA PAVEMENT MARKING SPECIAL – LINE 4" | FOOT | 26,000 |
| X7800520 | POLYUREA PAVEMENT MARKING SPECIAL – LINE 5" | FOOT | 11,000 |
| X7800530 | POLYUREA PAVEMENT MARKING SPECIAL – LINE 6" | FOOT | 3,800 |
| X7800540 | POLYUREA PAVEMENT MARKING SPECIAL – LINE 8" | FOOT | 3,800 |
| X7800550 | POLYUREA PAVEMENT MARKING SPECIAL – LINE 12" | FOOT | 3,800 |
| X7800580 | POLYUREA PAVEMENT MARKING SPECIAL – LINE 24" | FOOT | 3,800 |
| X7800600 | URETHANE PAVEMENT MARKING – LETTERS AND SYMBOLS, SPECIAL | SQ FT | 1,000 |
| X7800610 | URETHANE PAVEMENT MARKING – LINE 4" | FOOT | 4,800 |
| X7800620 | URETHANE PAVEMENT MARKING – LINE 5" | FOOT | 4,800 |
| X7800630 | URETHANE PAVEMENT MARKING – LINE 6" | FOOT | 4,800 |
| X7800640 | URETHANE PAVEMENT MARKING – LINE 8" | FOOT | 4,800 |
| X7800650 | URETHANE PAVEMENT MARKING – LINE 12" | FOOT | 2,800 |
| X7800680 | URETHANE PAVEMENT MARKING – LINE 24" | FOOT | 1,000 |

Various Routes
D 1 H-T PVT MKG REP 2007-08
Various Counties
Page 3 of 8
Contract No. 44959

SUMMARY OF QUANTITIES

100% STATE

| CODE | MEH | LIND | URBAN SFTY-1D QUANTTY |
|----------|--|-------|-----------------------------|
| | | 1 | |
| 67100100 | MOBILIZATION | L SUM | ~ |
| 70101700 | TRAFFIC CONTROL AND PROTECTION | L SUM | ~ |
| 78000100 | THERMOPLASTIC PAVEMENT MARKING – LETTERS AND SYMBOLS | SQ FT | 20,000 |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING – LINE 4" | FOOT | 257,000 |
| 78000300 | THERMOPLASTIC PAVEMENT MARKING LINE 5" | FOOT | 26,000 |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING – LINE 6" | FOOT | 39,000 |
| 78000500 | THERMOPLASTIC PAVEMENT MARKING – LINE 8" | FOOT | 8,400 |
| 78000600 | THERMOPLASTIC PAVEMENT MARKING – LINE 12" | FOOT | 12,400 |
| 78000650 | THERMOPLASTIC PAVEMENT MARKING – LINE 24" | FOOT | 8,400 |
| 78000815 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE 4' INCH | FOOT | 95,000 |
| 78000825 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE 5 110CH | FOOT | 47,000 |
| 78000845 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE 8' 1 MCH | FOOT | 17,000 |

Various Routes
D 1 H-T PVT MKG REP 2007-08
Various Counties
Page 4 of 8
Contract No. 44959

SUMMARY OF QUANTITIES

| CODE | ITEM | TIND | 100% STATE URBAN SFTY-1D QUANTTY |
|----------|--|-------|---|
| 78003100 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS | SQ FT | 350 |
| 78003110 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" | FOOT | 400 |
| 78003120 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5" | FOOT | 400 |
| 78003130 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6" | FOOT | 400 |
| 78003140 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8" | FOOT | 400 |
| 78003150 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12" | FOOT | 400 |
| 78003180 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24" | FOOT | 270 |
| 78006100 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 370 |
| 78006110 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 450 |
| 78006120 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 5" | FOOT | 450 |
| 78006130 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 450 |
| 78006140 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 450 |
| 78006150 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 450 |
| 78006180 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 450 |

Various Routes
D 1 H-T PVT MKG REP 2007-08
Various Counties
Page 5 of 8
Contract No. 44959

SUMMARY OF QUANTITIES

| CODE | ITEM | LIND | 100% STATE URBAN SFTY-1D QUANTTY |
|-----------|--|-------|---|
| 7.8008210 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" | FOOT | 29,000 |
| 78008220 | POLYUREA PAVEMENT MARKING TYPE 1 – LINE 5" | FOOT | 19,000 |
| 78008230 | POLYUREA PAVEMENT MARKING TYPE 1 ~ LINE 6" | FOOT | 6,900 |
| 78008240 | POLYUREA PAVEMENT MARKING TYPE 1 – LINE 8" | FOOT | 6,900 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 165,000 |

Various Routes D 1 H-T PVT MKG REP 2007-08 Various Counties Sheet 6 of 8 Contract No. 44959

WORK ORDER

District 1 High-Type Pavement Marking Repair 2007-08

| Sheet 1 of 2 | | | | | | | | | | | |
|--------------|---------------------------------------|---------------|-----------|-------------|-----------|--|--|--|--|--|--|
| WORK ORD | WORK ORDER NO.: DATE OF ISSUE: ROUTE: | | | | | | | | | | |
| LOCATION | DESCRIPTION: | | | | | | | | | | |
| | | . | | | | | | | | | |
| CONTRACT | No. <u>44959</u> | | | | | | | | | | |
| CODE | ITEM | UNIT | QUANTITY | UNIT | ITEM COST | | | | | | |
| NUMBER | | | | PRICE | | | | | | | |
| X7800500 | POLYUREA PM LT-SY SPL | SQ FT | | | | | | | | | |
| X7800510 | POLYUREA PM SPL LN 4 | FOOT | | - | | | | | | | |
| X7800520 | POLYUREA PM SPL LN 5 | FOOT | N | | | | | | | | |
| X7800530 | POLYUREA PM SPL LN 6 | FÖÖT | | | | | | | | | |
| X7800540 | POLYUREA PM SPL LN 8 | FOOT | | | | | | | | | |
| X7800550 | POLYUREA PM SPL LN 12 | FOOT | | | | | | | | | |
| X7800580 | POLYUREA PM SPL LN 24 | FOOT | | | | | | | | | |
| X7800600 | URETHANE PM LT-SY SPL | SQ FT | | | | | | | | | |
| X7800610 | URETH PAVT MK LINE 4 | FOOT | | | | | | | | | |
| X7800620 | URETH PAVT MK LINE 5 | FOOT | | · <u></u> | | | | | | | |
| X7800630 | URETH PAVT MK LINE 6 | FOOT | | | | | | | | | |
| X7800640 | URETH PAVT MK LINE 8 | FOOT | | | | | | | | | |
| X7800650 | URETH PAVT MK ;INE 12 | FOOT | · · · · · | | | | | | | | |
| X7800680 | URETH PAVT MK LINE 24 | FOOT | | | | | | | | | |
| 78000100 | THPL PVT MK LTR & SYM | SQ FT | | | | | | | | | |
| 78000200 | THPL PVT MK LINE 4 | FOOT | | , | | | | | | | |
| 78000300 | THPL PVT MK LINE 5 | FOOT | | | | | | | | | |
| 78000400 | THPL PVT MK LINE 6 | FOOT | | - | | | | | | | |
| 78000500 | THPL PVT MK LINR 8 | FOOT | | | | | | | | | |
| 78000600 | THPL PVT MK LINE 12 | FOOT | | | | | | | | | |
| 78000650 | THPL PVT MK LINE 24 | FOOT | | _ | | | | | | | |
| 78000815 | HS THPL PM LN 4 | FOOT | | | | | | | | | |
| 78000825 | HS THPL PM LN 5 | FOOT | | | | | | | | | |
| 78000845 | HS THPL PM LN 8 | FOOT | | | | | | | | | |
| 78003100 | PREF PL PM TB LTR-SYM | SQ FT | | | | | | | | | |
| 78003110 | PREF PL PM TB LINE 4 | FOOT | | | | | | | | | |
| 78003120 | PREF PL PM TB LINE 5 | FOOT | | | | | | | | | |
| 78003130 | PREF PL PM TB LINE 6 | FOOT | | | | | | | | | |
| 78003140 | PERF PL PM TB LINE 8 | FOOT | | | | | | | | | |
| 78003150 | PREF PL PM TB LINE 12 | FOOT | | | | | | | | | |
| 78003180 | PREF PL PM TB LINE 24 | FOOT | | | | | | | | | |
| 78006100 | PREF THPL PM LTR-SYM | SQ FT | | | | | | | | | |
| 78006110 | PREF THPL PM LINE 4 | FOOT | | | | | | | | | |
| 78006120 | PREF THPL PM LINE 5 | FOOT | | | | | | | | | |

Various Routes D 1 H-T PVT MKG REP 2007-08 Various Counties Page 7 of 8 Contract No. 44959

| Sheet 2 of 2 | | | | | |
|----------------|-----------------------|--|---------------|---------------|---------------------|
| WORK ORD | DER NO.: DIST. 1 HIGH | I-TYPE P. | AVEMENT MA | RKING R | EPAIR 2007-08 |
| CODE NUMBER | ITEM | UNIT | QUANTITY | UNIT PRICE | ITEM COST |
| 78006130 | PREF THPL PM LINE 6 | FOOT | | | |
| 78006140 | PREF THPL PM LINE 8 | FOOT | | | |
| 78006150 | PREF THPL PM LINE 12 | FOOT | | | |
| 78006180 | PREF THPL PM LINE 24 | FOOT | | | |
| 78008210 | POLYUREA PM T1 LN 4 | FOOT | | | |
| 78008220 | POLYUREA PM T1 LN 5 | FOOT | | | |
| 78008230 | POLYUREA PM T1 LN 6 | FOOT | | | |
| 78008230 | POLYUREA PM T1 LN 8 | FOOT | | | |
| | PAVT MARKING REMOVAL | SQ FT | | | <u>.</u> |
| 78300100 | PAVI MARKING REMOVAL | JOUFI | | | |
| | | | | | |
| | | ļ | | | |
| · | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | <u> </u> | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | 7. | - - | | | |
| | | | | | |
| | | | | | 1812 - 1817 TT 11 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | + | 1 | | |
| | | | | | |
| | | - | | | |
| | | 1 | TOTAL C | TPO | *** |
| | | | L | ,031 | |
| DISTRICT C | CONTACT | APPROV | ED BY: | | |
| טוטוועטו כ | , O 1 4 1 / 1 O 1 | , ., , , v | | | , Regional Engineer |
| | | | Sopuly Brioth | Jgyo | , 5 |
| NAME: | | DATE: | | | |
| I ALVIAIC. | | | | | _ |
| TELEPHON | E: | | | | |

Various Routes
D 1 H-T PVT MKG REP 2007-08
Various Counties
Sheet 8 of 8
Contract No. 44959

PAVEMENT MARKING SUMMARY

| | | Marking Removal (Sq. Ft) | | |
|-----------------------|--|--------------------------------|--------|--------|
| | | 24 Inch (Foot) | | |
| | is te | 12 Inch (Foot) | | |
| | of Quantitie (W) = Whi | 8 Inch (Foot) | | |
| IMARY | Summation of Quantities (Y) = Yellow (W) = White | 6 Inch (Foot) | | |
| IG SUM | s C | 5 Inch (Foot) | | |
| MARKIN | | 4 Inch (Foot) | | |
| EMENT MARKING SUMMARY | | Letters & Symbols (Sq. Ft) | | |
| PAVE | | Location | SINTOL | IOIALS |

ILLINOIS DEPARTMENT OF LABOR

PREVAILING WAGES FOR VARIOUS COUNTIES EFFECTIVE APRIL 2007

The Prevailing rates of wages are included in the Contract proposals which are subject to Check Sheet #5 of the Supplemental Specifications and Recurring Special Provisions. The rates have been ascertained and certified by the Illinois Department of Labor for the locality in which the work is to be performed and for each craft or type of work or mechanic needed to execute the work of the Contract. As required by Prevailing Wage Act (820 ILCS 130/0.01, et seq.) and Check Sheet #5 of the Contract, not less than the rates of wages ascertained by the Illinois Department of Labor and as revised during the performance of a Contract shall be paid to all laborers, workers and mechanics performing work under the Contract. Post the scale of wages in a prominent and easily accessible place at the site of work.

If the Illinois Department of Labor revises the prevailing rates of wages to be paid as listed in the specification of rates, the contractor shall post the revised rates of wages and shall pay not less than the revised rates of wages. Current wage rate information shall be obtained by visiting the Illinois Department of Labor web site at http://www.state.il.us/agency/idol/ or by calling 312-793-2814. It is the responsibility of the contractor to review the rates applicable to the work of the contract at regular intervals in order to insure the timely payment of current rates. Provision of this information to the contractor by means of the Illinois Department of Labor web site satisfies the notification of revisions by the Department to the contractor pursuant to the Act, and the contractor agrees that no additional notice is required. The contractor shall notify each of its subcontractors of the revised rates of wages.

Cook County Prevailing Wage for May 2007

| Trade Name | | | - | Base | FRMAN *M-F> | - | _ | | , | Pensn | Vac | Trng |
|---------------------------------------|----|------------|--------|------------------|---|---|-----|-----|----------------|----------------|-------|-------|
| AGDEGEOG ADE GEN | == | | = | | ======================================= | | == | | 7 460 | | _==== | 0.170 |
| ASBESTOS ABT-GEN ASBESTOS ABT-MEC | | ALL BLD | | 31.550 | 32.300 1.5 24.800 1.5 | | .5 | 2.0 | 7.460 7.860 | 4.840 4.910 | 0.000 | 0.170 |
| BOILERMAKER | | BLD | | | 42.000 2.0 | | .0 | 2.0 | 6.720 | 7.440 | 0.000 | 0.300 |
| BRICK MASON | | BLD | | 34.850 | 38.340 1.5 | | . 5 | 2.0 | 7.050 | 7.870 | 0.000 | 0.380 |
| CARPENTER | | ALL | | 36.520 | 38.520 1.5 | | . 5 | 2.0 | 7.960 | 5.910 | 0.000 | |
| CEMENT MASON | | ALL | | | 40.200 2.0 | | . 5 | | 6.790 | 5.620 | 0.000 | 0.170 |
| CERAMIC TILE FNSHER | | BLD | | 28.520 | 0.000 2.0 | 1 | . 5 | 2.0 | 5.650 | 5.750 | 0.000 | 0.330 |
| COMM. ELECT. | | BLD | | 32.440 | 34.940 1.5 | 1 | . 5 | 2.0 | 6.930 | 5.320 | 0.000 | 0.700 |
| ELECTRIC PWR EQMT OP | | ALL | | 36.050 | 42.000 1.5 | 1 | . 5 | 2.0 | 7.870 | 9.730 | 0.000 | 0.270 |
| ELECTRIC PWR GRNDMAN | | ALL | | 28.120 | 42.000 1.5 | 1 | . 5 | 2.0 | 6.140 | 7.600 | 0.000 | 0.210 |
| ELECTRIC PWR LINEMAN | | ALL | | | 42.000 1.5 | | . 5 | | 7.870 | 9.730 | 0.000 | 0.270 |
| ELECTRICIAN | | ALL | | | | | . 5 | 2.0 | 9.530 | 7.250 | 0.000 | 0.750 |
| ELEVATOR CONSTRUCTOR | | BLD | | 42.045 | | | . 0 | 2.0 | 8.275 | 6.060 | 2.520 | 0.550 |
| FENCE ERECTOR | | ALL | | | 28.640 1.5 | | . 5 | 2.0 | 7.500 | 7.590 | 0.000 | 0.250 |
| GLAZIER | | BLD | | | | | .0 | 2.0 | 6.490 | 9.050 | 0.000 | 0.500 |
| HT/FROST INSULATOR IRON WORKER | | BLD ALL | | 33.300 38.250 | 35.050 1.5 40.250 2.0 | | .5 | 2.0 | 7.860 9.470 | 11.27 | 0.000 | 0.310 |
| LABORER | | ALL | | 31.550 | 32.300 1.5 | | .5 | 2.0 | | 4.840 | 0.000 | 0.300 |
| LATHER | | BLD | | | 38.520 1.5 | | .5 | | 7.460 | | 0.000 | 0.170 |
| MACHINIST | | BLD | | | | | .0 | | 4.380 | 5.650 | 2.550 | 0.000 |
| MARBLE FINISHERS | | ALL | | 25.750 | 0.000 1.5 | | . 5 | 2.0 | 6.070 | 7.020 | 0.000 | 0.580 |
| MARBLE MASON | | BLD | | 34.850 | 38.340 1.5 | 1 | . 5 | 2.0 | 7.050 | 7.870 | 0.000 | 0.490 |
| MATERIAL TESTER 1 | | ALL | | 21.550 | 0.000 1.5 | 1 | . 5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| MATERIALS TESTER II | | ALL | | 26.550 | 0.000 1.5 | 1 | . 5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| MILLWRIGHT | | ALL | | 36.520 | 38.520 1.5 | 1 | . 5 | | 7.960 | 5.910 | 0.000 | 0.490 |
| OPERATING ENGINEER | | BLD | 1 | 41.550 | 45.550 2.0 | 2 | . 0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD | 2 | 40.250 | 45.550 2.0 | 2 | . 0 | 2.0 | | 5.600 | | 0.700 |
| OPERATING ENGINEER | | | 3 | 37.700 | 45.550 2.0 | | . 0 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | | 4 | 35.950 | 45.550 2.0 | | . 0 | | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | | 1 | 47.250 | 47.250 1.5 | | . 5 | | 6.850 | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER | | | 2 | 45.750 | 47.250 1.5 | | . 5 | 2.0 | | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER OPERATING ENGINEER | | | 3 4 | 40.700 33.850 | 47.250 1.5 47.250 1.5 | | .5 | 2.0 | 6.850 6.850 | 5.600 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER OPERATING ENGINEER | | HWY | | | 43.750 1.5 | | .5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER OPERATING ENGINEER | | | | 39.200 | 43.750 1.5 | | .5 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | HWY | | | 43.750 1.5 | | . 5 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | | | | 43.750 1.5 | | | | | 5.600 | | |
| OPERATING ENGINEER | | | | | 43.750 1.5 | 1 | . 5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| ORNAMNTL IRON WORKER | | ALL | | | 37.600 2.0 | | | | | 10.84 | | |
| PAINTER | | ALL | | 34.400 | 38.700 1.5 | 1 | . 5 | 1.5 | 6.200 | 6.400 | 0.000 | 0.390 |
| PAINTER SIGNS | | BLD | | 28.970 | 32.520 1.5 | 1 | . 5 | 1.5 | 2.600 | 2.310 | 0.000 | 0.000 |
| PILEDRIVER | | ALL | | 36.520 | 38.520 1.5 | | | | | 5.910 | | |
| PIPEFITTER | | BLD | | | 39.600 1.5 | | | | | 6.900 | | |
| PLASTERER | | BLD | | | 35.350 1.5 | | | | | 7.100 | | |
| PLUMBER | | BLD | | | 41.700 1.5 | | | | | 4.560 | | |
| ROOFER | | BLD | | | 35.650 1.5 | | | | | 3.310 | | |
| SHEETMETAL WORKER | | BLD | | | 36.070 1.5 | | | | | 7.850 | | |
| SIGN HANGER | | BLD | | | 26.190 1.5 | | | | | 2.250 | | |
| SPRINKLER FITTER STEEL ERECTOR | | BLD ALL | | | 40.500 1.5 37.750 2.0 | | | | | 6.100 10.77 | | |
| STONE MASON | | BLD | | | 36.580 1.5 | | | | | 7.020 | | |
| TERRAZZO FINISHER | | BLD | | 29.290 | | | | | | 6.940 | | |
| TERRAZZO MASON | | BLD | | | 36.650 1.5 | | | | | 8.610 | | |
| TILE MASON | | BLD | | | 38.600 2.0 | | | | | 7.000 | | |
| TRAFFIC SAFETY WRKR | | HWY | | | 24.400 1.5 | | | | | 1.875 | | |
| TRUCK DRIVER | E | | 1 | | 29.800 1.5 | | | | | 4.300 | | |
| TRUCK DRIVER | E | ALL | 2 | 29.400 | 29.800 1.5 | 1 | . 5 | 2.0 | 5.650 | 4.300 | 0.000 | 0.000 |
| TRUCK DRIVER | E | ALL | 3 | 29.600 | 29.800 1.5 | 1 | . 5 | 2.0 | 5.650 | 4.300 | 0.000 | 0.000 |

| TRUCK DRIVER | E | ALL 4 | 29.800 | 29.800 | 1.5 | 1.5 | 2.0 | 5.650 | 4.300 | 0.000 | 0.000 |
|--------------|---|-------|--------|--------|-----|-----|-----|-------|-------|-------|-------|
| TRUCK DRIVER | W | ALL 1 | 29.700 | 30.250 | 1.5 | 1.5 | 2.0 | 6.500 | 3.400 | 0.000 | 0.000 |
| TRUCK DRIVER | W | ALL 2 | 29.850 | 30.250 | 1.5 | 1.5 | 2.0 | 6.500 | 3.400 | 0.000 | 0.000 |
| TRUCK DRIVER | W | ALL 3 | 30.050 | 30.250 | 1.5 | 1.5 | 2.0 | 6.500 | 3.400 | 0.000 | 0.000 |
| TRUCK DRIVER | W | ALL 4 | 30.250 | 30.250 | 1.5 | 1.5 | 2.0 | 6.500 | 3.400 | 0.000 | 0.000 |
| TUCKPOINTER | | BLD | 34.500 | 35.500 | 1.5 | 1.5 | 2.0 | 4.710 | 6.340 | 0.000 | 0.400 |

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSA (Overtime is required for every hour worked on Saturday)

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

Explanations

COOK COUNTY

TRUCK DRIVERS (WEST) - That part of the county West of Barrington Road.

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial/Decoration Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, Christmas Day. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration such as the day after Thanksgiving for Veterans Day. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in

tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATIONS ELECTRICIAN - Installation, operation, inspection, maintenance, repair and service of radio, television, recording, voice sound vision production and reproduction, telephone and telephone interconnect, facsimile, data apparatus, coaxial, fibre optic and wireless equipment, appliances and systems used for the transmission and reception of signals of any nature, business, domestic, commercial, education, entertainment, and residential purposes, including but not limited to, communication and telephone, electronic and sound equipment, fibre optic and data communication systems, and the performance of any task directly related to such installation or service whether at new or existing sites, such tasks to include the placing of wire and cable and electrical power conduit or other raceway work within the equipment room and pulling wire and/or cable through conduit and the installation of any incidental conduit, such that the employees covered hereby can complete any job in full.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all mateiral that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installatin of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and experiors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior

and experior which sare installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

OPERATING ENGINEERS - BUILDING

Class 1. Mechanic; Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson attachment; Batch Plant; Benoto; Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, one, two and three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes; Squeeze Cretes-screw Type Pumps; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-form Paver; Straddle Buggies; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Greaser Engineer; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, inside Freight Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill self-propelled); Rock Drill (truck mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination - Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators - (Rheostat Manual Controlled); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 small Electric Drill Winches; Bobcat (up to and including 3/4 cu. yd.).

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

- Class 1. Craft foreman (Master Mechanic), diver/wet tender, engineer (hydraulic dredge).
- Class 2. Crane/backhoe operator, mechanic/welder, assistant engineer (hydraulic dredge), leverman (hydraulic dredge), and diver tender.
- Class 3. Deck equipment operator (machineryman), maintenance of crane (over 50 ton capacity) or backhoe (96,000 pounds or more), tug/launch operator, loader, dozer and like equipment on barge, breakwater wall, slip/dock or scow, deck machinery, etc.
- Class 4. Deck equipment operator machineryman/fireman), (4 equipment units or more) and crane maintenance 50 ton capacity and under or backhoe weighing 96,000 pounds or less, assistant tug operator.

OPERATING ENGINEERS - HEAVY AND HIGHWAY CONSTRUCTION Class 1. Craft Foreman; Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted): Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Hammerhead, Linden, Peco & Machines of a like nature; Crete Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dowell machine with Air Compressor; Dredges; Field Mechanic-Welder; Formless Curb and Gutter Machine; Gradall and Machines of a like nature; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Mounted; Hoists, One, Two and Three Drum; Hydraulic Backhoes; Backhoes with shear attachments; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Roto Mill Grinder; Slip-Form Paver; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Trenching Machine; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole; Drills (Tunnel Shaft); Underground Boring and/or Mining Machines; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine -Concrete; Greaser Engineer; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; All Locomotives, Dinky; Pump Cretes; Squeeze Cretes-Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotory Snow Plows; Rototiller, Seaman, etc., self-propelled; Scoops -Tractor Drawn; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper; Scraper - Prime Mover in Tandem (Regardless of Size); Tank Car Heater; Tractors, Push, Pulling Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

- Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Fireman on Boilers; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper Form-Motor Driven.
- Class 4. Air Compressor; Combination Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Hydro-Blaster; Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Tractaire; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.
- Class 5. Bobcats (all); Brick Forklifts, Oilers.

TRAFFIC SAFETY

Work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION - EAST & WEST

- Class 1. Two or three Axle Trucks. A-frame Truck when used for transportation purposes; Air Compressors and Welding Machines, including those pulled by cars, pick-up trucks and tractors; Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics Helpers and Greasers; Oil Distributors 2-man operation; Pavement Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors; Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man operation; Slurry Truck Conveyor Operation, 2 or 3 man; TEamsters Unskilled dumpman; and Truck Drivers hauling warning lights, barricades, and portable toilets on the job site.
- Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.
- Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.
- Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 618/993-7271 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

Du Page County Prevailing Wage for May 2007

| Trade Name | | TYP (| | Base | FRMAN * | | | | • | Pensn | Vac | Trng |
|---|--------|--------------|---|------------------|------------------|------------|------------|-----|----------------|----------------|-------|-------|
| ASBESTOS ABT-GEN | == | === = ALL | = | 31.550 | 32.300 | 1.5 | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| ASBESTOS ABT-MEC | | BLD | | | | 1.5 | 1.5 | | | 4.910 | 0.000 | 0.000 |
| BOILERMAKER | | BLD | | | | 2.0 | 2.0 | 2.0 | 6.720 | 7.440 | 0.000 | 0.300 |
| BRICK MASON | | BLD | | 34.850 | | 1.5 | 1.5 | 2.0 | 7.050 | 7.870 | 0.000 | 0.380 |
| CARPENTER | | ALL | | 36.520 | 38.520 | 1.5 | 1.5 | 2.0 | 7.960 | 5.910 | 0.000 | 0.490 |
| CEMENT MASON | | ALL | | 33.650 | 35.650 | 2.0 | 1.5 | 2.0 | 6.550 | 10.45 | 0.000 | 0.180 |
| CERAMIC TILE FNSHER | | BLD | | 28.520 | | 2.0 | 1.5 | 2.0 | 5.650 | 5.750 | 0.000 | 0.330 |
| COMMUNICATION TECH | | BLD | | 29.200 | | 1.5 | 1.5 | 2.0 | 7.000 | 9.790 | 0.000 | 0.440 |
| ELECTRIC PWR EQMT OP | | ALL | | 27.920 | | 1.5 | 1.5 | 2.0 | | 7.820 | 0.000 | 0.210 |
| ELECTRIC PWR GRNDMAN ELECTRIC PWR LINEMAN | | ALL ALL | | 21.640 33.220 | | 1.5 1.5 | 1.5 | 2.0 | 4.750 4.750 | 6.060 9.310 | 0.000 | 0.160 |
| ELECTRIC PWR TRK DRV | | ALL | | | | 1.5 | 1.5 | 2.0 | 4.750 | 6.260 | 0.000 | 0.230 |
| ELECTRICIAN | | BLD | | 32.750 | | 1.5 | 1.5 | 2.0 | | 12.15 | 3.600 | 0.490 |
| ELEVATOR CONSTRUCTOR | | BLD | | 42.045 | 47.300 | 2.0 | 2.0 | 2.0 | 8.275 | 6.060 | 2.520 | 0.550 |
| FENCE ERECTOR | NE | ALL | | 27.140 | 28.640 | 1.5 | 1.5 | 2.0 | 7.500 | 7.590 | 0.000 | 0.250 |
| FENCE ERECTOR | W | ALL | | | | 2.0 | 2.0 | 2.0 | 7.690 | 13.11 | | 0.230 |
| GLAZIER | | BLD | | 31.400 | | 1.5 | 2.0 | 2.0 | 6.490 | 9.050 | 0.000 | 0.500 |
| HT/FROST INSULATOR | _ | BLD | | 33.300 | | 1.5 | 1.5 | 2.0 | | 8.610 | 0.000 | 0.310 |
| IRON WORKER IRON WORKER | E W | ALL ALL | | 38.250 34.100 | | 2.0 | 2.0 | 2.0 | 9.470 7.690 | 13.11 | 0.000 | 0.300 |
| LABORER | VV | ALL | | | | 1.5 | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.230 |
| LATHER | | BLD | | 36.520 | | 1.5 | 1.5 | 2.0 | | 5.910 | 0.000 | 0.490 |
| MACHINIST | | BLD | | 36.890 | | 2.0 | 2.0 | 2.0 | 4.380 | 5.650 | 2.550 | 0.000 |
| MARBLE FINISHERS | | ALL | | 25.750 | 0.000 | 1.5 | 1.5 | 2.0 | 6.070 | 7.020 | 0.000 | 0.580 |
| MARBLE MASON | | BLD | | | | 1.5 | 1.5 | | 7.050 | 7.870 | 0.000 | 0.490 |
| MATERIAL TESTER 1 | | ALL | | 21.550 | | 1.5 | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| MATERIALS TESTER II MILLWRIGHT | | ALL ALL | | 26.550 36.520 | | 1.5 1.5 | 1.5 | 2.0 | 7.460 7.960 | 4.840 5.910 | 0.000 | 0.170 |
| OPERATING ENGINEER | | BLD 1 | ı | 41.550 | | 2.0 | 2.0 | | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD 2 | _ | 40.250 | | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD 3 | 3 | 37.700 | 45.550 | 2.0 | 2.0 | 2.0 | | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD 4 | | 35.950 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | HWY 1 | | 39.750 | | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | HWY 2 | | | | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER OPERATING ENGINEER | | HWY 3 | 3 | 37.150 35.750 | | 1.5 1.5 | 1.5 1.5 | 2.0 | 6.850 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | HWY 5 | | | | 1.5 | | | | 5.600 | | |
| ORNAMNTL IRON WORKER | E | ALL | | | 37.600 | | | | | 10.84 | | |
| ORNAMNTL IRON WORKER | | ALL | | | 35.810 | | | | | 13.11 | | |
| PAINTER | | ALL | | 35.330 | 36.330 | 1.5 | 1.5 | 1.5 | 6.400 | 6.500 | 0.000 | 0.500 |
| PAINTER SIGNS | | BLD | | | 32.520 | | | | | 2.310 | | |
| PILEDRIVER | | ALL | | | 38.520 | | | | | 5.910 | | |
| PIPEFITTER | | BLD | | | 38.010 | | | | | 8.690 | | |
| PLASTERER PLUMBER | | BLD BLD | | | 33.500 38.010 | | | | | 6.770 8.690 | | |
| ROOFER | | BLD | | | 35.650 | | | | | 3.310 | | |
| SHEETMETAL WORKER | | BLD | | | 38.510 | | | | | 8.020 | | |
| SPRINKLER FITTER | | BLD | | | 40.500 | | | | | 6.100 | | |
| STEEL ERECTOR | E | ALL | | 36.250 | 37.750 | 2.0 | 2.0 | 2.0 | 8.970 | 10.77 | 0.000 | 0.300 |
| STEEL ERECTOR | W | ALL | | | 35.810 | | | | | 13.11 | | |
| STONE MASON | | BLD | | | 36.580 | | | | | 7.020 | | |
| TERRAZZO FINISHER TERRAZZO MASON | | BLD BLD | | 29.290 | 0.000 36.650 | | | | | 6.940 8.610 | | |
| TILE MASON | | BLD | | | 38.600 | | | | | 7.000 | | |
| TRAFFIC SAFETY WRKR | | HWY | | | 24.400 | | | | | 1.875 | | |
| TRUCK DRIVER | | | L | | 30.250 | | | | | 3.450 | | |
| TRUCK DRIVER | | | | | 30.250 | | | | | 3.450 | | |
| TRUCK DRIVER | | ALL 3 | 3 | 30.050 | 30.250 | 1.5 | 1.5 | 2.0 | 6.500 | 3.450 | 0.000 | 0.000 |

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSA (Overtime is required for every hour worked on Saturday)

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

Explanations

DUPAGE COUNTY

IRON WORKERS AND FENCE ERECTOR (WEST) - West of Route 53.

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial/Decoration Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, Christmas Day. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration such as the day after Thanksgiving for Veterans Day. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

TRAFFIC SAFETY - work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in

tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATIONS TECHNICIAN

Low voltage installation, maintenance and removal of telecommunication facilities (voice, sound, data and video) including telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated system digital network), pulling of wire in raceways, but not the installation of raceways.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all mateiral that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installatin of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and experiors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and experior which sare installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel,

fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION
Class 1. Two or three Axle Trucks. A-frame Truck when used for
transportation purposes; Air Compressors and Welding Machines,
including those pulled by cars, pick-up trucks and tractors;
Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck
Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics
Helpers and Greasers; Oil Distributors 2-man operation; Pavement
Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors;
Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man
operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters
Unskilled dumpman; and Truck Drivers hauling warning lights,
barricades, and portable toilets on the job site.

- Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yeards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.
- Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.
- Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

OPERATING ENGINEERS - BUILDING

Class 1. Mechanic; Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson attachment; Batch Plant; Benoto; Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, one, two and three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes; Squeeze Cretes-screw Type Pumps; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-form Paver; Straddle Buggies; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Fortlist Trucks; Greaser Engineer; Highlift Shovels or Front Endloaders under 2-1/4

yd.; Hoists, Automatic; Hoists, inside Freight Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (self-propelled); Rock Drill (truck mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination - Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators - (Rheostat Manual Controlled); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 small Electric Drill Winches; Bobcat (up to and including 3/4 cu.yd.).

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

OPERATING ENGINEERS - HEAVY AND HIGHWAY CONSTRUCTION Class 1. Craft Foreman; Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted): Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Hammerhead, Linden, Peco & Machines of a like nature; Crete Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dowell machine with Air Compressor; Dredges; Field Mechanic-Welder; Formless Curb and Gutter Machine; Gradall and Machines of a like nature; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Mounted; Hoists, One, Two and Three Drum; Hydraulic Backhoes; Backhoes with shear attachments; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Roto Mill Grinder; Slip-Form Paver; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Trenching Machine; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole; Drills (Tunnel Shaft); Underground Boring and/or Mining Machines; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine -Concrete; Greaser Engineer; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; All Locomotives, Dinky; Pump Cretes; Squeeze Cretes-Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotory Snow Plows; Rototiller, Seaman, etc., self-propelled; Scoops - Tractor Drawn; Self-Propelled Compactor; Spreader - Chip -Stone, etc.; Scraper; Scraper - Prime Mover in Tandem (Regardless of Size); Tank Car Heater; Tractors, Push, Pulling Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Fireman on Boilers; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper - Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Hydro-Blaster; Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Tractaire; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. Bobcats (all); Brick Forklifts, Oilers.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 618/993-7271 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

Kane County Prevailing Wage for May 2007

| Trade Name | | TYP (| | | FRMAN *M-F>8 | | | • | Pensn | Vac | Trng |
|---------------------------------------|---|-------|---|--------|--------------------------|-----|-----|-------|----------------|-------|-------|
| ASBESTOS ABT-GEN | | ALL | - | | 32.300 1.5 | 1.5 | | | 4.840 | 0.000 | 0.170 |
| ASBESTOS ABT-MEC | | BLD | | | 24.800 1.5 | | | | 4.910 | | |
| BOILERMAKER | | BLD | | | 42.000 2.0 | 2.0 | | | 7.440 | | |
| BRICK MASON | | BLD | | | 38.340 1.5 | 1.5 | | | 7.870 | | |
| CARPENTER | | ALL | | | 37.320 1.5 | | | | 5.320 | | |
| CEMENT MASON | | ALL | | | 37.300 2.0 | | | | 8.910 | | |
| CERAMIC TILE FNSHER | | BLD | | 28.520 | 0.000 2.0 | | | | 5.750 | | |
| COMMUNICATION TECH | N | BLD | | 29.960 | 31.760 1.5 | 1.5 | | | 6.290 | | |
| COMMUNICATION TECH | S | BLD | | 32.120 | 34.220 1.5 | 1.5 | 2.0 | 8.490 | 7.390 | 0.000 | 0.640 |
| ELECTRIC PWR EQMT OP | | ALL | | 27.920 | 35.880 1.5 | 1.5 | 2.0 | 4.750 | 7.820 | 0.000 | 0.210 |
| ELECTRIC PWR GRNDMAN | | ALL | | 21.640 | 35.880 1.5 | 1.5 | 2.0 | 4.750 | 6.060 | 0.000 | 0.160 |
| ELECTRIC PWR LINEMAN | | ALL | | 33.220 | 35.880 1.5 | 1.5 | 2.0 | 4.750 | 9.310 | 0.000 | 0.250 |
| ELECTRIC PWR TRK DRV | | ALL | | 22.340 | 35.880 1.5 | 1.5 | | | 6.260 | | |
| ELECTRICIAN | N | ALL | | 38.910 | 42.800 1.5 | 1.5 | 2.0 | 9.140 | 8.940 | 0.000 | 0.480 |
| ELECTRICIAN | S | BLD | | 38.570 | 42.430 1.5 | 1.5 | | | 9.650 | | |
| ELEVATOR CONSTRUCTOR | | BLD | | | 47.300 2.0 | 2.0 | | | 6.060 | | |
| FENCE ERECTOR | | ALL | | | 35.810 2.0 | 2.0 | | | 13.11 | | 0.230 |
| GLAZIER | | BLD | | | 32.400 1.5 | 2.0 | | | 9.050 | | 0.500 |
| HT/FROST INSULATOR | | BLD | | | 35.050 1.5 | 1.5 | | | 8.610 | | |
| IRON WORKER | | ALL | | | 35.810 2.0 | 2.0 | | | 13.11 | | |
| LABORER | | ALL | | | 32.300 1.5 | 1.5 | | | 5.100 | | |
| LATHER | | BLD | | | 37.320 1.5 | 1.5 | | | 5.320 | | |
| MACHINIST | | BLD | | | 38.890 2.0 | 2.0 | | | 5.650 | | |
| MARBLE FINISHERS | | ALL | | 25.750 | 0.000 1.5 | 1.5 | | | 7.020 | | |
| MARBLE MASON | | BLD | | | 38.340 1.5 | 1.5 | | | 7.870 | | |
| MATERIAL TESTER 1 | | ALL | | 21.550 | 0.000 1.5 | 1.5 | | | 4.840 | | |
| MATERIALS TESTER II | | ALL | | 26.550 | 0.000 1.5 | 1.5 | 2.0 | | 4.840 | | 0.170 |
| MILLWRIGHT | | ALL | | | 37.320 1.5 45.550 2.0 | 1.5 | | | 5.320 5.600 | 0.000 | 0.490 |
| OPERATING ENGINEER OPERATING ENGINEER | | | | | 45.550 2.0 | 2.0 | | | 5.600 | | 0.700 |
| OPERATING ENGINEER OPERATING ENGINEER | | BLD 3 | | | 45.550 2.0 | 2.0 | | | 5.600 | | 0.700 |
| OPERATING ENGINEER | | | | | 45.550 2.0 | 2.0 | | | 5.600 | | |
| OPERATING ENGINEER | | | | | 43.750 1.5 | 1.5 | 2.0 | | 5.600 | | 0.700 |
| OPERATING ENGINEER | | | | | 43.750 1.5 | | | | 5.600 | | |
| OPERATING ENGINEER | | | | | 43.750 1.5 | 1.5 | | | 5.600 | | |
| OPERATING ENGINEER | | | | | 43.750 1.5 | 1.5 | | | 5.600 | | 0.700 |
| OPERATING ENGINEER | | | | | 43.750 1.5 | 1.5 | | | 5.600 | | 0.700 |
| ORNAMNTL IRON WORKER | | ALL | | 34.100 | 35.810 2.0 | | | | 13.11 | | |
| PAINTER | | ALL | | | 36.330 1.5 | | | | 6.500 | | |
| PAINTER SIGNS | | BLD | | 28.970 | 32.520 1.5 | | | | 2.310 | | |
| PILEDRIVER | | ALL | | 35.320 | 37.320 1.5 | 1.5 | 2.0 | 6.760 | 5.320 | 0.000 | 0.490 |
| PIPEFITTER | | BLD | | 36.010 | 38.010 1.5 | 1.5 | 2.0 | 8.450 | 8.690 | 0.000 | 0.950 |
| PLASTERER | | BLD | | 33.850 | 35.350 1.5 | 1.5 | 2.0 | 6.740 | 7.100 | 0.000 | 0.400 |
| PLUMBER | | BLD | | 36.010 | 38.010 1.5 | 1.5 | 2.0 | 8.450 | 8.690 | 0.000 | 0.950 |
| ROOFER | | BLD | | | 35.650 1.5 | | | | 3.310 | | |
| SHEETMETAL WORKER | | BLD | | | 38.510 1.5 | | | | 8.020 | | |
| SIGN HANGER | | BLD | | | 27.570 1.5 | | | | 3.550 | | |
| SPRINKLER FITTER | | BLD | | | 40.500 1.5 | | | | 6.100 | | |
| STEEL ERECTOR | | ALL | | | 35.810 2.0 | | | | 13.11 | | |
| STONE MASON | | BLD | | | 36.580 1.5 | | | | 7.020 | | |
| TERRAZZO FINISHER | | BLD | | 29.290 | | | | | 6.940 | | |
| TERRAZZO MASON | | BLD | | | 36.650 1.5 | | | | 8.610 | | |
| TILE MASON | | BLD | | | 38.600 2.0 | | | | 7.000 | | |
| TRAFFIC SAFETY WRKR | | HWY | | | 24.400 1.5 | | | | 1.875 | | |
| TRUCK DRIVER TRUCK DRIVER | | | | | 30.250 1.5 30.250 1.5 | | | | 3.450 3.450 | | |
| TRUCK DRIVER | | | | | 30.250 1.5 | | | | 3.450 | | |
| TRUCK DRIVER | | | | | 30.250 1.5 | | | | 3.450 | | |
| INOCK DIVIVER | | , nn | _ | 50.250 | JU.4JU 1.J | 1.5 | ۷.∪ | 0.500 | J. IJU | 0.000 | 0.000 |

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSA (Overtime is required for every hour worked on Saturday)

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

Explanations

KANE COUNTY

ELECTRICIANS AND COMMUNICATIONS TECHNICIAN (NORTH) - Townships of Burlington, Campton, Dundee, Elgin, Hampshire, Plato, Rutland, St. Charles (except the West half of Sec. 26, all of Secs. 27, 33, and 34, South half of Sec. 28, West half of Sec. 35), Virgil and Valley View CCC and Elgin Mental Health Center.

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial/Decoration Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, Christmas Day. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration such as the day after Thanksgiving for Veterans Day. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass,

tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

mosaics, fiberglass, and all substitute materials, for tile made in

COMMUNICATIONS TECHNICIAN

Construction, installation, maintenance and removal of telecommunication facilities (voice, sound, data and video), telephone, security systems, fire alarm systems that are a component of a multiplex system and share a common cable, and data inside wire, interconnect, terminal equipment, central offices, PABX and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area network), LAN (local area networks), and ISDN (integrated system digital network), pulling of wire in raceways, but not the installation of raceways.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all mateiral that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installatin of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and experiors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and experior which sare installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials;

field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

TRAFFIC SAFETY - work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION
Class 1. Two or three Axle Trucks. A-frame Truck when used for
transportation purposes; Air Compressors and Welding Machines,
including those pulled by cars, pick-up trucks and tractors;
Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck
Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics
Helpers and Greasers; Oil Distributors 2-man operation; Pavement
Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors;
Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man
operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters;
Unskilled dumpman; and Truck Drivers hauling warning lights,
barricades, and portable toilets on the job site.

- Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yeards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.
- Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.
- Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

OPERATING ENGINEERS - BUILDING

Class 1. Mechanic; Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson attachment; Batch Plant; Benoto; Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, one, two and three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes; Squeeze Cretes-screw Type Pumps; Raised and Blind

Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-form Paver; Straddle Buggies; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Greaser Engineer; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, inside Freight Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (self-propelled); Rock Drill (truck mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination - Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators - (Rheostat Manual Controlled); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 small Electric Drill Winches; Bobcat (up to and including 3/4 cu.yd.).

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

OPERATING ENGINEERS - HEAVY AND HIGHWAY CONSTRUCTION Class 1. Craft Foreman; Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted): Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Hammerhead, Linden, Peco & Machines of a like nature; Crete Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dowell machine with Air Compressor; Dredges; Field Mechanic-Welder; Formless Curb and Gutter Machine; Gradall and Machines of a like nature; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Mounted; Hoists, One, Two and Three Drum; Hydraulic Backhoes; Backhoes with shear attachments; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Roto Mill Grinder; Slip-Form Paver; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Trenching Machine; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole; Drills (Tunnel Shaft); Underground Boring and/or Mining Machines; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Greaser Engineer; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All

Attachments); Hydro-Blaster; All Locomotives, Dinky; Pump Cretes; Squeeze Cretes-Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotory Snow Plows; Rototiller, Seaman, etc., self-propelled; Scoops - Tractor Drawn; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper; Scraper - Prime Mover in Tandem (Regardless of Size); Tank Car Heater; Tractors, Push, Pulling Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Fireman on Boilers; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper - Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Hydro-Blaster; Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Tractaire; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. Bobcats (all); Brick Forklifts; Oilers.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 618/993-7271 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

Lake County Prevailing Wage for May 2007

| Trade Name | | | С | Base | FRMAN * | | | | • | Pensn | Vac | Trng |
|---------------------------------------|----|------------|--------|------------------|------------------|-----|------------|-----|----------------|----------------|-------|-------|
| AGDEGEOG ADE GEN | == | | = | | ===== | | === 1 F | === | | 4 040 | | 0 170 |
| ASBESTOS ABT-GEN ASBESTOS ABT-MEC | | ALL | | 31.550 | 32.300 24.800 | 1.5 | 1.5 1.5 | 2.0 | 7.460 | 4.840 4.910 | 0.000 | 0.170 |
| BOILERMAKER | | BLD BLD | | | | 2.0 | 2.0 | 2.0 | 6.720 | 7.440 | 0.000 | 0.300 |
| BRICK MASON | | BLD | | 34.850 | | 1.5 | 1.5 | 2.0 | 7.050 | 7.440 | 0.000 | 0.380 |
| CARPENTER | | ALL | | 36.520 | | 1.5 | 1.5 | 2.0 | 7.960 | 5.910 | 0.000 | 0.490 |
| CEMENT MASON | | ALL | | 33.490 | | 2.0 | 1.5 | 2.0 | | 8.800 | 0.000 | 0.100 |
| CERAMIC TILE FNSHER | | BLD | | 28.520 | | 2.0 | 1.5 | 2.0 | 5.650 | 5.750 | 0.000 | 0.330 |
| COMMUNICATION TECH | | BLD | | 29.390 | | 1.5 | 1.5 | 2.0 | 7.990 | 7.350 | | 0.430 |
| ELECTRIC PWR EOMT OP | | ALL | | 27.920 | | 1.5 | 1.5 | 2.0 | 4.750 | 7.820 | 0.000 | 0.210 |
| ELECTRIC PWR GRNDMAN | | ALL | | 21.640 | 35.880 | 1.5 | 1.5 | 2.0 | 4.750 | 6.060 | 0.000 | 0.160 |
| ELECTRIC PWR LINEMAN | | ALL | | 33.220 | 35.880 | 1.5 | 1.5 | 2.0 | 4.750 | 9.310 | 0.000 | 0.250 |
| ELECTRIC PWR TRK DRV | | ALL | | 22.340 | 35.880 | 1.5 | 1.5 | 2.0 | 4.750 | 6.260 | 0.000 | 0.170 |
| ELECTRICIAN | | BLD | | 34.020 | 37.420 | 1.5 | 1.5 | 2.0 | 8.510 | 9.520 | 1.700 | 0.480 |
| ELEVATOR CONSTRUCTOR | | BLD | | 42.045 | | 2.0 | 2.0 | 2.0 | 8.275 | 6.060 | 2.520 | 0.550 |
| FENCE ERECTOR | | ALL | | 27.140 | | 1.5 | 1.5 | 2.0 | 7.500 | 7.590 | 0.000 | 0.250 |
| GLAZIER | | BLD | | 31.400 | | 1.5 | 2.0 | 2.0 | 6.490 | 9.050 | 0.000 | 0.500 |
| HT/FROST INSULATOR | | BLD | | 33.300 | | 1.5 | 1.5 | 2.0 | | 8.610 | 0.000 | 0.310 |
| IRON WORKER | | ALL | | 38.250 | | 2.0 | 2.0 | 2.0 | 9.470 | 11.27 | | 0.300 |
| LABORER LATHER | | ALL | | 31.550 36.520 | | 1.5 | 1.5 1.5 | 2.0 | 7.460 7.960 | 4.840 5.910 | 0.000 | 0.170 |
| MACHINIST | | BLD BLD | | | | 2.0 | 2.0 | 2.0 | 4.380 | 5.650 | 2.550 | 0.490 |
| MARBLE FINISHERS | | ALL | | 25.750 | | 1.5 | 1.5 | 2.0 | | 7.020 | 0.000 | 0.580 |
| MARBLE MASON | | BLD | | 34.850 | | 1.5 | 1.5 | 2.0 | 7.050 | 7.870 | 0.000 | |
| MATERIAL TESTER 1 | | ALL | | 21.550 | | 1.5 | 1.5 | 2.0 | | 4.840 | 0.000 | 0.170 |
| MATERIALS TESTER II | | ALL | | 26.550 | 0.000 | 1.5 | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| MILLWRIGHT | | ALL | | 36.520 | 38.520 | 1.5 | 1.5 | 2.0 | 7.960 | 5.910 | 0.000 | 0.490 |
| OPERATING ENGINEER | | BLD | 1 | 41.550 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD | 2 | 40.250 | | 2.0 | 2.0 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD | 3 | 37.700 | | 2.0 | 2.0 | | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | BLD | 4 | 35.950 | | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | FLT | 1 | 47.250 | | 1.5 | 1.5 | 2.0 | | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER OPERATING ENGINEER | | FLT | 3 | 45.750 40.700 | | 1.5 | 1.5 1.5 | 2.0 | 6.850 6.850 | 5.600 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER OPERATING ENGINEER | | | ے 4 | 33.850 | | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER OPERATING ENGINEER | | HWY | 1 | | | 1.5 | 1.5 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | | | | | 1.5 | 1.5 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | | | | | 1.5 | 1.5 | 2.0 | | 5.600 | | 0.700 |
| OPERATING ENGINEER | | HWY | 4 | 35.750 | 43.750 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | | | | 43.750 | | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| ORNAMNTL IRON WORKER | | ALL | | 35.600 | 37.600 | 2.0 | 2.0 | 2.0 | 7.500 | 10.84 | 0.000 | 0.750 |
| PAINTER | | ALL | | | 38.700 | | | | | 6.400 | | |
| PAINTER SIGNS | | BLD | | | 32.520 | | | | | 2.310 | | |
| PILEDRIVER | | ALL | | | 38.520 | | | | | 5.910 | | |
| PIPEFITTER | | BLD | | | 39.600 | | | | | 6.900 | | |
| PLASTERER | | BLD | | | 32.700 | | | | | 8.590 | | |
| PLUMBER ROOFER | | BLD BLD | | | 39.500 35.650 | | | | | 6.850 3.310 | | |
| SHEETMETAL WORKER | | BLD | | | 36.070 | | | | | 7.850 | | |
| SIGN HANGER | | BLD | | | 26.190 | | | | | 2.250 | | |
| SPRINKLER FITTER | | BLD | | | 40.500 | | | | | 6.100 | | |
| STEEL ERECTOR | | ALL | | | 37.750 | | | | | 10.77 | | |
| STONE MASON | | BLD | | | 36.580 | | | | | 7.020 | | |
| TERRAZZO FINISHER | | BLD | | 29.290 | 0.000 | 1.5 | 1.5 | 2.0 | 5.650 | 6.940 | 0.000 | 0.270 |
| TERRAZZO MASON | | BLD | | | 36.650 | | | | | 8.610 | | |
| TILE MASON | | BLD | | | 38.600 | | | | | 7.000 | | |
| TRAFFIC SAFETY WRKR | | HWY | _ | | 24.400 | | | | | 1.875 | | |
| TRUCK DRIVER | | | | | 29.950 | | | | | 5.000 | | |
| TRUCK DRIVER | | АЬЬ | 2 | ∠9.550 | 29.950 | 1.5 | 1.5 | ∠.0 | 5.200 | 5.000 | 0.000 | 0.000 |

TRUCK DRIVER ALL 3 29.750 29.950 1.5 1.5 2.0 5.200 5.000 0.000 0.000 TRUCK DRIVER ALL 4 29.950 29.950 1.5 1.5 2.0 5.200 5.000 0.000 0.000 TUCKPOINTER BLD 34.500 35.500 1.5 1.5 2.0 4.710 6.340 0.000 0.400

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSA (Overtime is required for every hour worked on Saturday)

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

Explanations

LAKE COUNTY

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial/Decoration Day, Fourth of July, Day, Veterans Day, Thanksgiving Day, Christmas Day. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration such as the day after Thanksgiving for Veterans Day. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished

interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATION TECHNICIAN

Low voltage construction, installation, maintenance and removal of telecommunication facilities (voice, sound, data and video) including outside plant, telephone, security systems and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area network), LAN (local area networks), and ISDN (integrated system digital network), pulling of wire in raceways, but not the installation of raceways.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all mateiral that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installatin of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and experiors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and experior which sare installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

TRAFFIC SAFETY - work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION
Class 1. Two or three Axle Trucks. A-frame Truck when used for
transportation purposes; Air Compressors and Welding Machines,
including those pulled by cars, pick-up trucks and tractors;
Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck
Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics
Helpers and Greasers; Oil Distributors 2-man operation; Pavement
Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors;
Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man
operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters;
Unskilled dumpman; and Truck Drivers hauling warning lights,
barricades, and portable toilets on the job site.

- Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.
- Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.
- Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

OPERATING ENGINEERS - BUILDING

Class 1. Mechanic; Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson attachment; Batch Plant; Benoto; Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, one, two and three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes; Squeeze Cretes-screw Type Pumps; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-form Paver; Straddle Buggies; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Greaser Engineer; Highlift Shovels or Front Endloaders under 2-1/4

- yd.; Hoists, Automatic; Hoists, inside Freight Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (self-propelled); Rock Drill (truck mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.
- Class 3. Air Compressor; Combination Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators (Rheostat Manual Controlled); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 small Electric Drill Winches; Bobcat (up to and including 3/4 cu.yd.).
- Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

OPERATING ENGINEERS - FLOATING

- Class 1. Craft foreman (Master Mechanic), diver/wet tender, engineer (hydraulic dredge).
- Class 2. Crane/backhoe operator, mechanic/welder, assistant engineer (hydraulic dredge), leverman (hydraulic dredge), and diver tender.
- Class 3. Deck equipment operator (machineryman), maintenance of crane (over 50 ton capacity) or backhoe (96,000 pounds or more), tug/launch operator, loader, dozer and like equipment on barge, breakwater wall, slip/dock or scow, deck machinery, etc.
- Class 4. Deck equipment operator (machineryman/fireman), (4 equipment units or more) and crane maintenance 50 ton capacity and under or backhoe weighing 96,000 pounds or less, assistant tug operator. OPERATING ENGINEERS - HEAVY AND HIGHWAY CONSTRUCTION Class 1. Craft Foreman; Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted): Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Hammerhead, Linden, Peco & Machines of a like nature; Crete Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dowell machine with Air Compressor; Dredges; Field Mechanic-Welder; Formless Curb and Gutter Machine; Gradall and Machines of a like nature; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Mounted; Hoists, One, Two and Three Drum; Hydraulic Backhoes; Backhoes with shear attachments; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Roto Mill Grinder; Slip-Form Paver; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Trenching Machine; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole; Drills (Tunnel Shaft); Underground Boring and/or Mining Machines; Wheel Excavator; Widener (APSCO).
- Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (less than 1 cu. yd. Backhoe Bucket or over or with

attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Greaser Engineer; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; All Locomotives, Dinky; Pump Cretes; Squeeze Cretes-Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotory Snow Plows; Rototiller, Seaman, etc., self-propelled; Scoops - Tractor Drawn; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper; Scraper - Prime Mover in Tandem (Regardless of Size); Tank Car Heater; Tractors, Push, Pulling Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Fireman on Boilers; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper - Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Hydro-Blaster; Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Tractaire; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. Bobcats (all); Brick Forklifts; Oilers.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 618/993-7271 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape

plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

Mchenry County Prevailing Wage for May 2007

| Trade Name | RG | | С | Base | FRMAN | _ | | | | Pensn | Vac | Trng |
|---|----|------------|---|------------------|------------------|-----|-----|-----|----------------|----------------|-------|-------|
| ASBESTOS ABT-GEN | == | === ALL | - | 31.550 | 32.300 | | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| ASBESTOS ABT-MEC | | BLD | | 23.300 | 24.800 | | 1.5 | | 7.860 | | | 0.000 |
| BOILERMAKER | | BLD | | 38.540 | 42.000 | 2.0 | 2.0 | 2.0 | 6.720 | 7.440 | 0.000 | 0.300 |
| BRICK MASON | | BLD | | 34.850 | 38.340 | 1.5 | 1.5 | 2.0 | 7.050 | 7.870 | 0.000 | 0.380 |
| CARPENTER | | ALL | | 35.320 | 37.320 | 1.5 | 1.5 | 2.0 | 6.760 | 5.320 | 0.000 | 0.490 |
| CEMENT MASON | | ALL | | 35.300 | 37.300 | | 1.5 | 2.0 | 6.400 | 8.910 | 0.000 | 0.100 |
| CERAMIC TILE FNSHER | | BLD | | 28.520 | 0.000 | 2.0 | 1.5 | 2.0 | 5.650 | 5.750 | | 0.330 |
| COMMUNICATION TECH | | BLD | | 29.960 | 31.760 | 1.5 | 1.5 | 2.0 | | 6.290 | 0.000 | 0.375 |
| ELECTRIC PWR EQMT OP | | ALL | | 27.920 | 35.880 | | 1.5 | 2.0 | 4.750 | 7.820 | | 0.210 |
| ELECTRIC PWR GRNDMAN ELECTRIC PWR LINEMAN | | ALL | | 21.640 | 35.880 35.880 | | 1.5 | 2.0 | 4.750 | | 0.000 | 0.160 |
| ELECTRIC PWR LINEMAN ELECTRIC PWR TRK DRV | | ALL ALL | | 22.340 | 35.880 | | 1.5 | 2.0 | 4.750 | | | |
| ELECTRICIAN | | ALL | | 38.910 | 42.800 | | 1.5 | 2.0 | 9.140 | 8.940 | 0.000 | 0.480 |
| ELEVATOR CONSTRUCTOR | | BLD | | 42.045 | 47.300 | | 2.0 | 2.0 | | 6.060 | | 0.550 |
| FENCE ERECTOR | E | ALL | | 27.140 | 28.640 | | 1.5 | 2.0 | 7.500 | | 0.000 | |
| FENCE ERECTOR | S | ALL | | 34.100 | 35.810 | 2.0 | 2.0 | 2.0 | 7.690 | 13.11 | 0.000 | 0.230 |
| GLAZIER | | BLD | | 31.400 | 32.400 | 1.5 | 2.0 | 2.0 | 6.490 | 9.050 | 0.000 | 0.500 |
| HT/FROST INSULATOR | | BLD | | 33.300 | 35.050 | 1.5 | 1.5 | 2.0 | 7.860 | 8.610 | 0.000 | 0.310 |
| IRON WORKER | E | ALL | | 38.250 | 40.250 | | 2.0 | | 9.470 | | 0.000 | |
| IRON WORKER | S | ALL | | 34.100 | 35.810 | | 2.0 | 2.0 | 7.690 | | 0.000 | |
| IRON WORKER | W | ALL | | 30.760 | 32.300 | | 2.0 | 2.0 | 6.950 | 16.62 | | 0.550 |
| LABORER | | ALL | | 31.550 35.320 | 32.300 | | 1.5 | 2.0 | 7.200 | | 0.000 | 0.170 |
| LATHER MACHINIST | | BLD BLD | | 36.890 | 37.320 38.890 | 1.5 | 1.5 | 2.0 | 6.760 4.380 | 5.320 5.650 | | 0.490 |
| MARBLE FINISHERS | | ALL | | 25.750 | 0.000 | | 1.5 | 2.0 | | 7.020 | | 0.580 |
| MARBLE MASON | | BLD | | 34.850 | 38.340 | 1.5 | 1.5 | 2.0 | 7.050 | 7.870 | 0.000 | 0.490 |
| MATERIAL TESTER 1 | | ALL | | 21.550 | 0.000 | | 1.5 | | 7.460 | | 0.000 | |
| MATERIALS TESTER II | | ALL | | 26.550 | 0.000 | 1.5 | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| MILLWRIGHT | | ALL | | 35.320 | 37.320 | 1.5 | 1.5 | 2.0 | 6.760 | 5.320 | 0.000 | 0.490 |
| OPERATING ENGINEER | | BLD | 1 | 41.550 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | | 2 | 40.250 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | | 0.700 |
| OPERATING ENGINEER | | | 3 | 37.700 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | | 1.900 | |
| OPERATING ENGINEER | | | 4 | 35.950 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | | HWY | 2 | 39.750 39.200 | 43.750 43.750 | 1.5 | 1.5 | 2.0 | 6.850 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER OPERATING ENGINEER | | HWY HWY | | 37.150 | 43.750 | 1.5 | 1.5 | 2.0 | 6.850 | | 1.900 | 0.700 |
| OPERATING ENGINEER | | | | 35.750 | | | | | | | 1.900 | |
| OPERATING ENGINEER | | | | 34.550 | | | | | | | 1.900 | |
| ORNAMNTL IRON WORKER | E | ALL | _ | | 37.600 | | | | | | 0.000 | |
| ORNAMNTL IRON WORKER | | ALL | | | 35.810 | | | | | | 0.000 | |
| PAINTER | | ALL | | 35.330 | 36.330 | 1.5 | 1.5 | 1.5 | 6.400 | 6.500 | 0.000 | 0.500 |
| PAINTER SIGNS | | BLD | | | 32.520 | | | | | | 0.000 | |
| PILEDRIVER | | ALL | | | 37.320 | | | | | | 0.000 | |
| PIPEFITTER | | BLD | | | 39.600 | | | | | | 0.000 | |
| PLASTERER | | BLD | | | 35.350 | | | | | | 0.000 | |
| PLUMBER | | BLD | | | 39.500 35.650 | | | | | | 0.000 | |
| ROOFER SHEETMETAL WORKER | | BLD BLD | | | 38.510 | | | | | | 0.000 | |
| SIGN HANGER | | BLD | | | 27.570 | | | | | | 0.000 | |
| SPRINKLER FITTER | | BLD | | | 40.500 | | | | | | 0.000 | |
| STEEL ERECTOR | E | ALL | | | 37.750 | | | | | | 0.000 | |
| STEEL ERECTOR | S | ALL | | | 35.810 | | | | | | 0.000 | |
| STONE MASON | | BLD | | | 36.580 | | | | | | 0.000 | |
| TERRAZZO FINISHER | | BLD | | 29.290 | | | | | | | 0.000 | |
| TERRAZZO MASON | | BLD | | | 36.650 | | | | | | 0.000 | |
| TILE MASON | | BLD | | | 38.600 | | | | | | 0.000 | |
| TRAFFIC SAFETY WRKR | | HWY | 7 | | 24.400 | | | | | | 0.000 | |
| TRUCK DRIVER | | АЬЬ | Τ | 29.400 | ∠9.950 | 1.5 | 1.5 | ⊿.0 | 5.200 | 5.000 | 0.000 | 0.000 |

| TRUCK DRIVER | ALL 2 | 29.550 | 29.950 | 1.5 | 1.5 | 2.0 | 5.200 | 5.000 | 0.000 | 0.000 |
|--------------|-------|--------|--------|-----|-----|-----|-------|-------|-------|-------|
| TRUCK DRIVER | ALL 3 | 29.750 | 29.950 | 1.5 | 1.5 | 2.0 | 5.200 | 5.000 | 0.000 | 0.000 |
| TRUCK DRIVER | ALL 4 | 29.950 | 29.950 | 1.5 | 1.5 | 2.0 | 5.200 | 5.000 | 0.000 | 0.000 |
| TUCKPOINTER | BLD | 34.500 | 35.500 | 1.5 | 1.5 | 2.0 | 4.710 | 6.340 | 0.000 | 0.400 |

Legend:

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSA (Overtime is required for every hour worked on Saturday)

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

Explanations

MCHENRY COUNTY

FENCE ERECTOR (EAST) - That part of the county East and Northeast of a line following Route 31 North to Route 14, northwest to Route 47 north to the Wisconsin State Line.

IRONWORKERS (EAST) - That part of the county East of Rts. 47 and 14.

IRONWORKERS (SOUTH) - That part of the county South of Route 14 and East of Route 47.

IRONWORKERS (WEST) - That part of the county West of Route 47.

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial/Decoration Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, Christmas Day. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration such as the day after Thanksgiving for Veterans Day. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATIONS TECHNICIAN

Construction, installation, maintenance and removal of telecommunication facilities (voice, sound, data and video), telephone, security systems, fire alarm systems that are a component of a multiplex system and share a common cable, and data inside wire, interconnect, terminal equipment, central offices, PABX and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area network), LAN (local area networks), and ISDN (integrated system digital network), pulling of wire in raceways, but not the installation of raceways.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all mateiral that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installatin of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and experiors and customarily known as stone in the trade), carrara,

sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and experior which sare installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

TRAFFIC SAFETY - work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION
Class 1. Two or three Axle Trucks. A-frame Truck when used for
transportation purposes; Air Compressors and Welding Machines,
including those pulled by cars, pick-up trucks and tractors;
Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck
Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics
Helpers and Greasers; Oil Distributors 2-man operation; Pavement
Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors;
Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man
operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters;
Unskilled dumpman; and Truck Drivers hauling warning lights,
barricades, and portable toilets on the job site.

- Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yeards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.
- Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.
- Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

OPERATING ENGINEERS - BUILDING

Class 1. Mechanic; Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson attachment; Batch Plant; Benoto; Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader,

Elevating; Grouting Machines; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, one, two and three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes; Squeeze Cretes-screw Type Pumps; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-form Paver; Straddle Buggies; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Greaser Engineer; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, inside Freight Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (self-propelled); Rock Drill (truck mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination - Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators - (Rheostat Manual Controlled); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 small Electric Drill Winches; Bobcat (up to and including 3/4 cu.yd.).

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

OPERATING ENGINEERS - HEAVY AND HIGHWAY CONSTRUCTION Class 1. Craft Foreman; Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted): Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Hammerhead, Linden, Peco & Machines of a like nature; Crete Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dowell machine with Air Compressor; Dredges; Field Mechanic-Welder; Formless Curb and Gutter Machine; Gradall and Machines of a like nature; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Mounted; Hoists, One, Two and Three Drum; Hydraulic Backhoes; Backhoes with shear attachments; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Roto Mill Grinder; Slip-Form Paver; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Trenching Machine; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole; Drills (Tunnel Shaft); Underground Boring and/or Mining Machines; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common

Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Greaser Engineer; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; All Locomotives, Dinky; Pump Cretes; Squeeze Cretes-Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotory Snow Plows; Rototiller, Seaman, etc., self-propelled; Scoops - Tractor Drawn; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper; Scraper - Prime Mover in Tandem (Regardless of Size); Tank Car Heater; Tractors, Push, Pulling Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Fireman on Boilers; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper - Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Hydro-Blaster; Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Tractaire; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. Bobcats (all); Brick Forklifts; Oilers.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 618/993-7271 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing

classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

Will County Prevailing Wage for May 2007

| Trade Name | | | Base | FRMAN | | | | | Pensn | Vac | Trng |
|----------------------------------|------------|----|---------|------------------|-----|-----|-----|----------------|-------|-------|-------|
| ASBESTOS ABT-GEN | ALL | _ | | 32.300 | | 1.5 | | 7.460 | | 0.000 | 0.170 |
| ASBESTOS ABT-MEC | BLD | | | 24.800 | | | | 7.860 | | | |
| BOILERMAKER | BLD | | | 42.000 | | 2.0 | | 6.720 | | | |
| BRICK MASON | BLD | | | 38.340 | | 1.5 | | 7.050 | | | |
| CARPENTER | ALL | | | 39.650 | 1.5 | 1.5 | | 6.850 | | | |
| CEMENT MASON | ALL | | | 37.500 | | 2.0 | 2.0 | | 8.830 | | |
| CERAMIC TILE FNSHER | BLD | | 28.520 | 0.000 | | | | 5.650 | | | |
| COMMUNICATION TECH | BLD | | | | 1.5 | 1.5 | | 8.270 | | | |
| ELECTRIC PWR EQMT OP | ALL | | | | 1.5 | 1.5 | | 7.870 | | | |
| ELECTRIC PWR GRNDMAN | ALL | | | 42.000 | | 1.5 | | 6.140 | | | |
| ELECTRIC PWR LINEMAN | ALL | | | 42.000 | | 1.5 | | 7.870 | | | |
| ELECTRICIAN | BLD | | | 37.610 | | | | 7.920 | | | |
| ELEVATOR CONSTRUCTOR | BLD | | | 47.300 | | 2.0 | | 8.275 | | | 0.550 |
| GLAZIER | BLD | | | 32.400 | 1.5 | 2.0 | | 6.490 | | | 0.500 |
| HT/FROST INSULATOR | BLD | | | 35.050 | | 1.5 | | 7.860 | | | |
| IRON WORKER | ALL | | | 33.000 | | 2.0 | 2.0 | | 13.92 | | |
| LABORER | ALL | | | 32.300 | | 1.5 | | 7.460 | | 0.000 | |
| LATHER | ALL | | | | 1.5 | 1.5 | | 6.850 | | 0.000 | |
| MACHINIST | BLD | | | 38.890 | | 2.0 | | 4.380 | | | 0.000 |
| MARBLE FINISHERS | ALL | | 25.750 | 0.000 | | 1.5 | 2.0 | | 7.020 | | |
| MARBLE MASON | BLD | | | 38.340 | 1.5 | 1.5 | 2.0 | 7.050 | 7.870 | 0.000 | 0.490 |
| MATERIAL TESTER 1 | ALL | | 21.550 | | 1.5 | 1.5 | | 7.460 | | | |
| MATERIALS TESTER II | ALL | | 26.550 | 0.000 | 1.5 | 1.5 | 2.0 | 7.460 | 4.840 | 0.000 | 0.170 |
| MILLWRIGHT | ALL | | 36.050 | 39.650 | 1.5 | 1.5 | 2.0 | 6.850 | 9.810 | 0.000 | 0.490 |
| OPERATING ENGINEER | BLD | 1 | 41.550 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | BLD | 2 | 40.250 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | BLD | 3 | 37.700 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | BLD | 4 | 35.950 | 45.550 | 2.0 | 2.0 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | FLT | 1 | 47.250 | 47.250 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER | FLT | 2 | 45.750 | 47.250 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER | FLT | 3 | 40.700 | 47.250 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER | FLT | 4 | 33.850 | 47.250 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.000 |
| OPERATING ENGINEER | HWY | 1 | 39.750 | 43.750 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | HWY | 2 | 39.200 | 43.750 | 1.5 | 1.5 | 2.0 | 6.850 | 5.600 | 1.900 | 0.700 |
| OPERATING ENGINEER | HWY | 3 | 37.150 | 43.750 | 1.5 | 1.5 | 2.0 | | 5.600 | | 0.700 |
| OPERATING ENGINEER | | | 35.750 | | 1.5 | 1.5 | | 6.850 | | | 0.700 |
| OPERATING ENGINEER | | 5 | | 43.750 | | | 2.0 | | 5.600 | | |
| PAINTER | ALL | | | 38.700 | | | | 6.200 | | | |
| PAINTER SIGNS | BLD | | | 32.520 | | | | 2.600 | | | |
| PILEDRIVER | ALL | | | 39.650 | | | | 6.850 | | | |
| PIPEFITTER | BLD | | | 39.600 | | | | 8.660 | | | |
| PLASTERER | BLD | | | 35.350 | | | | 6.740 | | | |
| PLUMBER | BLD | | | 39.500 | | | | 7.050 | | | |
| ROOFER | BLD | | | 35.650 | | | | 6.460 | | | |
| SHEETMETAL WORKER | BLD | | | 38.510 | | | | 6.890 | | | |
| SPRINKLER FITTER | BLD | | | 40.500 | | | | 8.250 | | | |
| STONE MASON | BLD | | | 36.580 | | | | 6.450 | | | |
| TERRAZZO FINISHER TERRAZZO MASON | BLD | | 29.290 | | | | | 5.650 | | | |
| | BLD | | | 36.650 | | | | 5.650 | | | |
| TILE MASON TRAFFIC SAFETY WRKR | BLD HWY | | | 38.600 24.400 | | | | 5.650 3.078 | | | |
| TRUCK DRIVER | | 1 | | 33.590 | | | | 5.500 | | | |
| TRUCK DRIVER | | | | 33.590 | | | | 5.500 | | | |
| TRUCK DRIVER | | | | 33.590 | | | | 5.500 | | | |
| TRUCK DRIVER | | | | 33.590 | | | | 5.500 | | | |
| TUCKPOINTER | BLD | -1 | | 35.500 | | | | 4.710 | | | |
| TOCKEOTHIRK | עונים | | J-1.JUU | 33.300 | 1.5 | 1.5 | ∠.∪ | ±./10 | 0.540 | 0.000 | 0.400 |

M-F>8 (Overtime is required for any hour greater than 8 worked each day, Monday through Friday.

OSA (Overtime is required for every hour worked on Saturday)

OSH (Overtime is required for every hour worked on Sunday and Holidays)

H/W (Health & Welfare Insurance)

Pensn (Pension)

Vac (Vacation)

Trng (Training)

Explanations

WILL COUNTY

IRONWORKERS (SOUTH) - That part of the county South of a diagonal line through Braidwood and Goodenow.

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial/Decoration Day, Fourth of July, Labor Day, Veterans Day, Thanksgiving Day, Christmas Day. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration such as the day after Thanksgiving for Veterans Day. If in doubt, please check with IDOL.

EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation,

installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

COMMUNICATIONS TECHNICIAN

Installation, operation, inspection, maintenance, repair and service of radio, television, recording, voice, sound and vision production and reproduction, telephone and telephone interconnect, facsimile, equipment and appliances used for domestic, commercial, educational and entertainment purposes, pulling of wire through conduit but not the installation of conduit.

MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all mateiral that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installatin of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and experiors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and experior which sare installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

TRAFFIC SAFETY - work associated with barricades, horses and drums used to reduce lane usage on highway work, the installation and removal of temporary lane markings, and the installation and removal of temporary road signs.

TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION
Class 1. Two or three Axle Trucks. A-frame Truck when used for
transportation purposes; Air Compressors and Welding Machines,
including those pulled by cars, pick-up trucks and tractors;
Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck
Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics
Helpers and Greasers; Oil Distributors 2-man operation; Pavement
Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors;
Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man
operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters;
Unskilled dumpman; and Truck Drivers hauling warning lights,
barricades, and portable toilets on the job site.

- Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turnatrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yeards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.
- Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnatrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.
- Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

OPERATING ENGINEERS - BUILDING

- Class 1. Mechanic; Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson attachment; Batch Plant; Benoto; Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, one, two and three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes; Squeeze Cretes-screw Type Pumps; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-form Paver; Straddle Buggies; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.
- Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklist Trucks; Greaser Engineer; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, inside Freight Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (self-propelled); Rock Drill (truck mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller;

- Class 3. Air Compressor; Combination Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators (Rheostat Manual Controlled); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 small Electric Drill Winches; Bobcat (up to and including 3/4 cu.yd.).
- Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

OPERATING ENGINEERS - FLOATING

- Class 1. Craft foreman (Master Mechanic), diver/wet tender, engineer (hydraulic dredge).
- Class 2. Crane/backhoe operator, mechanic/welder, assistant engineer (hydraulic dredge), leverman (hydraulic dredge), and diver tender.
- Class 3. Deck equipment operator (machineryman), maintenance of crane (over 50 ton capacity) or backhoe (96,000 pounds or more), tug/launch operator, loader, dozer and like equipment on barge, breakwater wall, slip/dock or scow, deck machinery, etc.
- Class 4. Deck equipment operator (machineryman/fireman), (4 equipment units or more) and crane maintenance 50 ton capacity and under or backhoe weighing 96,000 pounds or less, assistant tug operator.

OPERATING ENGINEERS - HEAVY AND HIGHWAY CONSTRUCTION Class 1. Craft Foreman; Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines; ABG Paver; Backhoes with Caisson attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted): Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Hammerhead, Linden, Peco & Machines of a like nature; Crete Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dowell machine with Air Compressor; Dredges; Field Mechanic-Welder; Formless Curb and Gutter Machine; Gradall and Machines of a like nature; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Mounted; Hoists, One, Two and Three Drum; Hydraulic Backhoes; Backhoes with shear attachments; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Roto Mill Grinder; Slip-Form Paver; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Trenching Machine; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole; Drills (Tunnel Shaft); Underground Boring and/or Mining Machines; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu.

ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Greaser Engineer; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; All Locomotives, Dinky; Pump Cretes; Squeeze Cretes-Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotory Snow Plows; Rototiller, Seaman, etc., self-propelled; Scoops - Tractor Drawn; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper; Scraper - Prime Mover in Tandem (Regardless of Size); Tank Car Heater; Tractors, Push, Pulling Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Fireman on Boilers; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper - Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Hydro-Blaster; Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Tractaire; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. Bobcats (all); Brick Forklifts; Oilers.

TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 618/993-7271 for wage rates or clarifications.

LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the

classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.