

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		ST. CLAIR	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE

SIGN TAG	LOCATION	SQ. FT.	MESSAGE	* POST	SIGN DETAIL
#1	SEE SHEET 5	24	SEE SHEET 13	2	SEE SHEET 12
#2	SEE SHEET 5	24	SEE SHEET 14	2	SEE SHEET 12
#3	SEE SHEET 5	24	SEE SHEET 15	2	SEE SHEET 12
#4	SEE SHEET 5	24	SEE SHEET 16	2	SEE SHEET 12
#5	SEE SHEET 5	24	SEE SHEET 17	2	SEE SHEET 12
#6	SEE SHEET 5	24	SEE SHEET 18	2	SEE SHEET 12
TOTALS:		144		12*	

\* INCLUDED IN COST OF SIGN PANEL

AGGREGATE SCHEDULE

STATION	STATION	AGGREGATE BASE COURSE, TYPE A (CU YD)
100+00	100+25	1
134+05.94	135+75.31	13
TOTAL		14

EARTHWORK SCHEDULE

STATION	STATION	EARTH EXCAVATION 20200100 (CU YD)	FUNISHED EXCAVATION 20400800 (CU YD)	TOPSOIL FINISH & PLACE VARIABLE DEPTH (SQ. YD.) 21101600 (SQ. YD)
100+00	135+75.31	100	58	3734
TOTAL		100	58	3734

CULVERT SCHEDULE

STATION	PIPE CULVERT RCCP TYPE 1		P.R.C FLARED END SECTION		PIPE CULVERT REMOVAL (FOOT)
	12" (FOOT)	15" (FOOT)	12" (EACH)	15" (EACH)	
100+13.95		9		2	13
101+06.89		12		2	20
101+52.54		17		2	21
104+07.16		11		2	16
106+58.86	15		2		12
127+01.94		11		2	
134+98.69		5		2	12
TOTAL	15	65	2	12	94

SEEDING SCHEDULE

STATION	STATION	SEEDING CL 1 (ACRE)	NITROGEN FERT NUTR (POUND)	PHOSPHORUS FERT NUTR (POUND)	POTASSIUM FERT NUTR (POUND)	MULCH METH 1 (ACRE)
100+00	135+75.31	1.0	90	90	90	1.0
TOTAL		1.0	90	90	90	1.0

PARK BENCH SCHEDULE

LOCATION	NUMBER
115+40	1
122+34	1
130+86	1
TOTAL	3

DISTRICT PROJECT ENGINEER - LANCE KIDD

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  SCHEDULES  IDOT / IHPA JARROT MANSION STATE HISTORIC SITE
NAME	DATE	
SCALE: NTS		DRAWN BY: EJR
DATE: 2-26-07		CHECKED BY: GWW

...08110104-08-16 SCHEDULES.dgn 2/27/2007 2:07:50 AM User \*