

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	531 RS-1	COOK	34	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* FAU 2592 & FAP 305				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50	50				
40600300	AGGREGATE (PRIME COAT)	TON	225	225				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	40	40				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	755	755				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	490	490				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11105	11105				
42001300	PROTECTIVE COAT	SQ YD	850	850				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	110000	110000				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3820	3820				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2120	2120				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1520	1520				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	350	350				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	250	250				
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	30	30				
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	40	40				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	90	90				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	25	25				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	65	65				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11515	11515				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2060	2060				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41855	41855				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5795	5795				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	325	325				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1091	1091				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1461	1461				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11780	11780				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2060	2060				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	41855	41855				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5795	5795				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	325	325				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1091	1091				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1461	1461				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1910	1910				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1585	1585				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3966	3966				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	78	78				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4760	4760				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	150	150				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
HICKS RD. & US 14

4/24/2007 10:12:18 AM C:\PLOT\60620\60620.DWG