F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	42 RS	COOK	31	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60A86

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30					
40600300	AGGREGATE (PRIME COAT)	TON	142	142					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	718	718					
40600990	TEMPORARY RAMP	SQ YD	718	718					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	114	114					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7124	7124					
42001300	PROTECTIVE COAT	SQ YD	448	448					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	70577	70577					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1342	1342					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1081	1081					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	434	434					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	136	136					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	511	511					
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500					
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	19	19					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	65	65					
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	31	31					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11118	11118					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1165	1165					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28278	28278					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5772	5772					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	590	590					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1624	1624					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4470	4470					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1165	1165					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28278	28278					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5772	5772					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	590	590					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1624	1624					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	812	812					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	488	488					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2328	2328					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	188	188					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3054	3054					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	15	15					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. 30
SUMMARY OF QUANTITIES

PLOT DATE: 3/20/2007

3/20/2007
/Projects/60A086/design/qs.dgn