SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN 90% FED./10% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE: ROADWAY Sta. 789+00 to Sta. 950+84.47 I000-2A	WEBER Sta. 905+49.48 SFTY-2A	LIGHTING Sta. 789+00 to Sta. 950+84.47 Y031-1E	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6.5	6.5			
44000100	PAVEMENT REMOVAL	SQ YD	7,971	7,971			
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	69,770	69,770			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	27,574	27,574			
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	4,361	4,361			
44002228	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7"	SQ YD	35	35			
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	36,605	36,605			
44002600	GUTTER OUTLET REMOVAL	FOOT	60	60			
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	349	349			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2,268	2,268			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	349	349			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	559	559			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	83,336	83,336			
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	400		400		
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	3,334	3,334			
50102400	CONCRETE REMOVAL	CU YD	132.2		132.2	△1	
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3			
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	43.0		43.0		
50300225	CONCRETE STRUCTURES	CU YD	33.9		33.9	△1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25.4		25.4		
50300260	BRIDGE DECK GROOVING	SQ YD	598		598	△1	
50300300	PROTECTIVE COAT	SQ YD	3874	3,033	841	△1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6,280		6,280	△1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3			
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	1	1			
54247130	GRATING FOR CONCRETE FLARED END SECTIONS 24"	EACH	3	3			
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	1	1			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	2,053	2,053			
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	828	828			
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	273	273			
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	721	721			
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	677	677			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	604	604			

△1 Rev. 6-4-07 Rev.

PARSONS BRINCKERHOFF

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
143RD STREET TO WEBER ROAD

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 02-23-07
DRAWN BY AR
CHECKED BY SJV

FINAL