

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-3	WILL	305	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
	SOQ-02 OF 6			

CODE NO.	ITEM	UNIT	URBAN 90% FED. 10% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY Sta. 789+00 to Sta. 950+84.47 I000-2A	WEBER Sta. 905+49.48 SFTY-2A	LIGHTING Sta. 789+00 to Sta. 950+84.47 Y031-1E
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6.5	6.5		
44000100	PAVEMENT REMOVAL	SQ YD	7,971	7,971		
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	69,770	69,770		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	27,574	27,574		
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	4,361	4,361		
44002228	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7"	SQ YD	35	35		
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	36,605	36,605		
44002600	GUTTER OUTLET REMOVAL	FOOT	60	60		
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	349	349		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2,268	2,268		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	349	349		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	559	559		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	83,336	83,336		
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	400		400	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	3,334	3,334		
50102400	CONCRETE REMOVAL	CU YD	<del>88.0</del>		<del>88.0</del>	
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3		
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	43.0		43.0	
50300225	CONCRETE STRUCTURES	CU YD	<del>20.5</del>		<del>20.5</del>	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25.4		25.4	
50300260	BRIDGE DECK GROOVING	SQ YD	<del>513</del>		<del>513</del>	
50300300	PROTECTIVE COAT	SQ YD	3546	3,033	513	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4440		4440	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3		
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	1	1		
54247130	GRATING FOR CONCRETE FLARED END SECTIONS 24"	EACH	3	3		
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	1	1		
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	2,053	2,053		
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	828	828		
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	273	273		
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	721	721		
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	677	677		
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	604	604		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 55  
143RD STREET TO WEBER ROAD

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: 02-23-07

DRAWN BY AR  
CHECKED BY SJV



Rev.

FINAL