

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-3	WILL	305	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		SOQ-06 OF 6		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	WEBER	LIGHTING
				Sta. 789+00 to Sta. 950+84.47	Sta. 905+49.48	Sta. 789+00 to Sta. 950+84.47
				I000-2A	SFTY-2A	Y031-1E
* X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1			1
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	47	47		
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2		
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,867	1,867		
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SO YD	467	467		
X0484300	MEDIAN INLET BOX REMOVAL	EACH	9	9		
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	15,622	15,622		
X4066885	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	12,961	12,961		
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL, WITH TWO TYPE 20 FRAME AND GRATES	EACH	2	2		
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	400.0	400.0		
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	11,977	11,977		
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18		
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	18	18		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	360	360		
XX000582	WINGWALL REPAIR COMPLETE	L SUM	1	1		
XX001874	PERMANENT DITCH CHECKS	EACH	3	3		
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	8,207	8,207		
Z0001050	AGGREGATE SUBGRADE 12"	SO YD	56,385	56,385		
Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	1,318	1,318		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	27	27		
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	7	7		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	8	8		
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	8	8		
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	1	1		
0 Z0076600	TRAINEES	HOUR	4,000	4,000		
35501288	HOT-MIX ASPHALT BASE COURSE, 2 1/2"	SO YD	52,348	52,348		
X0325733	TEMPORARY ASPHALT WEDGE	SO YD	2,809	2,809		
X0325732	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	9	9		

@Y080
*SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
143RD STREET TO WEBER ROAD

SUMMARY OF QUANTITIES

SCALE: _____
DATE: 02-23-07

DRAWN BY AR
CHECKED BY SJV

FINAL