

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-3	WILL	305	127
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
RSCH 01 OF 02				

SHEET	STATION	OFFSET (FT)	CONCRETE HEADWALL REMOVAL (EACH)	REMOVAL (R)					ADJUST (ADJ)			STORM SEWER TO BE PLUGGED (CU YDS)	DRAIN. STRUCTURES TO BE CLEANED (C) (EACH)	STORM SEW./BOX CULVERT TO BE CLEANED (CLN) (FT)		
				CB (EACH)	MH (EACH)	PRC FES (EACH)	STORM SEWER				CB (EACH)				MH (EACH)	RECON MH (EACH)
							12"	15"	18"	24"						
DRU-01	795+50	120' R													24" 68	
DRU-01	801+75	CL	2									4.6				
DRU-02	809+40	CL							1							
DRU-02	809+60	CL														
DRU-02	809+70	CL														
DRU-02	809+75	CL														
DRU-02	809+75	CL														
DRU-02	809+75	100' R													2X3 140	
DRU-02	809+85	CL													2X3 60	
DRU-02	809+85	100' L													2X3 38	
DRU-03	821+60	CL														
DRU-03	821+70	CL														
DRU-03	821+75	CL														
DRU-03	821+75	CL L													2X2 75	
DRU-03	821+75	37' R													30" 60	
DRU-03	821+75	100' L													30" 38	
DRU-04	841+80	CL														
DRU-04	841+90	CL														
DRU-04	842+10	CL														
DRU-04	842+10	CL														
DRU-04	842+10	CL L													4X2 77	
DRU-04	842+10	CL R													24" 116	
DRU-04	842+10	100' R													4X2 62	
DRU-04	842+10	100' L													24" 88	
DRU-04	842+20	CL														
DRU-05	848+50	CL														
DRU-05	848+60	CL														
DRU-05	848+75	CL														
DRU-05	848+75	CL														
DRU-05	848+75	100' L													8X2 134	
DRU-05	848+75	100' R													8X2 43	
DRU-05	848+75	100' R													8X2 66	
DRU-07	880+15	CL													24" 136	
DRU-07	880+15	100' L													24" 40	
DRU-07	880+15	100' R													24" 56	
DRU-07	880+20	CL														
DRU-07	880+25	CL														
DRU-07	880+35	CL														
DRU-08	897+50	CL														
DRU-08	897+60	CL														
DRU-08	898+00	CL L													36" 153	
DRU-08	898+00	CL R													2X8 148	
DRU-08	898+00	100' L													36" 86	
DRU-08	898+00	220' R													2X4 178	
DRU-08	898+25	CL														
DRU-08	898+30	CL														
DRU-08	906+50	CL														
DRU-08	906+50	CL													24" 75	
DRU-09	907+65	CL														
DRU-09	909+00	CL													24" 240	
DRU-09	910+05	CL														
DRU-09	910+50	CL													24" 116	
DRU-09	911+25	CL														



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 143RD STREET TO WEBER ROAD

**DRAINAGE SCHEDULE -
 REMOVALS
 (1 OF 2)**

SCALE: 1" = 50'
 DATE: 02/23/2007

DRAWN BY: JPA
 CHECKED BY: TEH

FINAL